



THORNE &  
DERRICK  
INTERNATIONAL

Thorne & Derrick  
+44 (0) 191 410 4292  
[www.powerandcables.com](http://www.powerandcables.com)

# GENERAL CATALOGUE

LOW VOLTAGE POWER CONNECTION  
FOR INDUSTRIAL AND Ex APPLICATIONS



 **MARECHAL**  
ELECTRIC  
BEYOND CONNECTIONS

# MARECHAL ELECTRIC

THE GROUP, OUR TECHNOLOGY, STANDARDS, REFERENCING

**EVO**  
SEPARABLE  
SWITCH-DISCONNECTOR

**EVO40**

40 A



**DECONTACTOR™**  
& INDUSTRIAL SOCKET-OUTLET

**PNC**

16 A



**DSN**

20 A ➔ 63 A



**PN**

30 A



**PNHT**

30 A



**SINGLE POLE**  
POWER CONNECTORS

**CS**

250 A



**DSP400**

400 A



**CS1000**

500 A



**MULTICONTACT**  
CONNECTORS

**PN7C**

7 CONTACTS



**DS7C3/6**

7 CONTACTS



**DN9C**

9 CONTACTS



**MOBILE**  
APPLICATIONS

ELECTROMAGNETIC  
SELF-EJECTION



MECHANICAL  
SELF-EJECTING



JUNCTION AND DISTRIBUTION  
BOXES

DISTRIBUTION  
AND JUNCTION



CUSTOMISED  
SOLUTIONS



**CONNECTORS**

DECONTACTOR™ AND  
INDUSTRIAL SOCKET-OUTLET



SINGLE POLE



JUNCTION AND DISTRIBUTION  
BOXES

DISTRIBUTION  
AND JUNCTION



CONTROL



**LIGHTING**

LINEAR



FLOODLIGHT



**ACCESSORIES**  
AND SPARE PARTS

**DS**  
30 A ➡ 400 A**FC**  
50 A**DSHT**  
125 A**PFQ**  
400 A**PFC**  
600 A**SP**  
750 A**DSP1250**  
1250 A**PN12C**  
12 CONTACTS**DSN12C**  
12 CONTACTS**DN20C**  
20 CONTACTS**DSN24C**  
24 CONTACTS**DSN37C**  
37 CONTACTS

ANTI ENGINE START UP



DISTRIBUTION BOXES

SOLUTIONS  
FOR TUNNELS

MULTICONTACTS

BOXES  
AND CABINETS

SIGNAL



# THE MARECHAL ELECTRIC GROUP



## HISTORY

Founded in 1952, the MARECHAL ELECTRIC group was born to enhance electrical safety in industrial environments. Our main product DECONTACTOR and unique silver-nickel butt-contact technology offer a safe and innovative solution that allows break under load up to 250 A and reduces the risk of accidents. The group counts among the major players in **Low Voltage LT electrical connection systems** in industrial environments with or without the presence of an EX explosive atmosphere.

Its operational and/or sales subsidiaries in Europe, America, Asia, the Middle East, Africa and Australia, offer the best products and local services to the most demanding customers such as Technip, Total, Nestlé, Pepsi, Aramco, Sasol, SNCF, EDF, CEPSA, Actavis, Transnet, Arcelor, Universal Studios, Airbus, Boeing, McDonald's, Rio Tinto and BHP Billiton.

A workforce of nearly 500 worldwide includes R&D, manufacturing and commercial development skills. The product range is intended for all sectors of industrial activity where **safety** and **endurance** are required.

## MEANS

Since its inception, MARECHAL ELECTRIC Group's R&D has filed nearly 100 patents in more than 50 countries. The laboratory is approved by LCIE (Central Laboratory of Electrical Industries in France) Bureau Veritas for pre-testing and qualification of products. 5% of the turnover is invested every year in R&D to create, develop and adapt.

With a total surface area of almost 34,000 m<sup>2</sup>, 9 sites are dedicated to production, assembly, inspection and shipment: France (3), Germany, Italy, Singapore, Australia, South Africa and the United States.

MARECHAL ELECTRIC Group has a recognised expertise in the global industry, it actively participates in **standardization** work by providing the Secretariat for the technical committees SC 23H of the IEC - "Power sockets for industrial uses" and SC 31-2 of the CENELEC - "Explosion-proof "d" casing", as well as chairing the French UF 23H research committee.

MARECHAL® also participates in the work of **study committees** (IEC and CENELEC) such as TC64, TC18 and TC69.

Our sites are certified:

- ISO 9001 (France),
- DIN EN ISO 9001 (Germany),
- UL (QLHN.E145931 for power sockets/plugs and QLIW.E85952 for bases/connectors - United States).
- ATEX and IECEx (France, Italy)
- ISO 14001 (Italy).



MANUFACTURED  
IN FRANCE

# 70 years of expertise

## 2006

**SINGLE POLE  
POWER CONNECTORS**  
**SERIES SP**  
**SERIES SPEX**



## 2019

**SEPARABLE  
SWITCH-DISCONNECTOR**  
**EVO SERIES**



### MARKETS AND REFERENCES

MARECHAL® and TECHNOR® products are ideal for the most demanding users, installers, integrators (EPC, OEM, etc.) where safety, reliability and endurance are required. Each year, our teams provide advice, technical follow-up and design of customised solutions as part at sites projects or sites in more than 100 countries.

The offer is segmented by areas of activity and by types of site/project: NEW or RENOVATION, industrial or ATEX areas. In order to meet the requirements of the multiple configurations of electrical installations, more than 40,000 products references are supplied every year. MARECHAL ELECTRIC Group provides solutions for critical areas or processes of the industry where reliability, strength and safety are essential.

The main industries using our products are:

- the agri-food industry (safety),
- water treatment (reliability),
- chemicals and refineries (safety and reliability),
- heavy industry (strength),
- construction and building (strength and safety),
- energy (reliability),
- transport and airports (safety and reliability),
- entertainment and medias (safety),
- fire emergency services (safety and reliability),
- mines and quarries (safety and toughness),
- ports, marinas, offshore and shipyards (toughness and safety),
- tunnels (safety),
- towns and infrastructure (safety).

### MARECHAL®

Over the past 70 years, MARECHAL® has been the brand of low voltage electrical connectors designed, manufactured and controlled in France in strict compliance with the requirements of international standards (IEC and UL). Thanks to the butt-contact technology, the dozens of patents (filed in more than 50 countries) and the choice of the highly advanced materials, MARECHAL® connectors are the most reliable in the world. They guarantee the best safety for users and equipment in accordance with the requirements of the European Low Voltage Directive (LVD no. 2014/35/EU since April 20, 2016).

They are available for non-ATEX or ATEX environments (IECEx) Areas 1, 21, 2, 22:

- Separable switch disconnector (from 2 to 6 poles - 40 A).
- DECONTACTOR™ = plug + industrial switch (up to 250 A),
- multi-contact sockets (up to 37 contacts),
- industrial connectors (up to 600 A),
- single pole connectors (up to 1250 A with pilots),
- socket, distribution, break-out, junction, boxes.

### TECHNOR®

Part of the Marechal Group since 2013, this brand dedicated to ATEX/IECEx products has built its reputation over more than 30 years on exceptional product quality. All the products are designed, manufactured and tested in France and Italy.

A wide range of products conforming to the ATEX or/and IECEx standards:

- explosion-proof distribution and control boxes,
- explosion-proof cast aluminium, steel, stainless steel or GRP/thermoset,
- lighting (luminaires, spot lights with fluorescent or LEDS),
- stainless steel or GRP control and junction units,
- warning/indicator lights,
- earthing systems,

These products comply with European, international (IEC) and North American (UL, CSA) standards and regulations.



# ENERGY EFFICIENCY

## ENERGY EFFICIENCY AND SUSTAINABLE DEVELOPMENT

By choosing MARECHAL ELECTRIC, you select a technology that combines energy efficiency and sustainable development.

### REDUCE YOUR ENERGY CONSUMPTION

Industry requires energy. A running machine produces heat and therefore, energy. The optimisation of the energy consumption is key to reduce operation costs and enhance processes cost efficiency.

### LIMIT YOUR CARBON FOOTPRINT BY INVESTING IN LONG-LASTING SOLUTIONS

Sustainable development will not happen without sustainable products. MARECHAL ELECTRIC products have often been installed for more than 30 years in extreme environments such as offshore oil platforms, mines, docksides, water treatment sites and industrial sites in chemicals, food and beverage or aeronautics sectors.

## SAFETY & ENVIRONMENT CHARTER

MARECHAL ELECTRIC is committed to safety and the environment:

### 1. SAFETY FIRST AND FOREMOST

- Goal: 0 accident.
- To prevent potential risks related to our business.
- To raise awareness among employees to acquire and develop ecological reflexes.
- To promote well-being at work to establish a lasting trusting relationship with our employees.

### 2. RATIONAL AND REASONABLE USE OF RESOURCES TO REDUCE OUR FOOTPRINT

- To control our water, and energy.
- To encourage good practices for the environment.
- To reduce our paper printing.
- To sort our waste to facilitate recycling.
- To favour local distribution channels, as close as possible to our suppliers.

### 3. DESIGN FOR AN ENERGY-EFFICIENT PRODUCT

- To choose technical solutions and high-performance materials for a durable product.
- To propose spare parts to increase the lifespan of our products.
- To improve energy efficiency and reduce the users' energy consumption thanks to MARECHAL ELECTRIC butt-style contact technology.





# DECONTACTOR™, CONNECTIVITY TO REDUCE YOUR ENVIRONMENTAL FOOTPRINT

DECONTACTOR™, has been developed in response to a need to limit the heating of the contacts being an excellent compensation of the thermal cycle thanks to the butt-contact technology. The quality of the materials used and especially the silver-nickel tips on the end of our contacts guarantee little contact resistance and excellent environmental performances in extreme environments.

Investing in MARECHAL ELECTRIC's solutions is therefore the guarantee of a measurable return on investment at all stages of the life cycle of the products :

- **investment:** the DECONTACTOR™ is an industrial socket with an integrated switch, it is not a simple plug.
- **installation :** our 5A to 250A DECONTACTOR™ break under load, hence do not require a contactor-fed pilot.,,
- **use:** the DECONTACTOR™ with its silver-nickel butt-contact technology reduces heat dissipation compared with pins and sleeves solutions, generating less energy consumption,
- **maintenance:** spare parts are available for repairing damaged components, thus avoiding waste and pollution.

MARECHAL ELECTRIC products are internationally recognised for their durability which can reach more than 40 years.

## THE REPAIRABILITY INDEX



The Repairability Index\* aims to reduce obsolescence by providing information on whether a product is repairable or not at the time of purchase and thus extending its life and use. It is based on the following criteria:

availability of spare parts, availability of documentation, accessibility of after-sales service, ease of repair, price of spare parts.

\* Decree n°2020-1757 of 27 December 2020 (France).

## KEY FEATURES OF OUR DECONTACTOR™



Energy saving



Cost saving



Less cooling needed  
(in the data center case)



Less carbon  
foot print



Complementary saving  
dual voltage construction

SPARE PARTS CAN BE FOUND IN THE ACCESSORIES SECTION  
OF OUR CATALOGUE.  
PAGE 324





# APPLICABLE STANDARDS AND DIRECTIVES

## EUROPEAN REGULATION

Created in 1993, the European Union internal market is a single market where, among others, goods can circulate freely between the different countries of the Union. Furthermore, the safety and the protection of persons and of the environment is one of the main purposes of the European Regulation.

For this reason any manufacturer of potentially risky products for the end user has to affix the CE marking (meaning "European Conformity") previously to place the product on the single market complying with the requirements of the applicable European Regulation.

For the products intended to be used in potentially explosive atmospheres, the ATEX Directive 2014/34/UE is applicable.

For products intended for industrial purposes, the Low Voltage Directive (LVD) 2014/35/UE is applicable.

The ATEX and LVD directives require that a product complies with the essential safety requirements:

"Electrical equipment may be made available on the Union market only if, [...] it does not endanger the health and safety of persons [...] or property."

To reach this aim, the manufacturer can use the applicable harmonized European standards (EN standards) conferring a presumption of conformity of the product regarding the requirements of the applicable European Directive. Then the manufacturer can affix the CE marking on the product and place it on the single market.

In the case MARECHAL® devices would be associated with devices or spare parts other than from MARECHAL®, MARECHAL ELECTRIC S.A.S.'s responsibility cannot be engaged, and the CE marking is invalidated.

**ALL MARECHAL® appliances are consistent with the LVD and are manufactured within the framework of an ISO 9001 quality control system.**

Compliance with the French Labour Code, article R.4226-12, in accordance with the decree Royal Spanish 842/2002 REBT, ITC-BT-19, in conformity with the American standard NFPA70E

MINISTERIAL  
DECREE DATED  
20/12/2011

### Order relating to removable electrical devices and their conditions of connection and use.

This Order was published in the Official Journal on 27 January 2012. It stipulates:

Art. 6. - The joining or separation of the two parts of power sockets, extension cords and current connectors with a rating **higher than 32 amps**, must only be able to be performed off load.

**All MARECHAL® appliances comply with this order.**

## IEC/EN INTERNATIONAL STANDARDS

MARECHAL® devices comply with the following standards:

- IEC/EN 60309-1 :  
power outlets for industrial uses - Part 1: General rules
- IEC/EN 60309-4 :  
Power outlets for industrial uses - Part 4: Switched socket-outlets and connectors with or without interlock.

The break capacity of the MARECHAL® DECONTACTORTM is tested according to the following standard:

- IEC/EN 60947-3 : low voltage appliances - Part 3: Switches, disconnectors, switch-disconnectors and fuse-combination units.

For specific uses, the MARECHAL® appliances comply with the following standard:

- IEC/EN 61984 : connectors.

All MARECHAL products for ATEX comply with the following standard:

- IEC/EN 60079.

## UL/CSA AMERICAN STANDARDS

MARECHAL® devices comply with the following standards:

- UL 1682 (United States) and CSA C22.2 N° 182.1-07 (Canada) : power sockets and connectors.
- UL 2682 (United States) : power sockets with break capacity for motor connection.



## DEFINITIONS



### Ingress protection according to IEC/EN 60529

#### 1<sup>st</sup> digit: protection against solid foreign objects

- 2 = protection against dangerous live parts with a finger
- 4 = protection against dangerous live parts with a wire of a diameter superior or equal to 1mm
- 5 = protection against dust
- 6 = dustproof

#### 2<sup>nd</sup> digit: protection against ingress of water

- 4 = protection against water splashes
- 5 = protection against water jets
- 6 = protection against powerful water jets (fire hose)
- 7 = protection against a 30-minutes immersion up to 1m
- 8 = protection against a prolonged immersion for a determined period
- 9 = protection against high pressure water jets at high temperature



### Index of resistance to mechanical shocks according to IEC/EN 62262

- IK08 = withstands a shock of 1.7 kg to 30 cm (5 joules)
- IK09 = withstands a shock of 5 kg to 20 cm (10 joules)
- IK10 = withstands a shock of 5 kg to 40 cm (20 joules)



### Switching capacity according to IEC/EN 60947-3

- AC-21 = Resistive on load breaking (simple switchgear, lighting)
- AC-22 = Mix resistive and inductive on load breaking
- AC-23 = High inductive on load breaking (motor)
- AC-3 = Start And Switching Off - Squirrel Cage Motors



### Pilot and auxiliary

#### Pilot

A pilot circuit is meant to electrically control a switchgear that energizes/de-energizes a socket-outlet after plugging, and before unplugging an apparatus, to protect the operator.

This switchgear is controlled:

- by means of a microswitch located inside the socket-outlet (non-crossing pilot circuit), mechanically operated by the plug;
- by means of a contact or a pair of contacts, plug side and socket-outlet side (crossing pilot circuit), that make last and break first (LIFO: last-in/first-out), integrated in the control circuit.

#### Auxiliaries

Additional to the main contacts, auxiliary contacts are located plug side and socket-outlet side, and are intended for signal, communication, thermistor, etc...

## HAZARDOUS AREA CERTIFICATION



Certification according to European directive 2014/34/EU on all equipments used in or related to explosive atmospheres.



Complying with international standards for electrical and non-electrical equipment for use in potentially explosive atmosphere areas.

### Presence of potentially explosive atmosphere

#### Permanent

#### Occasional

#### Rare

Zoning for gas & vapours	Zone 0	Zone 1	Zone 2
Zoning for dust & fiber	Zone 20	Zone 21	Zone 22

Performance level of MARECHAL® devices.



# DECONTACTOR™ TECHNOLOGY




## DECONTACTOR™, A ONE OF A KIND DESIGN IN THE WORLD

The DECONTACTOR™ is a device which combines

- the advantages of a **power socket**,
- and the performance of a **switch**.

With 70 years of research and innovation, the DECONTACTOR™ range offers a level of reliability and safety not yet equalled anywhere in the world.

It allows devices to be connected and disconnected thousands of times and in the most severe environments in perfect **safety** for the user!




## BUTT CONTACT WITH A SILVER-NICKEL TIP

The MARECHAL® DECONTACTOR™ and connectors are all fitted **with butt contacts with silver-nickel tips**. They provide exceptional connection quality by eliminating the damage due to electric arcs and wear seen with pin and sleeve sockets. Silver is an excellent conductor of current even when oxidized. Conductivity is optimal even in the presence of vibration and temperature variation thanks to the **pressure of the springs**.

## CRIMPED BRAIDS

The MARECHAL® contact uses a **crimped braid with a spring** which provides contact performance and tolerances superior to pin and sleeve contacts. The flexibility of the braid and the spring allows the base contact tip to always be perfectly aligned with the plug contact tip. These contacts, which are silver and anti-corrosion treated, **offer very good corrosion resistance**.



## ELASTIC LOCK TERMINALS

MARECHAL® contacts are fitted with «elastic lock» connection terminals. The wire clamp is split and surrounded by an elliptical deforming ring. This method allows the tightening force on the wire to be constant. Hence despite the creep of the conductor, the variations of temperature and vibration, the conductor wire is perfectly connected to the contact terminal.



## SAFETY SHUTTER

DECONTACTOR™ sockets are fitted with an interlocked safety shutter which prevents access to live contacts. This shutter only unlocks at the time of connection of the plug into the socket which avoids any risk of electric shock.

## CASING MADE FROM ADVANCED MATERIALS

MARECHAL® range connectors and DECONTACTOR™ have casings made from **glass fibre reinforced polyester GRP**, or **metal** depending on the models. This choice of material contributes to the excellent mechanical performance and **longevity** of the socket.



## MARECHAL® TECHNOLOGY

## ADVANTAGES

### DECONTACTOR™,

Socket-outlet with integrated switch up to 250A



Saves you from buying and installing a contactor or wiring pilots. Guarantees disconnection on load.

Safety shutter



No access to the live parts of the socket-outlet.

Breaking capacity AC-22/AC-23



Local disconnection possible, fast maintenance or repair, reduction of downtimes.

Padlocking facility



Prevents unintentional connections and disconnections while keeping the operator safe from any hazard.

Automatic IP66/IP67/IP69 ingress protection, once the socket-outlet lid is shut or once the inlet has mated with the socket-outlet



Resistance to high pressure cleaning up to +80°C.

ATEX/IECEx



Disconnection and padlocking are possible in hazardous areas. This simplifies maintenance in hazardous locations.

T<sub>amb</sub> -40 °C/+60 °C



Materials resist harsh weather conditions.

Dual voltage 230 V/400 V



A 5-pole socket-outlet can be mated with 2-pole, 3-pole, 4-pole and 5-pole inlet plugs.

GRP IK09  
Metal IK09/IK10



Materials with high mechanical endurances.

Butt contact with silver-nickel plated tip



Better conductivity.  
No corrosion, unlike copper or brass contacts.  
Low resistance = lower current consumption.

Further certification schemes and bodies:  
LCIE, VDE, UL, CSA, BV Marine, EAC...



No hassle exporting your machines all over the world.

Up to 24 keying positions



Identify and secure dedicated circuits.

Auxiliaries  
Pilots



Signal & control transmission.  
Electrical Interlocking.

## ECONOMY OF INSTALLATION: DUAL-VOLTAGE

With a single socket-outlet base (e.g.: 3 PNE - 230/400 V) it is possible to accommodate 3 different plugs:

- a 3 PNE - 400 V plug,
- a 3 PE - 400 V plug,
- a 1 PNE - 230 V.

This compatibility provides real savings on the installation of these sockets for the user.

400 V plug - 3P+E



230 V plug - 1P+N+E

400 V plug - 3P+N+E



230/400 V socket-outlet  
3P+N+E



Industrial-domestic  
adapter with 1P+N+E /  
230 V - 10/16 A domestic  
socket



# DECONTACTOR™ TECHNOLOGY

## DESIGNED FOR EFFICIENCY AND SAFETY

The quality of the material, the design, the assembly and the inspection of each component are at the core of our know-how and the MARECHAL® technology.

They each provide a precise function that optimizes the **performance, safety** and **sustainability** of our sockets and your installations.




- |   |  |
|---|--|
| <b>1</b> Gasket colour confirms voltage rating: <b>as per standards</b>                       | <b>6</b> Silver-nickel contacts: <b>excellent electrical conductivity and performance</b>              |
| <b>2</b> Load break release button:<br><b>The plug ejects when acting on the latch</b>        | <b>7</b> Integral cable gland with adaptable range-take and cable anchoring: <b>up to IP69</b>         |
| <b>3</b> Arc chamber  | <b>8</b> Central earth contact:<br><b>no danger of mis-wiring</b>                                      |
| <b>4</b> Automatic watertightness: <b>up to IP69</b>  | <b>9</b> Silver-plated contacts:<br><b>anti-corrosion treatment</b>                                    |
| <b>5</b> Safety shutter prevents unwanted access to contacts: <b>user safety (IP4X/IPXXD)</b> | <b>10</b> Glass fibre reinforced polyester (GRP) or metal casing: <b>excellent mechanical strength</b> |
| <b>11</b> Spring-loaded terminals: <b>resistance to vibration and copper creep</b>            |  |



## MARECHAL MODULARITY

Socket-outlet	Inclined socket	Wall mounting socket	Coupler socket	Plug	Appliance inlet	Wall mounting appliance inlet	Inclined appliance inlet
Active part	Socket-outlet	Socket-outlet	Socket-outlet	Socket-outlet	Appliance inlet	Appliance inlet	Appliance inlet
Mounting accessories	/	Inclined sleeve	Wall box	Handles	Handles	/	Wall box Inclined sleeve

## IEC 60309-1 NORM TERMINOLOGY






# DECONTACTOR™ TECHNOLOGY

## 24 POSSIBILITIES FOR VOLTAGE/FREQUENCY INTERLOCKING

The interlock device is associated with coding positions on the electrical connectors. It enables 24 different positions that are distinguished by voltage/frequency. This is achieved by machining the relevant 'notch' on the coding ring. The colours in the rows of the table below correspond to the international voltage standard. These are the colours of the rings and labels on the bases and connectors.



Keying  
exemple




Inlet  
interior

Keying positions				Keying positions			
20-24 V AC	AC	2P, 2P+N 3P, 3+N	08	220-250 V	AC	1P+N+E	01
20-24 V AC	AC 60 Hz	2P, 2P+N 3P, 3+N	UL 02	220-250 V 380-440 V	AC	2P+N+E, 3P+N+E	01
25-28 V	AC	2P, 2P+N 3P, 3+N	06	220-250 V	AC 60 Hz	2P+E, 3P+E	UL 07
40-48 V	AC	2P, 2P+N 3P, 3+N	13	220-250 V	DC	2P+E	20
110-125 V	AC 60 Hz	1P+N+E	UL 07	255-277 V	AC 60 Hz	1P+N+E	UL 04
110-125 V 220-250 V	AC 60 Hz	2P+N+E, 3P+N+E	UL 07	255-277 V 440-480 V	AC 60 Hz	2P+N+E, 3P+N+E	UL 04
110-130 V	AC	1P+N+E	03	347 V	AC 60 Hz	1P+N+E	UL 14
110-130 V 190-230 V	AC	2P+N+E, 3P+N+E	03	347 V 600 V	AC 60 Hz	2P+N+E, 3P+N+E	UL 14
110-130 V	DC	2P+E	10	380-400 V 660-690 V	AC	2P+N+E, 3P+N+E	19
115-127 V	AC 200 Hz	1P+N+E	12	380-440 V	AC	2P+E, 3P+E	01
115-127 V 200-220 V	AC 200 Hz	2P+N+E, 3P+N+E	12	380-440 V	AC	1P+N+E	19
115-127 V	AC 400 Hz	1P+N+E	11	440-480 V	AC 60 Hz	2P+E, 3P+E	UL 04
115-127 V 200-220 V	AC 400 Hz	2P+N+E, 3P+N+E	11	480-500 V	AC	2P+E, 3P+E	09
120-127 V	AC 60 Hz	1P+N+E	16	600 V	AC 60 Hz	2P+E, 3P+E	UL 14
120-127 V 208-220 V	AC 60 Hz	2P+N+E, 3P+N+E	16	660-690 V	AC	2P+E, 3P+E	19
190-230 V	AC	2P+E, 3P+E	03	1000 V	AC	1P+N+E, 2P+E, 2P+N+E, 2P+N+E, 3P+E, 3P+N+E	22
200-220 V	AC 200 Hz	2P+E, 3P+E	12	AC = 50/60 Hz			
200-220 V	AC 400 Hz	2P+E, 3P+E	11				
208-220 V	AC 60 Hz	2P+E, 3P+E	UL 16				



## DECONTACTOR™

socket outlet + integrated switch



## ALTERNATIVE SOLUTION

Industrial socket with external switch

63 A product (identical scale)




## DECONTACTOR™

### ADVANTAGES

- Ease of installation : no pilot conductor or upstream contactor.
- No compulsory switch required, even beyond 32 A.
- More compact.
- Cable extension possibility.

### COMPARATIVE HEATING CURVE




- Thanks to their low internal resistance, our DECONTACTOR have a long time constant: they slowly reach the equilibrium temperature and can withstand temporary overcurrent with no excessive heating.
- Electrical appliances which comply with IEC 60309-2 will reach critical temperature much quicker in case of overcurrent.



# EVO TECHNOLOGY

A DUAL FUNCTION FOR A SINGLE PRODUCT



SWITCH



THE FIRST  
SEPARABLE SWITCH-  
DISCONNECTOR



DISCONNECTOR

EVO

CLEAR BREAKING AND SEPARABILITY FOR 100% VISUAL ISOLATION

IP66/IP67/IP69 WATERPROOFING IN THE ON AND OFF POSITIONS

COMPACT DESIGN

STANDARD PADLOCKING

ELECTRICAL ENDURANCE > 15 000 CYCLES





## SEPARABLE SWITCH-DISCONNECTOR

Cage terminals improving conductivity  
and vibration resistance

Double break  
AC-22A/AC-23A (18,5 kW)  
AC-3 (11 kW)

Colour Coded terminals  
1, 2, 3, 4/N, 5, 6


Ergonomic handle  
Screwless fixings

IP4X safety shutter  
Protection from live parts

Contacts on silver alloy tips  
(anti-corrosion treatment)

Glass reinforced poly  
enclosure

IP66/IP67/IP69 automatic waterproofing  
in ON and OFF positions



# STANDARDS AND TECHNOLOGY

In some environments, the occurrence of potentially explosive atmospheres may result from the presence of combustible gases, vapors, aerosols, or dusts.  
In case of ignition, the effects can be destructive (devastating) for both workers and facilities.

## KNOW ITS ATMOSPHERE

In the workplace, explosive atmospheres may occur due to the presence of:


- gases and vapors: fuels for heating or drying installations, storage of combustible gases, vapors of flammable solvents stored or handled ;
- combustible dusts likely to form explosive clouds within the air during routine operations (loading or unloading of powdery products, dust removal from filters...) such as flour, sugar, wood dusts, cereal dusts, metal dusts...

### From potentially explosive atmosphere to explosion

An explosion results from:

- a mixture of air (oxidizing),
- combustible substances in sufficient proportions (flammable substance),
- an ignition source: high temperature, electrical arcing, static electricity, lightning, flames,
- and finally ideal atmospheric conditions (pressure, temperatures, etc...).

This is how we refer to the explosion triangle.



### Identification of Substances

The danger of an explosive atmosphere depends on its concentration of flammable substances, but also on the characteristics of these substances. It is necessary to divide these substances according to two classifications of hazardous properties:

1. gas groups and dust groups,
2. self-ignition temperature (temperature classes for gases).

The lower the energy it is necessary to ignite a substance, the more dangerous the substance is said to be.

### GAS GROUP SUBDIVISIONS

DANGEROUSNESS		
	Propane	IIA
	Ethylene	IIB
	Acetylene	IIC
	Hydrogen	

Group IIB classified devices are suitable for applications requiring Group IIA devices. Similarly, group IIC classified devices are suitable for applications requiring Group IIA or Group IIB devices.

### DUST GROUP SUBDIVISIONS

Combustible particles suspended in the air	IIIA
Non-conductive dust	IIIB
Conductive dust	IIIC

Group IIIB classified devices are suitable for applications requiring Group IIA devices. Similarly, group IIIC classified devices are suitable for applications requiring Group IIIA or Group IIIB devices.

The lower the ignition temperature, the more dangerous the substance is. Therefore, equipment are classified from T1 to T6 according to the **maximum surface temperature** (or temperature of the hottest point depending on the type of protection).

Equipment classified T6 is suitable for an atmosphere with an ignition temperature of T5, T4, T3, T2 or T1.

Note: the ignition temperature of a gas is not related to its danger. Even though hydrogen is an extremely explosive gas (necessary energy to ignite hydrogen atmosphere is about 10 times less than a natural gas atmosphere), it is T1 classified as its self-ignition temperature is very high (560 °C).

MAXIMUM SURFACE TEMPERATURE		EXAMPLES OF IGNITION TEMPERATURES		
TEMPERATURE CLASS	MAXIMUM VALUE °C	FLAMMABLE SUBSTANCES	IGNITION TEMPERATURE	
T1	450 °C	Gaz/Vapeur	Hydrogène 560 °C (T1)	
T2	300 °C		Méthane 537 °C (T1)	
T3	200 °C		Ethylène 425 °C (T2)	
T4	135 °C		Acétylène 305 °C (T2)	
T5	100 °C		Kérosène 210 °C (T3)	
T6	85 °C		Ether 175 °C (T4)	
		Disulphite de Carbone 95 °C (T6)		
		Fibre de papier 570 °C (T1)		
		Aluminium 560 °C (T1)		
		Poussières/fibres	Blé 510 °C (T1)	
			Bois 500 °C (T1)	
			Sucre 490 °C (T1)	
		Polyéthylène 440 °C (T1)		

## IDENTIFY ITS ZONES

HAZARDOUS AREAS			
ATEX	Certification according the European Directive 2014/34/EU related potentially explosive atmospheres		
IECEx	Certification according international standards related to equipment used in hazardous areas		
Presence of potentially explosive atmosphere	Permanent	Occasional	Rare
Zoning applicable to gas and vapors	Zone 0	Zone 1	Zone 2
Choice of equipment protection level	Ga	Ga - Gb	Ga - Gb - Gc
Zoning applicable to dusts and fibers	Zone 20	Zone 21	Zone 22
Choice of equipment protection level	Da	Da - Db	Da - Db - Dc

MARECHAL® offer.

# STANDARDS AND TECHNOLOGY

## AVOID IGNITION

Products intended to operate in potentially explosive atmosphere must :

- **Prevent the formation of an arc** likely to cause an explosion or contain inflammation,
- **Resist shocks**, to a higher degree than usually is required for normal industrial products,
- **Not to be likely to accumulate electrostatic charges that may generate a spark**,
- **Have a maximum temperature below the self-ignition temperature of the surrounding atmosphere.**

From the design of the equipment, it is necessary to consider the type(s) of protection adapted to the equipment intended to be installed in potentially explosive atmospheres by acting on one of the following actions:

- **deletion of the potentially explosive atmosphere**
- **deletion of the source of ignition**,
- **non-propagation of ignition**.

The design and verification rules for these types of protection are regulated by international standards and the devices are identified by letters (see table).

ACTION	DESCRIPTION OF TYPE OF PROTECTION	APPLICABLE STANDARD	IDENTIFICATION	APPLICATION
			Ex pxb	
	Pressurized enclosure: a protective gas maintains a pressure higher than the one of the external atmosphere.	EN/IEC 60079-2	Ex pyb	Zone 1, Zone 21
			Ex pzc	Zone 2, Zone 22
DELETION OF THE POTENTIALLY EXPLOSIVE ATMOSPHERE	Restricted breathing enclosure: in normal operation, to restrict the entry of gases, vapours and mists	EN/IEC 60079-15	Ex nR	Zone 2
	Liquid immersion : explosive gas atmosphere which may be above the liquid or outside the enclosure cannot be ignited	EN/IEC 60079-6	Ex ob	Zone 1
			Ex oc	Zone 2
			Ex ma	Zone 0, Zone 20
	Encapsulated: hazardous parts completely enclosed in a resin	EN/IEC 60079-18	Ex mb	Zone 1, Zone 21
			Ex mc	Zone 2, Zone 22
	Hermetically-sealed device: in normal operation, device which cannot be opened and is sealed	EN/IEC 60079-15	Ex nC	Zone 2
			Ex ta	Zone 20
	Dust ignition protection by enclosure: limitation of dusts ingress (IP5X or IP6X)	EN/IEC 60079-31		Zone 21
			Ex tc	Zone 22

<b>ACTION</b>	<b>DESCRIPTION OF TYPE OF PROTECTION</b>	<b>APPLICABLE STANDARD</b>	<b>IDENTIFICATION</b>	<b>APPLICATION</b>
	Increased safety: measures to prevent excessive temperature and occurrence of arcs or sparks	EN/IEC 60079-7	Ex eb	Zone 1
			Ex ec	Zone 2
			Ex ia	Zone 0, Zone 20
	Intrinsically safe: limitation of electrical energy at a level below that which may cause ignition	EN/IEC 60079-11	Ex ib	Zone 1, Zone 21
			Ex ic	Zone 2, Zone 22
	Non-incendive component: in normal operation, component having contacts for making or breaking a specified circuit in which the mechanism is constructed so that the component is not capable of causing ignition	EN/IEC 60079-15	Ex nC	Zone 2
<b>DELETION OF THE SOURCE OF IGNITION</b>			Ex da	Zone 0
	Flameproof enclosure: the ignition can occur inside the enclosure but can be transmitted to the external atmosphere.	EN/IEC 60079-1	Ex db	Zone 1
			Ex dc	Zone 2
<b>NON-PROPAGATION OF IGNITION</b>	Powder filling: the parts capable of igniting an explosive gas atmosphere completely surrounded by filling material (example glass beads)	EN/IEC 60079-5	Ex q	Zone 1

Other types of protection exist: Protection of equipment and transmission systems using optical radiation (op pr, op is,...), ventilated rooms (v).... Non-electrical equipment can also create potential sources of ignition and to address this problem, there are types of protection for these devices

# STANDARDS AND TECHNOLOGY

## FOCUS ON MAIN TYPES OF PROTECTION

### Flameproof enclosure: Ex da, db or dc

Flameproof equipment is an enclosure in which devices/components capable of igniting an explosive gas atmosphere are enclosed.


Flameproof enclosures must:

- contain an internal explosion without casing deformation (withstand of explosion pressure),
- ensure that ignition is not transmitted to the surrounding atmosphere,
- have an external temperature lower than the self-ignition temperature of the atmosphere.



The construction parameters for flameproof equipment depending on the gas group for which the equipment is intended, are essential in order to meet all three criteria:

- type of flamepath : thread, flat surface, sealed path, cylindrical,...
- the length of flamepath,
- the space between the 2 surfaces of the flamepath (=gap),
- thickness of walls.



Example of an explosion-proof enclosure with a flat flame passage.

### Increased safety: Ex eb or ec

Increased safety equipment must, by design and with a high level of safety, provide the possibility of excessive temperature and occurrence of arcs or sparks during normal operation or under specified abnormal conditions.

In difference to flameproof enclosure, all devices or components installed in the increased safety enclosure must, in advance, be ATEX/IECEx certified for the appropriate application (or assessed with the enclosure) and must also be listed in the certificate.



These enclosures must be at least IP54. The electrical parameters are defined by the temperature rise and the clearances and creepage distances, which are different than the ones defined in industrial standards. The quality of the connection is essential in the protection of the increased safety equipment.

MARECHAL sockets are equipped with elastic connections terminals with thread protection tabs, in order to prevent the deterioration of the threads and to ensure a uniform pressure on the strands (heating control).




Terminals for connecting to a MARECHAL® Ex socket.

#### **Combinaison: Ex db eb/db eb mb**

To design safe equipment that can be installed in a potentially explosive atmosphere, it is essential to apply the most appropriate type of protection. The DECONTACTOR™ combines several modes of protection.

Example of an ATEX and IECEx certified DECONTACTOR™

Ex II 2 G D Ex db eb IIC T6 ou T5 Gb  
Ex tb IIIC T70 °C ou T90 °C Db



# ITEM REFERENCING

1000101  
1000101  
1011010  
1011010

## 7 DIGITS FOR BASIC PRODUCTS + 3 DIGITS FOR SPECIALS PRODUCTS

Main option combination suffixes page 317.

1<sup>ST</sup> DIGIT

2<sup>ND</sup> DIGIT

3<sup>RD</sup> DIGIT

PRODUCT LINE	CASING	RATING
0 = PN - PNC	IEC : 1 = BLUE POLY	16 A E = PNC
1 = DN	5 = BLACK POLY	30 A N/2 = PN
2 = DX - DXN - DXA	9 = METAL	20 A 8 [ ] = DN
3 = DS		30 A 1 [ ]
4 = PF - SP - CS- SPeX	UL : 3 = BLUE POLY	50 A 3 [ ] = DS/DX
5 = ACCESSORIES	7 = METAL	90 A 6 [ ]
6 = DSN	6 = BLACK METAL	30 A 1 [ ]
8 = EVO		50 A 3 [ ]
9 = BOXES		90 A 6 [ ]
		150 A 9 [ ]
		250 A 2 [ ]
		400 A 4 [ ]
		20 A 1 [ ] = DSN/DXN/DXA
		32 A 3 [ ]
		63 A 6 [ ]
		315 A 3 [ ] = PFQ
		400 A 4 [ ]
		500 A 5 [ ] = PFC
		600 A 6 [ ]
		40 A 4 = EVO
		500 A 3 = CS1000
		680 A 4 = SPeX
		750 A 4 = SP

1101001  
0000101  
1011010  
1101011

**OUR CONFIGURATOR IS AVAILABLE ON OUR WEBSITE**  
[marechal.com/configurator](http://marechal.com/configurator)



**4<sup>TH</sup> DIGIT**

**5<sup>TH</sup> & 6<sup>TH</sup> DIGIT**

**7<sup>TH</sup> DIGIT**

<b>TYPE</b>	<b>VOLTAGE</b>			<b>POLARITY</b>
<b>Male</b>				<b>Alternative current (AC)</b>
<b>1</b> = Plug (with handle)	08 =	20-24 V	AC	<b>5</b> = 1P+N+E
<b>6</b> = Wall mounting appliance inlet (with box)	06 =	25-28 V	AC	<b>3</b> = 3P+E
<b>8</b> = Appliance inlet (male) semi-recessed	13 =	40-48 V	AC	<b>4</b> = 4P+E (EVO)
<b>9</b> = Inclined appliance inlet (with sleeve)	03 =	110-130/190-230 V	AC	<b>7</b> = 3P+N+E
	01 =	220-250/380-440 V	AC	<b>D</b> = 1P+N
	09 =	480-500 V	AC	<b>A</b> = 2P (L1, L2)
	19 =	400/690 V	AC	<b>E</b> = 2P (L1, L3)
	22 =	1 000 V	AC	<b>G</b> = 2P+N
<b>Female</b>				<b>B</b> = 3P
<b>0</b> = Wall mounting socket (with box)	02 =	20-24 V	60 Hz	<b>C</b> = 3P+N
<b>3</b> = Coupler socket (with handle)	16 =	120-208 V	60 Hz	<b>L</b> = 2P+2P
<b>7</b> = Inclined socket (with sleeve)	07 =	110-125/220-250 V	60 Hz	<b>H</b> = 1P+E
<b>4</b> = Socket-outlet (female) semi-recessed	04 =	255-277/440-480 V	60 Hz	<b>Z</b> = 2P+E
	14 =	347-600 V	60 Hz	<b>6</b> = 2P+N+E
	12 =	115-127/200-220 V	200 Hz	<b>6</b> = 6P+E (EVO)
	11 =	115-127/200-220 V	400 Hz	<b>M</b> = 2P+2P+E
				<b>Direct current (DC)</b>
	10 =	110-130 V	DC	<b>8</b> = 2P+E Double breaking point
	20 =	220-250 V	DC	<b>9</b> = 2P+E
	03 =	220-250 V	AC	<b>J</b> = 3P (-/+/0 V)
	01 =	380-480 V	AC	<b>K</b> = 3P+E (-/+/0 V/T)
	05 =	500-690 V	AC	<b>N</b> = 2P+2P
	Other voltages and frequencies are available on request, see table page 14.			<b>P</b> = 2P+2P+E
				<b>Z</b> = 2P

## MAIN FEATURES

40 A

# EVO SEPARABLE SWITCH-DISCONNECTOR

## KEY FEATURES

Up to 6 poles + earth

Smooth sleek design, no visible fastening screws

Surface mounting dimension restricted to 120 mm

IP4X on supply side

IP66/IP67/IP69 tightness in ON and OFF positions when supply and load parts are connected, including when separated using plug caps

Visible and distinctly obvious breaking

Maneuvering speed independent of the operator's applied force

Padlockable in OFF position

## A UNIQUE PRODUCT

**EV040** is a manually operated separable switch-disconnector, with configurations from 2 to 6 poles + Earth.

Certified by LCIE BUREAU VERITAS to IEC/EN 60947-1 and 60947-3 standards. EV040 allows for frequent making and breaking on load, while ensuring safe isolation of any low voltage electrical circuit: resistive (AC-21A), mixed resistive/inductive (AC-22A) or inductive (AC-23A). EV040 also allows for on load making & breaking of all electric motors (AC-3), as per IEC/EN 60943-3 standard requirements.

Equipped with self-cleaning silver alloy contact tips and a unique and patented **mechanism**, our new technological concept combines the functionalities of a switch and an isolator.

The design facilitates successive double breaking pole by pole, which ensures optimal safety during any maintenance operation.

Once the supply and load parts have been separated, a safety shutter prevents any risk of electric shock (IP4X/IPXXD). The **robust mechanism** allows **distinctly and visibly separated** disconnection and separation even in the event of overload currents.

Thanks to the compact design, **EV040** can be configured to be panel-mounted or flush-mounted on a wall box with varying angles. Other standard features include: **padlockable** accessory, hidden screws, and a smooth, crevice-free design.

The quality of **EV040** materials offers flexibility in the most demanding of applications in terms of hygiene, robustness and reliability (IP66/IP67/IP69 and IK09): Halogen-free; UL94-Standard compliant self-extinguishing materials; resistant to hot vapours (tropicalisation as per IEC 60068-2) as well as UVs (class f1), corrosion and chemical agents.

## EVO FACILITATES THE COMPLIANCE OF:

- electrical machinery to the "Machinery" European Directive on isolating device, and to standards EN 12100 and EN 60204-1,
- electrical installations to installation standards: IEC/HD 60364 and NF C 15-100 (French) or other national transposition.

### EVO is certified by LCIE BUREAU VERITAS to standard :

- EC/EN 60947-1/-3 : Low-voltage switchgear and controlgear - Part 3: Switches, disconnectors, switch-disconnectors and fuse-combination units.



## OUR CERTIFICATIONS


EVO is a switch-disconnector with visible and fully apparent breaking. As such, it is not subject to the obligation of a 30 mA residual current device (RCD).

EVO allows:


- continuity of service: no unwanted tripping, no production loss;
- space saving and cost reduction;

- securing and simplifying interventions: for maintenance or replacement of an equipment, EVO can be separated in two parts, by means of a tool, and padlocked. When separated, EVO has an IP4X/IPXXD rating. It is therefore not necessary to use authorized personnel or protection procedures.

### STANDARD INSTALLATION



### EVO40 SOLUTION



## MAIN FEATURES

40 A


# EVO SEPARABLE SWITCH-DISCONNECTOR

## LOAD BREAK ROTARY SWITCH

- Simple operation
- Automatic IP in ON and OFF positions



SEPARATED POSITION



POSITION 00



POSITION OFF




POSITION ON





## POSSIBLE INSTALLATIONS

- Inclined sleeve or wall box
- Inclined sleeve on box
- Straight sleeve under box
- Coupler




# 6 POLES

18,5 kW

690 V

**U MAX**

## SEPARABLE SWITCH-DISCONNECTOR EVO40



IP66  
IP67/IP69



2,5-10 mm<sup>2</sup> <sup>(1)</sup>  
2,5-16 mm<sup>2</sup> <sup>(2)</sup>



GRP



IK09



-25 °C  
+60 °C



See table



60947-1/-3

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).



A padlock key is provided with each source

### SWITCHING CAPACITY


kW/V	230 V	400 V	690 V
AC-21A/AC-22A	40 A	40 A	40 A
AC-23A	11 kW	18,5 kW	18,5 kW
AC-3	7,5 kW	11 kW	11 kW

### OTHER FEATURES

Electrical Load cycles	15 000 cycles*
$U_i$ : Rated insulation voltage	1 000 V AC
$U_{max}$ : Operational voltage	690 V
$I_{the}$ : Conventional enclosed thermal current	40 A
$U_{imp}$ : Rated impulse withstand voltage	8 kV
$I_{cc}$ : Rated short-circuit breaking current capacity with gG fuses and aM fuse	100 kA
$I_{cm}$ : Rated short-circuit making current capacity	1 kA

\* In AC-23A 690 V AC/40A service operation.

# REFERENCES



Voltage	Poles	Supply	Load	Straight sleeve	70° inclined sleeve	Handle <sup>(1)</sup>	90° wall box <sup>(2)</sup>
200-250 V AC	2P+E	8144032	8148032				
	3P+E	8144033	8148033				
	4P+E	8144034	8148034	51LM0	51LM7	51LP0D21	51LC9000
	6P+E	8144036	8148036				
380-480 V AC	2P+E	8144012	8148012				
	3P+E	8144013	8148013				
	4P+E	8144014	8148014	51LM0	51LM7	51LP0D21	51LC9000
	6P+E	8144016	8148016				
500-690 V AC	2P+E	8144052	8148052				
	3P+E	8144053	8148053				
	4P+E	8144054	8148054	51LM0	51LM7	51LP0D21	51LC9000
	6P+E	8144056	8148056				
Umax 690 V AC	2P+E	8144122	8148122				
	3P+E	8144123	8148123				
	4P+E	8144124	8148124	51LM0	51LM7	51LP0D21	51LC9000
	6P+E	8144126	8148126				
Load side cap IP66/IP67 padlockable		Included	814A426G				

(1) Gland size 5-21 mm.

(2) Without drilling, top entry. Reversible wall box for 50° angle with bottom entry.



## ADDITIONAL PADLOCKING KEYS



Packaging = 10

814A541

## SAFETY HASP FOR UP TO 6 PADLOCKS



613A541

## PRODUCT WITH ANTI-BACTERIAL TREATMENT

NEW


This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on antibacterial treated handles please consult us.



# DRAWINGS AND DIMENSIONS


Dimensions are in millimeters.

**STRAIGHT SLEEVE**




A	B	C	E1	E2
209	256	94	52	45

**INCLINED SLEEVE 70°**




**ON FLEXIBLE CABLE**



A	B	C	D	E1	E2
127	286	110	128	95	100


A	B
279	81

REVERSIBLE WALL BOX 50° AND 90°



A1	A2	B1	B2	C	D	E1	E2
236	118	236	301	110	120	95	74

MANCHON 70° SUR BOITIER B2



A	B	C	E1	E2
220	305	178	157	145,5



# DECONTACTOR™ & INDUSTRIAL SOCKET-OUTLET

MODEL	CURRENT	U MAX AC	MAX NB OF CONTACTS	MAX NUMBER OF AUX./PIL.	DECONTACTOR™ (BREAK: AC)
PNC	16A	480 V	4+E	/	/
DSN1	20A	500 V	4+E	2 PIL.	AC-22/AC-23
PN	30A	500 V	4+E	/	/
PNHT	30A	500 V	4+E	/	/
DS1	30A	690 V	4+E	2 AUX.	AC-22/AC-23
DSN3	32A	690 V	4+E	2 AUX.	AC-22/AC-23
DS3	50A	1 000 V	4+E	4 AUX.	AC-22/AC-23
FC	50A	500 V	4+E	/	/
DSN6	63A	1 000 V	4+E	4 AUX.	AC-22/AC-23
DS6	90A	1 000 V	4+E	4 AUX.	AC-22/AC-23
DSHT	125A	440 V	4+E	2 AUX.	/
DS9	150A	1 000 V	4+E	6 AUX.	AC-22/AC-23
DS2	250A	1 000 V	4+E	6 AUX.	AC-22/AC-23
DS2	350A	1 000 V	4+E	2 PIL.	/
DS4	400A	1 000 V	3+E	2 PIL.	/
PFQ4	400A	690 V	4+E	6 AUX. + 2 PIL.	/
PFC6	600A	1 000 V	4+E	2 AUX. + 2 PIL.	/

Other currents, voltages, frequencies and contacts configurations are available (see page 14).

DOWNLOAD ALL TECHNICAL SHEETS ON OUR  
WEBSITE **MARECHAL.COM**

## SELECTION GUIDE

DECONTACTOR™  
& INDUSTRIAL  
SOCKET-OUTLETS

MATERIAL	IP	EMC	IK	PAGE
POLY	IP66/IP67/IP69	/	IK08	40
POLY	IP66/IP67/IP69	/	IK09	42
POLY/METAL	IP66/IP67	Yes (metal)	IK09	46
METAL	IP44	/	IK09	50
POLY	IP55	/	IK09	52
POLY	IP66/IP67/IP69	/	IK09	56
POLY	IP55	/	IK09	60
POLY	IP54	/	IK09	64
POLY	IP66/IP67/IP69	/	IK09	66
POLY/METAL	IP66/IP67	Yes (metal)	IK09	70/74
METAL	IP44	/	IK09	78
POLY/METAL	IP66/IP67/IP69	Yes (metal)	IK09/IK10	80/84
METAL	IP66/IP67	Yes	IK10	88
METAL	IP66/IP67	Yes	IK10	92
METAL	IP66/IP67	Yes	IK10	96
METAL	IP66/IP67	/	IK10	102
METAL	IP66/IP67	/	IK10	106

## MAIN FEATURES

16 A

### PNC CONNECTORS

IP66/IP67/IP69

GRP casing

30 A

### PN INDUSTRIAL PLUG AND SOCKET-OUTLET

IP66/IP67

GRP or metal casing

50 A

### FC FLAT CONNECTORS

IP54

GRP casing

For flat cables



#### PNC CONNECTORS FACILITATE THE COMPLIANCE OF ELECTRICAL INSTALLATION TO:

- the national regulations relating to the improvement of safety and health of workers at work in France, Italy, Spain, Belgium,
- the installation standards IEC/HD 60364 and NF C 15-100.

#### PNC connectors comply with :

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation,
- the IEC/EN 61984, IEC/EN 60529, IEC/EN 62262 standards.



#### PN PLUGS AND SOCKET- OUTLETS FACILITATE THE COMPLIANCE OF:

- electrical machinery to the Machinery European Directive regarding isolation device,
- the national regulations relating to the improvement of safety and health of workers at work in France, Italy, Spain, Belgium,
- the installation standards IEC/HD 60364 and NF C 15-100.

#### PN plugs and socket-outlets comply with :

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation,
- the IEC/EN 60309-1, IEC/EN 60309-4 standards (essential requirements) ; UL 1682 (USA) and CSA C22.2 N°182.1-07 (Canada) standards.



#### FC FLAT CONNECTORS FACILITATE THE COMPLIANCE OF ELECTRICAL INSTALLATION TO:

- the national regulations relating to the improvement of safety and health of workers at work in France, Italy, Spain, Belgium,
- the installation standards IEC/HD 60364 and NF C 15-100.

#### FC flat connectors comply with :

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation,
- the IEC/EN 61984, IEC/EN 60529, IEC/EN 62262 standards.

**20A ➔ 63A**

## **DSN DECONTACTOR™**

IP66/IP67/IP69

GRP casing

Breaking capacity AC-22 and AC-23

Up to 4 auxiliaries



**30A ➔ 250A**

## **DS DECONTACTOR™**

IP54/55 (IP66/IP67 from 90 A)

GRP casing up to 150 A

Metal casing from 90 A to 250 A

Breaking capacity AC-22 and AC-23



### **DECONTACTOR™ DSN AND DS FACILITATE THE COMPLIANCE OF:**

- electrical machinery to the Machinery European Directive,
- electrical installation to French decree of 30 aout 2010 and 22 septembre 2010 relating to health and safety at work when using electrical installations,
- electrical installation to national regulation relating to the improvementof the safety and health of workers at work in Italy, Spain, Belgium,
- electrical installation to IEC/HD 603064, NF C 15-100 and NFPA70 standards.

### **DSN and DS DECONTACTOR™ comply with :**

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation,
- IEC/EN 60309-1, IEC/EN 60309-4, IEC/EN 60947-3 (dealing with the load breaking capacities AC-22 and AC-23) standards,
- UL 1682, UL 2682 (USA), CSA C22.2 N° 182.1-07 (Canada) standards,
- BV Marine specifications (DSN series, DS9, DS2).

## **OUR CERTIFICATIONS**



France and  
International  
Europe



Germany



USA and  
North  
America



Canada



Australia



Russia  
and Eurasia



Marine



Military  
(Mil-S-901D)



China

## MAIN FEATURES

30 A

### PNHT HIGH TEMPERATURE PLUG AND SOCKET-OUTLET

High-temperature environment up to 240 °C  
Metal casing



#### PNHT PLUGS AND SOCKET-OUTLETS FACILITATE THE COMPLIANCE TO:

- electrical machinery to the Machinery European Directive regarding isolation device,
- electrical installation to national regulation relating to the improvement of the safety and health of workers at work in Italy, Spain, Belgium,
- electrical installation to IEC/HD 603064 and NF C 15-100 standards.

#### PNHT plugs and socket-outlets comply with:

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation.

125 A NEW

### DSHT HIGH TEMPERATURE PLUG AND SOCKET-OUTLET

High-temperature environment up to 150 °C  
Metal casing



#### DSHT PLUGS AND SOCKET-OUTLETS FACILITATE THE COMPLIANCE OF:

- electrical machinery to the Machinery European Directive regarding isolation device,
- electrical installation to French decree of August 30, 2010 and September 22, 2010 relating to health and safety at work when using electrical installations,
- electrical installation to national regulation relating to the improvement of the safety and health of workers at work in Italy, Spain, Belgium,
- electrical installation to IEC/HD 603064 and NF C 15-100 standards.

#### DSHT plugs and socket-outlets comply with:

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation.

**350 A >> 400 A**

## **DS INDUSTRIAL PLUGS AND SOCKET-OUTLETS**

IP66/IP67

Metal casing



### **DS PLUGS AND SOCKET-OUTLETS FACILITATE THE COMPLIANCE TO:**

- electrical machinery to the Machinery European Directive regarding isolation device,
- electrical installation to IEC/HD 603064 and NF C 15-100 standards.

#### **DS plugs and socket-outlets comply with:**

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation.

**400 A >> 600 A**

## **PF INDUSTRIAL PLUGS AND SOCKET-OUTLETS**

IP66/IP67

Plug and socket-outlet casing in painted aluminium and box in stainless steel AISI 316L



### **PF PLUGS AND SOCKET-OUTLETS FACILITATE THE COMPLIANCE ELECTRICAL INSTALLATIONS TO:**

- electrical installation to French decree of 30 aout 2010 and 22 septembre 2010 relating to health and safety at work when using electrical installations,
- electrical installation to IEC/HD 603064 and NF C 15-100 standards.

#### **PF plugs and socket-outlets comply with:**

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation.
- UL 1682 (USA) and CSA C22.2 N° 182.1-07 (Canada) standards.

## **OUR CERTIFICATIONS**



USA and North  
America



Canada



Russia  
and Eurasia




Military  
(Mil-S-901D)

# 16 A

480 V  
U MAX

## CONNECTOR PNC



IP66  
IP67  
IP69



0,75 mm<sup>2</sup>  
2,5 mm<sup>2</sup>



GRP



IK08



-40 °C  
+100 °C

### OTHER FEATURES

Permitted current range 4-20 mA/16 A

Impulse withstand voltage 5 kV

Contact resistance <2 mΩ

Polarity 4P+E

Casing/insulator Glass reinforced thermoplastics UL94 V-0

Vibrations Frequency range 5-1000 Hz, 1 g (1h 30 on each critical frequency)  
according to IEC/EN 60068-2-6

Load cycles > 2000 cycles

IP (socket-outlet with cap) IP66/IP67/IP69

IP66/IP67

IP (connected plug) IP68 test at 10m deep during 15 days  
(contact us for these references)  
IP69

Salt mist 50 000 hours

## REFERENCES AND ACCESSORIES

**SOCKET-OUTLET**

female  
(with M25 lock nut)  
**PNC**



**INLET** male  
(with M25 lock nut)  
**PNC**



480 V AC

4+E

01E4007

01E8007

**COUPLER**  
socket female  
**PNC**



**PLUG**  
male  
**PNC**



480 V AC

4+E


01E3007

01E1007

Cable diameter 11-15 mm (smaller diameter available according to specification).

ACCESSORIES	Reference	HANDLE	Input/Cable outer Ø	Reference
<b>INLET CAP</b>				
	Socket-outlet cap Inlet cap	01EA125 01EA126		M20
<b>ADAPTER PLATE FOR DSN1 OR DXN1 ACCESSORIES</b>				
	251A457-E		5-12 mm	9PEM20POLY+J
<b>STRAIGHT SLEEVE</b>				
	01EA127		3-9 mm	9PEM20RNPOL+J

## DRAWINGS AND DIMENSIONS



A

165

B

45

C

45

# 20 A

500 V  
U MAX

## DECONTACTOR™ DSN1



IP66  
IP67  
IP69



1-2,5 mm<sup>2</sup> <sup>(1)</sup>  
1,5-4 mm<sup>2</sup> <sup>(2)</sup>



GRP



IK09



-40 °C  
+60 °C



AC-22  
AC-23



60309-1  
60309-4  
60947-3



2 PIL. <sup>(3)</sup>

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).  
(3) Flexible wiring 0.8 mm<sup>2</sup>.



Other configurations  
on request

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 and IEC/EN 60309-4 standards 20 A/500 V

Load-break capability according to IEC/EN 60947-3/AC-22 20 A/500 V

Load-break capability according to IEC/EN 60947-3/AC-23 20 A/500 V

Short-circuit current Icc 10 kA

Power kW AC-22/AC-23 10 kW



For a black colour  
housing replace the  
second reference  
character with 5.

Dual-voltage  
socket-outlet  
(see p. 11)

**SOCKET-OUTLET**  
female  
**DSN1**



**INLET** male  
**DSN1**



20-24 V AC	2P	611408A	611808A
220-250 V AC	1P+N+E	6114015	6118015
380-440 V AC	3P+E	6114013	6118013
220-250 V AC   380-440 V AC	3P+N+E	6114017	6118017
480-500 V AC	3P+E	6114093	6118093
480-500 V AC	3P+N+E	6114097	6118097
Pilotes 2 A/250 V AC	+ 2 pilotes*	Ref. + 972	NA

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

\* Unlike the rest of the DSN range, DSN1 auxiliaries are located on the female side only and are shunted. Electrical continuity is only ensured when the inlet and the socket-outlet are connected and when the pilot circuit is closed.


OPTIONS	Reference
<b>INDUSTRIAL/DOMESTIC ADAPTERS</b>	
Industrial inlet MARECHAL® 1P+N+E and domestic socket-outlet 10/16 A 230 V fuse protection 10 A and 16 A (with integrated fuse). All these plug adapters are available to local standards: replace D11 by D40 for UK, D30 for Germany/Netherlands/Luxembourg, D06 for Italy.	
	6118015D11
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	613A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	611A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	611A346
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Socket-outlet ref.+R
<b>SELF-EJECTING</b>	
	See page 192
<b>PRODUCTS AVAILABLE IN BLACK ●</b>	
The black dot means these products are also available in black color. Replace the second character of the product reference with 5	
<b>PRODUCT WITH ANTI-BACTERIAL TREATMENT ● NEW</b>	
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.	

BOXES	 x°	Input	Reference
<b>POLY BOX ●</b>			
	30°	M20	511B3M20
	30°	M25	511B3M25
<b>POLY BOX + POLY SLEEVE (BLACK VERSION SEE ACCESSORIES DXN1 PAGE 239)</b>			
	70°	Without hole	511C7000
	70°	Hole Ø 20	511C7M20
Earth bar ref.: 51AA089	70°	Hole Ø 25	511C7M25
	70°	Hole Ø 32	511C7M32
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M20	511C3M20
Cable glands are not delivered with the boxes.			
HANDLE	Input/ Cable outer Ø	Reference	Self-ejection
<b>POLY HANDLE WITH GLAND ● ●</b>			
	9-18 mm	511P0D18	/
	5-21 mm	511P0D21	/
	60° 9-18 mm	511P6D18	/
<b>POLY HANDLE + POLY CABLE GLAND ● ●</b>			
	5-12 mm	511P020P	Ref. +443 (10-14 mm)
	9-18 mm	511P025P	Ref. +443 (12-18 mm)
	14-25 mm	511P032P	Ref. +443
<b>POLY HANDLE (WITHOUT CABLE GLAND) ●</b>			
	M20	511P0M20	/
	M25	511P0M25	/
	M32	511P0M32	/

SLEEVE	 x°	Reference
<b>POLY SLEEVE ●</b>		
	30°	511M3
	70°	511M7
<b>METAL SLEEVE</b>		
	0° (Straight)	591M0
	30°	591M3


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
147	134	58	42

COUPLER




A	B
231	89

PLUG ON 30° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
196	180	68	90	36/56	78

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
200	244	138	126	117	106

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
177	175	77	108	64	95


A	B	C	D	E
131	244	126	126	95



# 30 A

500 V  
U MAX

## INDUSTRIAL PLUG PN



IP66  
IP67



1-6 mm<sup>2</sup><sup>(1)</sup>  
1,5-10 mm<sup>2</sup><sup>(2)</sup>



GRP  
METAL



IK09



-40 °C  
+60 °C



EMC  
METAL

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).



Other configurations  
on request

GRP devices are not  
compatible with metal  
devices.



For a black colour  
GRP housing replace  
the second reference  
character with 5.

Dual-voltage  
socket-outlet  
(see p. 11)



**SOCKET-OUTLET**  
female  
**PN**



**INLET** male  
**PN**



20-24 V AC	2P	01N408A	01N808A
220-250 V AC	1P+N+E	01N4015	01N8015
380-440 V AC	3P+E	01N4013	01N8013
220-250 V AC   380-440 V AC	3P+N+E	01N4017	01N8017
480-500 V AC	3P+E	01N4093	01N8093
480-500 V AC	3P+N+E	01N4097	01N8097

► Other currents, voltages, frequencies and contact configurations are available (see page 14).



**SOCKET-OUTLET**  
female  
**PN**



**INLET** male  
**PN**



20-24 V AC	2P	09N408A	09N808A
220-250 V AC	1P+N+E	09N4015	09N8015
380-440 V AC	3P+E	09N4013	09N8013
220-250 V AC   380-440 V AC	3P+N+E	09N4017	09N8017
480-500 V AC	3P+E	09N4093	09N8093
480-500 V AC	3P+N+E	09N4097	09N8097


► Other currents, voltages, frequencies and contact configurations are available (see page 14).

OPTIONS	Reference		
<b>INDUSTRIAL/DOMESTIC ADAPTERS</b>			
Industrial inlet MARECHAL® 1P+N+E and domestic socket-outlet 10/16 A 230 V fuse protection 10A and 16A (with integrated fuse). All these plug adapters are available to local standards: replace D11 by D40 for UK, D30 for Germany/Netherlands/Luxembourg, D06 for Italy.			
	01N8015D11		
<b>LOCKING FOR 1 PADLOCK Ø 4 mm (WITHOUT SHAFT)</b>			
	Ref. + 843		
<b>SCREW LOCKING IMPRINT BTR 2,5</b>			
	Ref. socket + 22		
<b>REVERSED INTERIOR AND CONTACTS</b>			
	The connector is supplied with a rubber inlet cap. Ref. conn. + 001 Ref. socket + 001		
<b>IP55 SOCKET-OUTLET SELF-CLOSING LID</b>			
	Replace N by S Ex: 400 V 3P+N+E poly = 01S4017		
<b>INLET CAP IP66/IP67</b>			
	01NA426		
<b>180° OPENING LID</b>			
	Ref. socket +10		
<b>SELF CLOSING/SELF RETURNING LID</b>			
	Socket-outlet ref.+R		
<b>180° OPENING + SELF-RETURNING LID</b>			
	Ref. socket +18		
<b>ELECTROMAGNETIC COMPATIBILITY (EMC) ● NEW</b>			
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.		
<b>PRODUCTS AVAILABLE IN BLACK ●</b>			
The black dot means these products are also available in black color. Replace the second character of the product reference with 5			
<b>PRODUCT WITH ANTI-BACTERIAL TREATMENT ● NEW</b>			
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.			
SLEEVE	$\Delta x^\circ$	Ref.	EMC Option
<b>POLY SLEEVE ●</b>			
	30°	511M3	/
	70°	511M7	/
<b>METAL SLEEVE ●</b>			
	0° (Straight)	591M0	Ref. +EMC
	30°	591M3	Ref. +EMC
	45°	591M4	Ref. +EMC

BOXES	$\Delta x^\circ$	Input	Ref.
<b>POLY BOX</b>			
	0° (Straight)	M20	511B0M20
	0° (Straight)	M25	511B0M25
	30°	M20	511B3M20
	30°	M25	511B3M25
<b>METAL BOX (+ EARTHING WIRE) ●</b>			
	0° (Straight)	M20	591B0M20
	0° (Straight)	M25	591B0M25
<b>POLY BOX + POLY SLEEVE</b>			
	70°	Without hole	511C7000
	70°	Hole Ø 20	511C7M20
Earth bar ref. : 51AA089	70°	Hole Ø 25	511C7M25
	70°	Hole Ø 32	511C7M32
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE ●</b>			
	30°	M20	511C3M20
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE ●</b>			
	45°	M20	591C4M20
	45°	M25	591C4M25
	45°	M32	591C4M32
Table of cable glands on page 318.			
HANDLE	Input/Cable outer Ø	Ref.	
<b>POLY HANDLE WITH GLAND ● ●</b>			
	9-18 mm	511P0D18	
	5-21 mm	511P0D21	
	60°	9-18 mm	511P6D18
<b>POLY HANDLE + POLY CABLE GLAND ● ●</b>			
	5-12 mm	511P020P	
	9-18 mm	511P025P	
	14-25 mm	511P032P	
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>			
	7-13 mm	591P020M	
	8-16 mm	591P025M	
	16-24 mm	591P032M	
<b>POLY HANDLE (PE PAGE 318) ●</b>			
	M20	511P0M20	
	M25	511P0M25	
	M32	511P0M32	
<b>METAL HANDLE METRIC THREAD ENTRY (PE PAGE 318) ● ●</b>			
	M20	591P0M20	
	M25	591P0M25	
	M32	591P0M32	


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




	A	B	C	E
<b>Straight handle</b>	127	140	58	42
<b>Angled handle</b>	117	138	61	42

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




	A	B	C	D	E1	E2
<b>Straight handle</b>	178	176	68	90	36/56	78
<b>Angled handle</b>	153	176	68	90	36/56	78

## PLUG ON 30° INCLINED SOCKET-OUTLET



	A	B	C	D	E1	E2
<b>Straight handle</b>	160	170	77	108	64	95
<b>Angled handle</b>	133	165	77	108	64	95

## COUPLER



	A	B	C
<b>Straight handle</b>	208	132	58

# 30 A

500 V  
U MAX

## HIGH-TEMPERATURE PLUG PNHT

240 °C



IP44



1.6 mm<sup>2</sup>  
1,5-10 mm<sup>2</sup>



METAL



IK09



Self-closing lid as a standard

### OTHER FEATURES

Flexible wiring (min.-max.)

1-6 mm<sup>2</sup>

Stranded wiring (min.-max.)

1,5-10 mm<sup>2</sup>



**SOCKET-OUTLET**  
female  
**PNHT**



**INLET** male  
**PNHT**



20-24 V AC	2P	092408A185	092808A185
220-250 V AC	1P+N+E	0924015185	0928015185
380-440 V AC	3P+E	0924013185	0928013185
220-250 V AC	3P+N+E	0924017185	0928017185

BOXES		Input	Reference
<b>METAL BOX (+ EARTHING WIRE)</b>			
	0° [Straight]	M20	571B0M20185
	0° [Straight]	M25	571B0M25185
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	45°	M20	571C4M20185
	45°	M25	571C4M25185
	45°	M32	571C4M32185


Cable glands are not delivered with the boxes.

SLEEVE		Reference
<b>METAL SLEEVE</b>		
	45°	571M4185

HANDLE		Input/ Cable outer Ø	Reference
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>			
		8-13 mm	571P020M185
		12-20 mm	571P025M185
		18-28 mm	571P032M185
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
		M25	571P0M25185
		M32	571P0M32185


## DRAWINGS AND DIMENSIONS

SOCKET ON STRAIGHT WALL BOX



A	B	C	E1	E2
121	80	79	64	24

PLUG



A	C
128	56

# 30 A

690 V  
U MAX

## DECONTACTOR™ DS1



IP54<sup>(1)</sup>  
IP55<sup>(2)</sup>



2,5-6 mm<sup>2</sup> <sup>(3)</sup>  
2,5-10 mm<sup>2</sup> <sup>(4)</sup>



GRP



IK09



-40 °C  
+60 °C



AC-22  
AC-23



60309-1  
60309-4  
60947-3



2 AUX<sup>(5)</sup>

- (1) IP protection plug connected
- (2) IP protection lid closed
- (3) Flexible wiring (min.-max.).
- (4) Stranded wiring (min.-max.).
- (5) Flexible wiring : 2,5-6 mm<sup>2</sup>, stranded : 2,5-10 mm<sup>2</sup>

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 and IEC/EN 60309-4 standards 30 A/690 V

Load-break capability according to IEC/EN 60947-3/AC-22 30 A/690 V

Load-break capability according to IEC/EN 60947-3/AC-23 30 A/480 V

Short-circuit current Icc 10 kA

Power kW AC-22/AC-23 15 kW



Other cable sections:  
please contact us



For a black colour  
housing replace the second  
reference character with 5.

SOCKET-  
OUTLET female  
**DS1**



INLET male  
**DS1**



20-24 V AC	2P	311408A	311808A
220-250 V AC	1P+N+E	3114015	3118015
380-440 V AC	3P+E	3114013	3118013
220-250 V AC   380-440 V AC	3P+N+E	3114017	3118017
660-690 V AC	3P+E	3114193	3118193
380-400 V AC   660-690 V AC	3P+N+E	3114197	3118197
Up to 500 V AC - Auxiliaries 30 A*	+ 2 contacts	Ref. + 972	Ref. + 972

► Other currents, voltages, frequencies and contact configurations are available (see page 14).


\* When ordering the auxiliary option, the maximum tolerated voltage is reduced to 500 V AC.

OPTIONS	Reference
<b>INDUSTRIAL/DOMESTIC ADAPTERS</b>	
Industrial inlet MARECHAL® 1P+N+E and domestic socket-outlet 10/16 A 230 V fuse protection 10A and 16 A (with integrated fuse). All these plug adapters are available to local standards: replace D11 by D40 for UK, D30 for Germany/Netherlands/Luxembourg, D06 for Italy.	
	3118015D11
<b>COUPLER FITTED WITH A DIFFERENTIAL BREAKER</b>	
Coupler fitted with a domestic plug (IP44 - 10/16 A 250V 2P+E), a mobile socket-outlet (DS1 type - IP55-230V 1P+N+E) and a differential circuit breaker (IP55-10 or 30 mA - nominal current 16 A) with reset button.	
	3114015ID3 (30 mA)
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	613A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	311A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	613A346
<b>IP55 SELF-RETURNING LID</b>	
	Socket-outlet ref.+R
<b>IP55 METAL LOCKABLE SELF-CLOSING LID FOR INLET</b>	
	311A226
<b>SELF-EJECTING</b>	
	See page 192
<b>PRODUCTS AVAILABLE IN BLACK</b> ●	
The black dot means these products are also available in black color. Replace the second character of the product reference with 5	
<b>PRODUCT WITH ANTI-BACTERIAL TREATMENT</b> ● <span style="background-color: orange; padding: 2px;">NEW</span>	
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.	
SLEEVE	Reference
<b>POLY SLEEVE</b> ●	
	30° 512M3
	70° 512M7
<b>METAL SLEEVE</b>	
	0° [Straight] 592M0
	30° 592M3

BOXES	x°	Input	Reference
<b>POLY BOX</b> ●			
	30°	M20	512B3M20
	30°	M25	512B3M25
<b>METAL BOX (+ EARTHING WIRE)</b>			
	20°	M20	592B2M20
	20°	M25	592B2M25
<b>POLY BOX + POLY SLEEVE</b>			
	70°	Without hole	512C7000
Earth bar ref. : 51AA089	70°	Hole Ø 20	512C7M20
	70°	Hole Ø 25	512C7M25
	70°	Hole Ø 32	512C7M32
	70°	Hole Ø 40	512C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M20	512C3M20
	30°	M25	512C3M25
	30°	M32	512C3M32
	30°	M40	512C3M40
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M20	592C3M20
	30°	M25	592C3M25
	30°	M32	592C3M32
	0° [Straight]	M20	592C0M20
	0° [Straight]	M25	592C0M25
	0° [Straight]	M32	592C0M32
Cable glands are not delivered with the boxes.			
HANDLE	Input/ Cable outer Ø	Reference	Self-ejection
<b>POLY HANDLE WITH GLAND</b> ● ●			
	5-21 mm	512P0D21	/
<b>POLY HANDLE + POLY CABLE GLAND</b> ● ●			
	5-12 mm	512P020P	Ref. +443
	9-18 mm	512P025P	Ref. +443
	14-25 mm	512P032P	Ref. +443
	18-32 mm	512P040P	Ref. +443
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b> ●			
	M20	512P0M20	Ref. +443
	M25	512P0M25	Ref. +443
	M32	512P0M32	Ref. +443
	M40	512P0M40	Ref. +443
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>			
	7-13 mm	592P020M	/
	8-16 mm	592P025M	/
	16-24 mm	592P032M	/
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M20	592P0M20	/
	M25	592P0M25	/
	M32	592P0M32	/


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
166	163	69	48

COUPLER




A	B	C
259	117	69

PLUG ON 30° WALL MOUNTED SOCKET OUTLET







A	B	C	D	E
209	157	84	84	70

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET



A	B	C	D	E1	E2
206	259	138	126	117	106

PLUG ON 30° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
193	200	77	108	63	95

A	B	C	D	E
138	259	126	126	95



# 32 A

690 V  
U MAX

## DECONTACTOR™ DSN3



IP66  
IP67  
IP69



2,5-6 mm<sup>2</sup> [1]  
2,5-10 mm<sup>2</sup> [2]



GRP



IK09



-40 °C  
+60 °C



AC-22  
AC-23



60309-1  
60309-4  
60947-3



2 AUX. [3]

[1] Flexible wiring (min.-max.).

[2] Stranded wiring (min.-max.).

[3] Flexible wiring : 2,5-6 mm<sup>2</sup>,  
stranded : 2,5-10 mm<sup>2</sup>



**Other cable sections:  
please contact us**

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 and IEC/EN 60309-4 standards

32 A/690 V

Load-break capability according to IEC/EN 60947-3/AC-22

32 A/690 V

Load-break capability according to IEC/EN 60947-3/AC-23

32 A/480 V

Short-circuit current Icc

10 kA

Power kW AC-22/AC-23

18,5 kW



For a black colour  
housing replace the second  
reference character with 5.

**SOCKET-  
OUTLET female  
DSN3**



**INLET male  
DSN3**



20-24 V AC	2P	613408A	613808A
220-250 V AC	1P+N+E	6134015	6138015
380-440 V AC	3P+E	6134013	6138013
220-250 V AC   380-440 V AC	3P+N+E	6134017	6138017
660-690 V AC	3P+E	6134193	6138193
380-400 V AC   660-690 V AC	3P+N+E	6134197	6138197
Auxiliaries 30 A/500 V AC	+ 2 contacts	Ref. + 972	Ref. + 972

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

\* When ordering the auxiliary option, the maximum tolerated voltage is reduced to 500 V AC.

OPTIONS	Reference
<b>INDUSTRIAL/DOMESTIC ADAPTERS</b>	
Industrial inlet MARECHAL® 1P+N+E and domestic socket-outlet 10/16A 230 V fuse protection 10A and 16A (with integrated fuse). All these plug adapters are available to local standards: replace D11 by D40 for UK, D30 for Germany/Netherlands/Luxembourg, D06 for Italy.	
	
LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)	6138015D11
	
SAFETY HASP FOR UP TO 6 PADLOCKS	Socket-outlet ref. +843
	
LARGER RELEASE BUTTON	613A541
	
INLET CAP IP66/IP67	Ref. socket +453
	
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
 	613A346
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	
IP55 METAL LOCKABLE SELF-CLOSING LID FOR INLET	Socket-outlet ref.+R
	
613A226	
<b>SELF-EJECTION</b>	
	
See page 192	
<b>PRODUCTS AVAILABLE IN BLACK</b> ●	
The black dot means these products are also available in black color. Replace the second character of the product reference with 5	
<b>PRODUCT WITH ANTI-BACTERIAL TREATMENT</b> ● NEW	
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.	

BOXES	$\Delta x^\circ$	Input	Reference
<b>POLY BOX</b> ●			
	30°	M20	512B3M20
	30°	M25	512B3M25
<b>METAL BOX (+ EARTHING WIRE)</b>			
	20°	M20	592B2M20
	20°	M25	592B2M25
<b>POLY BOX + POLY SLEEVE (BLACK VERSION SEE ACCESSORIES DXN3 PAGE 253)</b>			
	70°	Without hole	512C7M00
Earth bar ref.: 51AA089	70°	Hole Ø 20	512C7M20
	70°	Hole Ø 25	512C7M25
	70°	Hole Ø 32	512C7M32
	70°	Hole Ø 40	512C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M20	512C3M20
	30°	M25	512C3M25
	30°	M32	512C3M32
	30°	M40	512C3M40
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M20	592C3M20
	30°	M25	592C3M25
	30°	M32	592C3M32
	0° [Straight]	M20	592C0M20
	0° [Straight]	M25	592C0M25
	0° [Straight]	M32	592C0M32


Cable glands are not delivered with the boxes.

HANDLE	Input/ Cable outer Ø	Reference	Self-ejection
<b>POLY HANDLE WITH GLAND</b> ● ●			
	5-21 mm	512P0D21	/
<b>POLY HANDLE + POLY CABLE GLAND</b> ● ●			
	5-12 mm	512P020P	Ref. +443
	9-18 mm	512P025P	Ref. +443
	14-25 mm	512P032P	Ref. +443
	18-32 mm	512P040P	Ref. +443
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>			
	7-13 mm	592P020M	/
	8-16 mm	592P025M	/
	16-24 mm	592P032M	/
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b> ●			
	M20	512P0M20	Ref. +443
	M25	512P0M25	Ref. +443
	M32	512P0M32	Ref. +443
	M40	512P0M40	Ref. +443
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M20	592P0M20	/
	M25	592P0M25	/
	M32	592P0M32	/

SLEEVE	$\Delta x^\circ$	Reference
<b>POLY SLEEVE</b> ●		
	30°	512M3
	70°	512M7
<b>METAL SLEEVE</b>		
	0° [Straight]	592M0
	30°	592M3


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
171	171	77	48

COUPLER




A	B
265	116

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




A	B	C	D	E1	E2
213	191	84	84	70	70

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
207	262	138	126	117	105.5

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
195	165	77	191	63	95

A	B	C	D	E
138	262	126	126	95



# 50 A

1 000 V  
U MAX / I

## DECONTACTOR™ DS3



IP54<sup>(1)</sup>  
IP55<sup>(2)</sup>



6-16 mm<sup>2</sup> <sup>(3)</sup>  
10-25 mm<sup>2</sup> <sup>(4)</sup>



GRP



IK09



-40 °C  
+60 °C



AC-22  
AC-23



60309-1  
60309-4  
60947-3



4 AUX. <sup>(5)</sup>

- (1) IP protection plug connected
- (2) IP protection lid closed
- (3) Flexible wiring (min.-max.).
- (4) Stranded wiring (min.-max.).
- (5) Flexible wiring : 1-2,5 mm<sup>2</sup>, stranded : 1,5-4mm<sup>2</sup>



Other cable sections:  
please contact us



For a black colour  
housing replace the second  
reference character with 5.

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 and IEC/EN 60309-4 standards

(50 A/690 V) or (45 A/1000 V)

Load-break capability according to IEC/EN 60947-3/AC-22

40 A/690 V

Load-break capability according to IEC/EN 60947-3/AC-23

50 A/400 V

Short-circuit current Icc

10 kA

Power kW AC-22/AC-23

30 kW

**SOCKET-OUTLET**  
female  
**DS3**



**INLET** male  
**DS3**



20-24 V AC	2P	313408A	313808A
220-250 V AC	1P+N+E	3134015	3138015
380-440 V AC	3P+E	3134013	3138013
220-250 V AC   380-440 V AC	3P+N+E	3134017	3138017
660-690 V AC	3P+E	3134193	3138193
380-400 V AC   660-690 V AC	3P+N+E	3134197	3138197
1 000 V AC	3P+E	3134223	3138223
Auxiliaries 16 A/400 V AC	+ 2 contacts	Ref. + 972	Ref. + 972
Auxiliaries 16 A/400 V AC	+ 4 contacts	Ref. + 264	Ref. + 264

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

OPTIONS	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	613A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	313A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	616A346
<b>IP55 SELF-RETURNING LID</b>	
	Socket-outlet ref.+R
<b>IP55 METAL LOCKABLE SELF-CLOSING LID FOR INLET</b>	
	313A226
<b>SELF-EJECTING</b>	
	See page 192
<b>PRODUCTS AVAILABLE IN BLACK</b> ●	

The black dot means these products are also available in black color.  
Replace the second character of the product reference with 5


PRODUCT WITH ANTI-BACTERIAL TREATMENT	NEW
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.	

HANDLE	Input/ Cable outer Ø	Reference	Self-ejection
<b>POLY HANDLE WITH GLAND</b> ● ●			
	10-30 mm	513P0D30	/
<b>POLY HANDLE + POLY CABLE GLAND</b> ● ●			
	9-18 mm	513P025P	Ref. +443
	14-25 mm	513P032P	Ref. +443
	18-32 mm	513P040P	Ref. +443
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b> ●			
	M20	513P0M20	Ref. +443
	M25	513P0M25	Ref. +443
	M32	513P0M32	Ref. +443
	M40	513P0M40	Ref. +443
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>			
	7-13 mm	593P020M	/
	8-16 mm	593P025M	/
	16-24 mm	593P032M	/
	22-32 mm	593P040M	/
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M20	593P0M20	/
	M25	593P0M25	/
	M32	593P0M32	/
	M40	593P0M40	/

BOXES		Input	Reference
<b>POLY BOX</b> ●			
	30°	M25	513B3M25
<b>METAL BOX (+ EARTHING WIRE)</b>			
	20°	M20	593B2M20
	20°	M25	593B2M25
	20°	M32	593B2M32
<b>POLY BOX + POLY SLEEVE</b>			
	70°	Without hole	513C7000
	70°	Hole Ø 25	513C7M25
Earth bar ref. : 51AA089	70°	Hole Ø 32	513C7M32
	70°	Hole Ø 40	513C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M20	513C3M20
	30°	M25	513C3M25
	30°	M32	513C3M32
	30°	M40	513C3M40
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M20	593C3M20
	30°	M25	593C3M25
	30°	M32	593C3M32
	30°	M40	593C3M40
	0° [Straight]	M20	593C0M20
	0° [Straight]	M25	593C0M25
	0° [Straight]	M32	593C0M32
	0° [Straight]	M40	593C0M40
	70°	M20	593C7M20
	70°	M25	593C7M25
	70°	M32	593C7M32
	70°	M40	593C7M40
Cable glands are not delivered with the boxes.			
SLEEVE		Reference	
<b>POLY SLEEVE</b> ●			
	30°	513M3	
	70°	513M7	
<b>METAL SLEEVE</b>			
	0° [Straight]	593M0	
	30°	593M3	
	70°	593M7	


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
179	184	80	55

COUPLER




A	B
277	145

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




A	B	C	D	E1	E2
235	219	89	100	77	88

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
238	313	178	166	157	146

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
208	214	77	108	63	95

A	B	C	D	E
169	313	166	166	135



# 50 A

500 V  
U MAX / I

## FLAT CONNECTOR FC



IP54



6 - 10 mm<sup>2</sup>



GRP



IK09



-40 °C  
+60 °C



**Suitable for flat cables** with width between 26 mm and 40 mm and height between 7 mm and 11 mm

### OTHER FEATURES

Polarity	4P+E
Flexible wiring (min.-max.)	6 - 10 mm <sup>2</sup>
Stranded wiring (min.-max.)	6 - 10 mm <sup>2</sup>
Number of operations	2000 cycles
IP protection plug connected	IP54
IP protection disconnected	IP2X

## REFERENCES AND ACCESSORIES

**SOCKET-  
OUTLET** female  
**FC**



500 V AC

4+E

**INLET** male  
**FC**




05F8007

05F4007

ACCESSORIES	Reference
<b>HANDLES</b>	
	01FA013
	Adapter accessory for 5G6 flat cables is included.

## DRAWINGS AND DIMENSIONS



A	B	C	D	E
84	131	19	138	89

# 63 A

1 000 V  
U MAX / ■ ■ ■

## DECONTACTOR™ DSN6



IP66  
IP67  
IP69



6-16 mm<sup>2</sup> [1]  
10-25 mm<sup>2</sup> [2]



GRP



IK09



-40 °C  
+60 °C



AC-22  
AC-23



60309-1  
60309-4  
60947-3



4 AUX. [3]

[1] Flexible wiring (min.-max.).

[2] Stranded wiring (min.-max.).

[3] Flexible wiring : 1-2,5 mm<sup>2</sup>,  
stranded : 1,5-4 mm<sup>2</sup>



**Other cable sections:  
please contact us**

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 and IEC/EN 60309-4 standards

(63 A/690 V) or (45 A/1000 V)

Load-break capability according to IEC/EN 60947-3/AC-22

40 A/690 V

Load-break capability according to IEC/EN 60947-3/AC-23

63 A/400 V

Short-circuit current Icc

10 kA

Power kW AC-22/AC-23

30 kW



**For a black colour  
housing replace the second  
reference character with 5.**

**SOCKET-OUTLET**  
female  
**DSN6**



**INLET** male  
**DSN6**



20-24 V AC	2P	616408A	616808A
190-230 V AC	3P+E	6164033	6168033
220-250 V AC	1P+N+E	6164015	6168015
380-440 V AC	3P+E	6164013	6168013
220-250 V AC   380-440 V AC	3P+N+E	6164017	6168017
660-690 V	3P+E	6164193	6168193
380-400 V	3P+N+E	6164197	6168197
Auxiliaries 16 A/400 V AC	+ 2 contacts	Ref. + 972	Ref. + 972
Auxiliaries 16 A/400 V AC	+ 4 contacts	Ref. + 264	Ref. + 264

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

Dual-voltage  
socket-outlet  
(see p. 11)



OPTIONS	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	613A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	616A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	616A346
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Socket-outlet ref.+R
<b>IP55 METAL LOCKABLE SELF-CLOSING LID FOR INLET</b>	
	616A226
<b>SELF-EJECTION</b>	
	See page 192
<b>PRODUCTS AVAILABLE IN BLACK</b>	

The black dot means these products are also available in black color.  
Replace the second character of the product reference with 5

#### PRODUCT WITH ANTI-BACTERIAL TREATMENT

This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.

SLEEVE	Ax°	Reference
<b>POLY SLEEVE ●</b>		
	30°	513M3
	70°	513M7
<b>METAL SLEEVE</b>		
	0° [Straight]	593M0
	30°	593M3
	70°	593M7


BOXES*	Ax°	Input	Reference
<b>POLY BOX ●</b>			
	30°	M25	513B3M25
<b>METAL BOX (+ EARTHING WIRE)</b>			
	20°	M20	593B2M20
	20°	M25	593B2M25
	20°	M32	593B2M32
<b>POLY BOX + POLY SLEEVE (BLACK VERSION SEE ACCESSORIES DXN6 PAGE 259)</b>			
	70°	Without hole	513C7000
Earth bar ref.: 51AA089	70°	Hole Ø 25	513C7M25
	70°	Hole Ø 32	513C7M32
	70°	Hole Ø 40	513C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M20	513C3M20
	30°	M25	513C3M25
	30°	M32	513C3M32
	30°	M40	513C3M40
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M20	593C3M20
	30°	M25	593C3M25
	30°	M32	593C3M32
	30°	M40	593C3M40
	0° [Straight]	M20	593C0M20
	0° [Straight]	M25	593C0M25
	0° [Straight]	M32	593C0M32
	0° [Straight]	M40	593C0M40
	70°	M20	593C7M20
	70°	M25	593C7M25
	70°	M32	593C7M32
	70°	M40	593C7M40

\* Cable glands are not delivered with the boxes.

HANDLE	Input/ Cable outer Ø	Reference	Self-ejection
<b>POLY HANDLE WITH GLAND ● ●</b>			
	10-30 mm	513P0D30	/
<b>POLY HANDLE + POLY CABLE GLAND ● ●</b>			
	5-12 mm	513P020P	Ref. +443
	9-18 mm	513P025P	Ref. +443
	14-25 mm	513P032P	Ref. +443
	18-32 mm	513P040P	Ref. +443
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>			
	7-13 mm	593P020M	/
	8-16 mm	593P025M	/
	16-24 mm	593P032M	/
	22-32 mm	593P040M	/
<b>POLY HANDLE (WITHOUT CABLE GLAND) ●</b>			
	M20	513P0M20	Ref. +443
	M25	513P0M25	Ref. +443
	M32	513P0M32	Ref. +443
	M40	513P0M40	Ref. +443
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M20	593P0M20	/
	M25	593P0M25	/
	M32	593P0M32	/
	M40	593P0M40	/


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
184	195	84	55

COUPLER




A	B
286	122

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




A	B	C	D	E1	E2
238	225	89	100	77	88

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
239	317	178	166	157	146

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
212	219	77	108	64	95

A	B	C	D	E
170	317	166	166	135



# 90 A

1 000 V  
U MAX / I

## DECONTACTOR™ DS6 POLY



IP66  
IP67



10-25 mm<sup>2</sup><sup>(1)</sup>  
10-35 mm<sup>2</sup><sup>(2)</sup>



GRP



IK09



-40 °C  
+60 °C



AC-22  
AC-23



60309-1  
60309-4



4 AUX.<sup>(3)</sup>

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).  
(3) Flexible wiring 2,2 mm<sup>2</sup>.



Other cable sections:  
please contact us

GRP devices are not  
compatible with metal  
devices.

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 and IEC/EN 60309-4 standards

(90 A/690 V) or (63 A/1000 V)

Load-break capability according to IEC/EN 60947-3/AC-22

63 A/690 V

Load-break capability according to IEC/EN 60947-3/AC-23

90 A/400 V

Short-circuit current Icc

10 kA

Power kW AC-22/AC-23

45 kW

**SOCKET-OUTLET**  
female  
**DS6**



**INLET** male  
**DS6**



For a black colour  
housing replace the second  
reference character with 5.

Dual-voltage  
socket-outlet  
(see p. 11)

220-250 V AC	1P+N+E	3164015	3168015
380-440 V AC	3P+E	3164013	3168013
220-250 V AC	3P+N+E	3164017	3168017
660-690 V AC	3P+E	3164193	3168193
380-400 V AC	3P+N+E	3164197	3168197
1 000 V AC	3P+E	3164223	3168223
Auxiliaries 5 A/500 V AC	+ 2 contacts	Ref. + 972	Ref. + 972
Auxiliaries 5 A/500 V AC	+ 4 contacts	Ref. + 264	Ref. + 264

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

► Existing version for 100 A is available, order Reference +228.

OPTIONS	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	399A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	316A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	316A346
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Ref. socket + R
<b>IP55 METAL LOCKABLE SELF-CLOSING LID FOR INLET</b>	
	316A226
<b>SELF-EJECTION</b>	
	See page 192
<b>PRODUCTS AVAILABLE IN BLACK</b> ●	
The black dot means these products are also available in black color. Replace the second character of the product reference with 5	


HANDLE	Input/ Cable outer Ø	Reference	Self-ejection
<b>ELASTOMER HANDLE WITH GLAND</b>			
	18-25 mm	554P0D25L	Ref. +443
	25-35 mm	554P0D35L	Ref. +443
	35-45 mm	554P0D45L	Ref. +443
	45-49 mm	554P0D49L	Ref. +443
<b>POLY HANDLE WITH GLAND</b> ●			
	13-35 mm	514P0D35	/
<b>POLY HANDLE + POLY CABLE GLAND</b> ●			
	14-25 mm	514P032P	Ref. +443
	18-32 mm	514P040P	Ref. +443
	24-38 mm	514P050P	Ref. +443
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b> ●			
	M32	514P0M32	Ref. +443
	M40	514P0M40	Ref. +443
	M50	514P0M50	/
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M25	594P0M25	/
	M32	594P0M32	/
	M40	594P0M40	/
	M50	594P0M50	/

HANDLE	Input/Cable outer Ø	Reference
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>		
	8-16 mm	594P025M
	16-24 mm	594P032M
	22-32 mm	594P040M
	34-44 mm	594P050M

BOXES		Input	Reference
<b>POLY BOX</b> ●			
	30°	M32	514B3M32
	30°	M40	514B3M40
<b>METAL BOX (+ EARTHING WIRE)</b>			
	20°	M25	594B2M25
	20°	M32	594B2M32
	20°	M40	594B2M40
<b>POLY BOX + POLY SLEEVE</b>			
	70°	Without hole	514C7000
	70°	Hole Ø 32	514C7M32
Earth bar ref. : 51AA089	70°	Hole Ø 40	514C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M25	514C3M25
	30°	M32	514C3M32
	30°	M40	514C3M40
	30°	M50	514C3M50
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M25	594C3M25
	30°	M32	594C3M32
	30°	M40	594C3M40
	30°	M50	594C3M50
0° (Straight)			
	0° (Straight)	M25	594C0M25
	0° (Straight)	M32	594C0M32
	0° (Straight)	M40	594C0M40
	0° (Straight)	M50	594C0M50
0° (Straight)			
	0° (Straight)	M25	594C7M25
	0° (Straight)	M32	594C7M32
	0° (Straight)	M40	594C7M40
	0° (Straight)	M50	594C7M50
Cable glands are not delivered with the boxes.			
SLEEVE		Reference	
<b>POLY SLEEVE</b>			
	30°	514M3	
	70°	514M7	
<b>METAL SLEEVE</b>			
	0° (Straight)	594M0	
	30°	594M3	
	70°	594M7	


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C
252	228	105

COUPLER




A	B
405	228

PLUG ON 30° WALL MOUNTED SOCKET OUTLET





A	B	C	E1	E2
329	296	105	89	112

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET





A	B	C	E1	E2
267	383	178	157	145

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	E1	E2
278	280	105	87	122

A	B	C	E
203	381	166	135



# 90 A

1 000 V  
U MAX / I

## DECONTACTOR™ DS6 METAL



IP66  
IP67



10-25 mm<sup>2</sup><sup>(1)</sup>  
10-35 mm<sup>2</sup><sup>(2)</sup>



METAL



IK09



-40 °C  
+60 °C



AC-22  
AC-23



60309-1  
60309-4  
60947-3



4 AUX.<sup>(3)</sup>



EMC

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).  
(3) Flexible wiring : 2,2 mm<sup>2</sup>.



Other configurations on request

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 and IEC/EN 60309-4 standards

(90 A/690 V) or (63 A/1000 V)

Load-break capability according to IEC/EN 60947-3/AC-22

63 A/690 V

Load-break capability according to IEC/EN 60947-3/AC-23

90 A/400 V

Short-circuit current Icc

10 kA

Power kW AC-22/AC-23

45 kW

GRP devices are not compatible with metal devices.

SOCKET-  
OUTLET female  
**DS6**



Dual-voltage  
socket-outlet  
(see p. 11)

220-250 V AC	1P+N+E	3964015	3968015
380-440 V AC	3P+E	3964013	3968013
220-250 V AC	3P+N+E	3964017	3968017
660-690 V AC	3P+E	3964193	3968193
380-400 V AC	3P+N+E	3964197	3968197
1 000 V AC	3P+E	3964223	3968223
Auxiliaries 5 A/500 V AC	+ 2 contacts	Ref. + 972	Ref. + 972
Auxiliaries 5 A/500 V AC	+ 4 contacts	Ref. + 264	Ref. + 264

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

► Existing version for 100 A is available, order Reference +228.

OPTIONS	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	399A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	316A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	316A346
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Ref. socket + R
<b>IP55 METAL LOCKABLE SELF-CLOSING LID FOR INLET</b>	
	396A226
<b>ELECTROMAGNETIC COMPATIBILITY (EMC)</b>	
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.
<b>SELF-EJECTION</b>	
	See page 192

HANDLE	Input/Cable outer Ø	Reference	Self-ejection
<b>ELASTOMER HANDLE WITH GLAND</b>			
	18-25 mm	554P0D25L	Ref. +443
	25-35 mm	554P0D35L	Ref. +443
	35-45 mm	554P0D45L	Ref. +443
	45-49 mm	554P0D49L	Ref. +443

SLEEVE	Reference	
	POLY	METAL
	0° (Straight)	/
	30°	514M3
	70°	514M7
	50° (Straight)	594M0
	50° (Angled)	594M1
	70° (Straight)	594M2
	70° (Angled)	594M3
	90° (Straight)	594M4
	90° (Angled)	594M5


BOXES		Input	Reference
<b>POLY BOX</b>			
	30°	M32	514B3M32
	30°	M40	514B3M40
<b>METAL BOX (+ EARTHING WIRE)</b>			
	20°	M25	594B2M25
	20°	M32	594B2M32
	20°	M40	594B2M40
<b>POLY BOX + POLY SLEEVE</b>			
	70°	Without hole	514C7000
	70°	Ø 32 mm drill hole	514C7M32
Earth bar ref. : 51AA089	70°	Ø 40 mm drill hole	514C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M25	514C3M25
	30°	M32	514C3M32
	30°	M40	514C3M40
	30°	M50	514C3M50
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M25	594C3M25
	30°	M32	594C3M32
	30°	M40	594C3M40
	30°	M50	594C3M50
	0° [Straight]	M25	594C0M25
	0° [Straight]	M32	594C0M32
	0° [Straight]	M40	594C0M40
	0° [Straight]	M50	594C0M50
	70°	M25	594C7M25
	70°	M32	594C7M32
	70°	M40	594C7M40
	70°	M50	594C7M50

Cable glands are not delivered with the boxes.

HANDLE	Input/ Cable outer Ø	Reference	Self-ejection
<b>POLY HANDLE WITH GLAND</b>			
	13-35 mm	514P0D35	/
<b>POLY HANDLE + POLY CABLE GLAND</b>			
	14-25 mm	514P032P	Ref. +443
	18-32 mm	514P040P	Ref. +443
	24-38 mm	514P050P	Ref. +443
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b>			
	M32	514P0M32	Ref. +443
	M40	514P0M40	Ref. +443
	M50	514P0M50	/
<b>METAL HANDLE + METAL CABLE GLAND (+ EARTHING WIRE)</b>			
	8-16 mm	594P025M	/
	16-24 mm	594P032M	/
	22-32 mm	594P040M	/
	34-44 mm	594P050M	/
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M25	594P0M25	/
	M32	594P0M32	/
	M40	594P0M40	/
	M50	594P0M50	/


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
241	230	104	66

COUPLER




A	B
386	230

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




A	B	C	E1	E2
338	270	135	125	97

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
246	357	145	166	125	97

PLUG ON 30° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
279	257	102	136	88	122

PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	E1	E2
169	346	104	88	122



# 125 A

440 V  
U MAX / ■ ■ ■

## HIGH TEMPERATURE PLUG DSHT

150 °C



IP44



10-35 mm<sup>2</sup> <sup>[1]</sup>  
10-50 mm<sup>2</sup> <sup>[2]</sup>



METAL



IK09



2 AUX.

[1] Flexible wiring (min.-max.).  
[2] Stranded wiring (min.-max.).

### OTHER FEATURES

Pre-cabled auxiliaries - high-temperature cable

1.5 mm<sup>2</sup>

Earthing cable section

35 mm<sup>2</sup> max.



No breaking under load

Other configurations on request



SOCKET-OUTLET  
DSHT

INLET  
DSHT

220-250 V AC	1P+N+E	3964H15	3968H15
380-440 V AC	3P+E	3964H13	3968H13
220-250 V AC	3P+N+E	3964H17	3968H17
Auxiliaries 5 A/500 V AC	+ 2 contacts	Ref. + 972	Ref. + 972

OPTIONS	Reference
LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)	Réf + 843


BOXES (WITHOUT CABLE GLAND)		Input	Reference
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M25	574C3M25185
	30°	M32	574C3M32185
	30°	M40	574C3M40185
	30°	M50	574C3M50185

HANDLE (WITHOUT CABLE GLAND)		Input	Reference
<b>METAL HANDLE (+ EARTHING WIRE)</b>			
		M25	574P0M25185
		M32	574P0M32185
		M40	574P0M40185
		M50	574P0M50185


HIGH TEMPERATURE CABLE GLAND (IP2X)	Cable outer Ø	Input	Reference
	12,0 - 20,5 mm	M25	9PEM25BR
	18,0 - 27,8 mm	M32	9PEM32BR
	24,0 - 33,0 mm	M40	9PEM40BR
	33,0 - 42,0 mm	M50	9PEM50BR

## DRAWINGS AND DIMENSIONS

PLUG ON SOCKET OUTLET



PLUG ON 30° WALL MOUNTED SOCKET OUTLET



A	B	C	E1	A	B	C	E1	E2
248	230	105	66	345	308	150	125	97

# 150 A

1 000 V  
U MAX / ■ ■ ■

## DECONTACTOR™ DS9 POLY



IP66  
IP67  
IP69

25-70 mm<sup>2</sup> (1)  
25-95 mm<sup>2</sup> (2)

GRP

IK09

-40 °C  
+60 °C

AC-22  
AC-23

60309-1  
60309-4  
60947-3

6 AUX. (3)

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).  
(3) Flexible wiring : 2,5 mm<sup>2</sup>.

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 and IEC/EN 60309-4 standards

150 A/690 V

Load-break capability according to IEC/EN 60947-3/AC-22

(90 A/690 V) or (150 A/600 V)

Load-break capability according to IEC/EN 60947-3/AC-23

100 A/440 V

Short-circuit current Icc

10 kA

Power kW AC-22/AC-23

80 kW



Other configurations on request

GRP devices are not compatible with metal devices.



Each inlet should be connected to a wall box, a sleeve or a handle to ensure correct operation of the closing mechanism.

**SOCKET-OUTLET**  
female  
**DS9**



**INLET** male  
**DS9**



380-440 V AC	3P+E	3194013	3198013
220-250 V AC	380-440 V AC	3P+N+E	3194017
660-690 V AC		3P+E	3194193
380-400 V AC	660-690 V AC	3P+N+E	3198197
1 000 V AC*		3P+E	3194223
Auxiliaries 10 A/400 V AC		+ 2 contacts	Ref. + 262
Auxiliaries 10 A/400 V AC		+ 4 contacts	Ref. + 264
Auxiliaries 10 A/400 V AC		+ 6 contacts	Ref. + 976

► Other currents, voltages, frequencies and contact configurations are available (see page 14).


\* Switch rating up to 125 A.

OPTIONS	Reference		
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>			
	Socket-outlet ref. +843		
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>			
	399A541		
<b>LARGER RELEASE BUTTON</b>			
	Ref. socket +453		
<b>INLET CAP IP66/IP67</b>			
	319A426		
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>			
	Socket-outlet ref.+R		
HANDLE	Input/ Cable outer Ø	Reference	Self-ejection
<b>ELASTOMER HANDLE WITH GLAND</b>			
	18-25 mm	555P0D25	Ref. +443
	25-35 mm	555P0D35	Ref. +443
	35-45 mm	555P0D45	Ref. +443
	45-49 mm	555P0D49	Ref. +443
<b>POLY HANDLE + POLY CABLE GLAND</b>			
	14-25 mm	515P032P	Ref. +443
	18-32 mm	515P040P	Ref. +443
	24-38 mm	515P050P	Ref. +443
	35-48 mm	515P063P	/
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b>			
	M50	515P0M50	/
	M63	515P0M63	/
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>			
	16-24 mm	595P032M	/
	22-32 mm	595P040M	/
	34-44 mm	595P050M	/
	35-48 mm	595P063M	/
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M32	595P0M32	/
	M40	595P0M40	/
	M50	595P0M50	/
	M63	595P0M63	/

BOXES		Input	Reference
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M32	515C3M32
	30°	M40	515C3M40
	30°	M50	515C3M50
	30°	M63	515C3M63
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M32	595C3M32
	30°	M40	595C3M40
	30°	M50	595C3M50
	30°	M63	595C3M63
	0° (Straight)	M32	595C0M32
	0° (Straight)	M40	595C0M40
	0° (Straight)	M50	595C0M50
	0° (Straight)	M63	595C0M63
	70°	M32	595C7M32
	70°	M40	595C7M40
	70°	M50	595C7M50
	70°	M63	595C7M63
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE + CORNET</b>			
	0° (Straight)	M50	595E0M50
	30°	M50	595E3M50
	30°	M63	595E3M63
	70°	M50	595E7M50
	70°	M63	595E7M63
Cable glands are not delivered with the boxes.			
SLEEVE		Reference	
<b>POLY SLEEVE</b>			
	30°	515M3	
<b>METAL SLEEVE</b>			
	0° (Straight)	595M0	
	30°	595M3	
	70°	595M7	


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
313	279	322	81

COUPLER




A	B
491	280

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




A	B	C	D	E1	E2
448	265	190	142	170	108

PLUG ON 70° WALL BOX MOUNTED SOCKET




A	B	C	D	E1	E2
311	427	190	142	170	108

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E
355	329	322	141	124

A	B	C	D	E
218	425	322	140	124



# 150 A

1 000 V  
U MAX / ■ ■ ■

## DECONTACTOR™ DS9 METAL



IP66  
IP67  
IP69



25-70 mm<sup>2</sup> <sup>(1)</sup>  
25-95 mm<sup>2</sup> <sup>(2)</sup>



METAL



IK10



-40 °C  
+60 °C



AC-22  
AC-23



60309-1  
60309-4  
60947-3



6 AUX. <sup>(3)</sup>



EMC

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).  
(3) Flexible wiring : 2,5 mm<sup>2</sup>.

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 and IEC/EN 60309-4 standards

150 A/690 V

Load-break capability according to IEC/EN 60947-3/AC-22

(90 A/690 V) or (150 A/600 V)

Load-break capability according to IEC/EN 60947-3/AC-23

100 A/440 V

Short-circuit current Icc

10 kA

Power kW AC-22/AC-23

80 kW



Other configurations on request

GRP devices are not compatible with metal devices.



Each inlet should be connected to a wall box, a sleeve or a handle to ensure correct operation of the closing mechanism.

**SOCKET-OUTLET**  
female  
**DS9**



**INLET** male  
**DS9**



380-440 V AC	3P+E	3994013	3998013
220-250 V AC	380-440 V AC	3P+N+E	3998017
660-690 V AC		3P+E	3998193
380-400 V AC	660-690 V AC	3P+N+E	3998197
1 000 V AC*		3P+E	3998223
Auxiliaries 10 A/400 V AC	+ 2 contacts	Ref. + 262	Ref. + 262
Auxiliaries 10 A/400 V AC	+ 4 contacts	Ref. + 264	Ref. + 264
Auxiliaries 10 A/400 V AC	+ 6 contacts	Ref. + 976	Ref. + 976

► Other currents, voltages, frequencies and contact configurations are available (see page 14).


\* Switch rating up to 125 A.

OPTIONS	Reference	
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>		
	Socket-outlet ref. +843	
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>		
	399A541	
<b>ALLEN-SCREW LOCKING LATCH</b>		
Direct latch locking, no padlocking option.	Ref. socket + 22	
<b>INLET CAP IP66/IP67</b>		
	319A426	
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>		
	Socket-outlet ref.+R	
<b>ELECTROMAGNETIC COMPATIBILITY (EMC)</b>		
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.	
HANDLE	Input/ Cable outer Ø	Reference
<b>ELASTOMER HANDLE WITH GLAND</b>		
	18-25 mm	555P0D25
	25-35 mm	555P0D35
	35-45 mm	555P0D45
	45-49 mm	555P0D49
<b>POLY HANDLE + POLY CABLE GLAND</b>		
	14-25 mm	515P032P
	18-32 mm	515P040P
	24-38 mm	515P050P
	35-48 mm	515P063P
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b>		
	M50	515P0M50
	M63	515P0M63
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>		
	16-24 mm	595P032M
	22-32 mm	595P040M
	34-44 mm	595P050M
	35-48 mm	595P063M
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>		
	M32	595P0M32
	M40	595P0M40
	M50	595P0M50
	M63	595P0M63

BOXES		Input	Reference
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M32	515C3M32
	30°	M40	515C3M40
	30°	M50	515C3M50
	30°	M63	515C3M63
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M32	595C3M32
	30°	M40	595C3M40
	30°	M50	595C3M50
	30°	M63	595C3M63
	0° [Straight]	M32	595C0M32
	0° [Straight]	M40	595C0M40
	0° [Straight]	M50	595C0M50
	0° [Straight]	M63	595C0M63
	70°	M32	595C7M32
	70°	M40	595C7M40
	70°	M50	595C7M50
	70°	M63	595C7M63
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE + CORNET</b>			
	0° [Straight]	M50	595E0M50
	30°	M50	595E3M50
	30°	M63	595E3M63
	70°	M50	595E7M50
	70°	M63	595E7M63
Cable glands are not delivered with the boxes.			
SLEEVE		Reference	
<b>POLY SLEEVE</b>			
	30°	515M3	
<b>METAL SLEEVE</b>			
	0° [Straight]	595M0	
	30°	595M3	
	70°	595M7	


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C
313	299	322

COUPLER




A	B
490	299

PLUG ON 30° WALL MOUNTED SOCKET OUTLET







A	B	C	D	E1	E2
448	330	322	142	170	108

PLUG ON 70° WALL BOX MOUNTED SOCKET



A	B	C	D	E1	E2
310	426	190	142	170	108

PLUG ON 30° INCLINED SOCKET-OUTLET



A	B	C	D	E
355	331	322	141	124

A	B	C	D	E
217	424	322	141	124



# 250 A

1 000 V  
U<sub>MAX</sub>

## DECONTACTOR™ DS2



IP66  
IP67



70-95 mm<sup>2</sup><sup>(1)</sup>  
70-120 mm<sup>2</sup><sup>(2)</sup>



METAL



IK10



-40 °C  
+60 °C



AC-22  
AC-23



60309-1  
60309-4  
60947-3



6 AUX.<sup>(3)</sup>



EMC

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).  
(3) Flexible wiring : 2,5 mm<sup>2</sup>.

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 and IEC/EN 60309-4 standards

(250 A/500 V) or (200 A/690 V)

Load-break capability according to IEC/EN 60947-3/AC-22

(250 A/400 V) or (125 A/690 V)

Load-break capability according to IEC/EN 60947-3/AC-23

160 A/440 V

Short-circuit current I<sub>SC</sub>

10 kA



Other configurations on request.



Each inlet should be connected to a wall box, a sleeve, a handle or a spacer to ensure correct operation of the closing mechanism.

**SOCKET-OUTLET**  
female  
**DS2**



**INLET** male  
**DS2**



380-440 V AC	3P+E	3924013	3928013
220-250 V AC	380-440 V AC	3P+N+E	3928017
660-690 V AC		3P+E	3928193
380-400 V AC	660-690 V AC	3P+N+E	3928197
1 000 V AC**		3P+E	3928223
Auxiliaries 5 A/400 V AC		+ 2 contacts	Ref. + 972
Auxiliaries 5 A/400 V AC		+ 4 contacts*	Ref. + 174
Auxiliaries 5 A/400 V AC		+ 6 contacts*	Ref. + 976

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

\* These versions cannot be ordered with neutral.


\*\* Switch rating up to 150 A.

OPTIONS	Section de câblage	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>		
	Socket-outlet ref. +843	
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>		
	399A541	
<b>ALLEN-SCREW LOCKING LATCH</b>		
Direct latch locking, no padlocking option.	Ref. socket + 22	
<b>INLET CAP IP66/IP67</b>		
	392A426	
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>		
	Socket-outlet ref.+R	
<b>ELECTROMAGNETIC COMPATIBILITY (EMC)</b>		
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.	
<b>CABLE AMPLIFIER LUGS</b>		
	Flexible 120 mm <sup>2</sup> Stranded 150 mm <sup>2</sup>	392A277150
	Flexible 150 mm <sup>2</sup> Stranded 185 mm <sup>2</sup>	392A277185
<b>INCOMPATIBILITY</b>		
	Those products marked with a red dot are incompatible with use with amplifier ends.	
<b>SPACERS (BETWEEN THE WALL BOX OR PANEL)</b>		
	Depth 68 mm	5K7M0-68
	Depth 115 mm	5K7M0-115
<b>PADLOCKING/ELECTRO-MECHANICAL INTERLOCKING</b>		
	Socket-outlet reference+MIL. Check out the details on page 312	
<b>SLEEVE</b>		
<b>METAL SLEEVE</b>		
	0° (Straight)	596M0
	60°	596M6
	60°	597M6

BOXES		Input	Reference
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE + CORNET</b>			
	60°	M50	596E6M50
	60°	M63	596E6M63
	60°	M75	596E6M75
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE + CORNET</b>			
	60°	M63	597E6M63
	60°	M75	597E6M75
Cable glands are not delivered with the boxes.			
HANDLE	Input/ Cable outer Ø	Reference	
<b>ELASTOMER HANDLE WITH GLAND</b>			
	25-35 mm	556P0D35	
	35-45 mm	556P0D45	
	45-49 mm	556P0D49	
<b>POLY HANDLE + POLY CABLE GLAND</b>			
	35-48 mm	516P063P	
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b>			
	M63	516P0M63	
	M75	516P0M75	
<b>METAL HANDLE WITH INTEGRATED CABLE CLAMP</b>			
	40-50 mm	5K6P0D50	
	51-60 mm	5K6P0D60	
	61-70 mm	5K6P0D70	
	71-80 mm	5K6P0D80	
	81-90 mm	5K6P0D90	
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M50	596P0M50	
	M63	596P0M63	
	M75	596P0M75	
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M40	5K6P0M40L	
	M50	5K6P0M50L	
	M63	5K6P0M63L	
	M75	5K6P0M75L	
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND) - LARGE SIZE</b>			
	M63	796P0M63	
	M75	796P0M75	


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
362	327	340	98

COUPLER




A	B
590	327

PLUG ON 60° WALL BOX MOUNTED SOCKET OUTLET



A	B	C	E1	E2
392	465	340	202	154

PLUG ON 60° INCLINED SOCKET OUTLET




A	B	C	D	E
300	465	191	191	165



# 350 A

1 000 V  
U MAX / ■ ■ ■

## INDUSTRIAL SOCKET OUTLET DS2



IP66  
IP67



95 mm<sup>2</sup> <sup>(1)</sup>  
95-120 mm<sup>2</sup> <sup>(2)</sup>



METAL



IK10



-40°C  
+60°C



2 PIL.



EMC

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### OTHER FEATURES

Pilot wiring

2,5 mm<sup>2</sup>

\* See our cable AMPLIFIER lugs for sections bigger than 95 mm<sup>2</sup> (flexible) or 120 mm<sup>2</sup> (stranded).



Padlocking system is standard.

SOCKET-OUTLET  
female  
**DS2**



INLET male  
**DS2**



Each socket-outlet and each inlet should be connected to a wall box, a sleeve, a handle or a spacer to ensure correct operation of the closing mechanism.

220-250 V AC	380-440 V AC	3P+N+E+2 pilots	3924017240	3928017240
380-400 V AC	660-690 V AC	3P+N+E+2 pilots	3924197240	3928197240

► Other currents, voltages, frequencies are available (see page 14).

OPTIONS	Cable section	Reference
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>		
	399A541	
<b>ALLEN-SCREW LOCKING LATCH</b>		
Direct latch locking, no padlocking option.	Ref. socket + 22	
<b>INLET CAP IP66/IP67</b>		
	392A426	
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>		
	Socket-outlet ref.+R	
<b>ELECTROMAGNETIC COMPATIBILITY (EMC) </b>		
Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.		
<b>CABLE AMPLIFIER LUGS</b>		
	Flexible 120 mm <sup>2</sup> Stranded 150 mm <sup>2</sup>	392A277150
	Flexible 150 mm <sup>2</sup> Stranded 185 mm <sup>2</sup>	392A277185
<b>SPACERS (BETWEEN THE WALL BOX OR PANEL)</b>		
	Depth 68 mm	5K7M0-68
	Depth 115 mm	5K7M0-115
<b>PADLOCKING/ELECTRO-MECHANICAL INTERLOCKING</b>		
	Socket-outlet reference+MIL. Check out the details on page 312	

## ELECTRICAL INTERLOCKING


At this level of power, it is not possible to break directly under load. Electrical interlocking with a switch or a pilot controlled contactor is required.

Boxes with the following equipment are available upon request:

- circuit breaker or differential switch,
- contactor,
- fuses,
- loop-out enclosures,
- terminals for single pole cables...


HANDLE	Cable outer Ø (min./max.)	Reference
<b>METAL HANDLE WITH INTEGRATED CABLE CLAMP</b>		
	40-50 mm	5K6P0D50
	51-60 mm	5K6P0D60
	61-70 mm	5K6P0D70
	71-80 mm	5K6P0D80
	81-90 mm	5K6P0D90
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b> 		
	M40	5K6P0M40L
	M50	5K6P0M50L
	M63	5K6P0M63L
	M75	5K6P0M75L
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND) - LARGE SIZE</b> 		
	M63	796P0M63
	M75	796P0M75
SLEEVE		Reference
<b>METAL SLEEVE</b> 		
	60°	597M6
BOXES		Cable outer Ø
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE + CORNET</b> 		
	60°	M63
	60°	M75
		597E6M63
		597E6M75
<b>STAINLESS STEEL (+ EARTHING WIRE) + METAL SLEEVE + METAL CABLE GLAND (+ EARTHING WIRE)</b>		
	70°	35-46 mm
	70°	48-65 mm
		577C763M
		577C775M

## TYPICAL WIRING DIAGRAM OF THE DS2 CONTROL CIRCUIT




# DRAWINGS AND DIMENSIONS

INLET




A	B	C
420	188	217

COUPLER SOCKET




A	B	C	D
503	188	375	327

## WALL BOX MOUNTED SOCKET-OUTLET 70°



A	B	C	D	E1	E2
206	784	375	651	240	190

## PANEL MOUNTED SOCKET-OUTLET 60°



A	B	C1	C2	D	E
255	474	180	375	180	165

# 400 A

1 000 V  
U MAX / ■ ■ ■

## INDUSTRIAL SOCKET-OUTLET DS4



IP66  
IP67



95-150 mm<sup>2</sup><sup>(1)</sup>  
95-185 mm<sup>2</sup><sup>(2)</sup>



METAL



IK10



-40 °C  
+60 °C



2 PIL.



EMC

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).



Other cable sections:  
please contact us

### OTHER FEATURES

Mechanical interlock	standard
Inlet closing device in stainless steel	standard
Pilot contacts 5 A/400 V AC for electrical interlock	2
Auxiliaries wiring	2,5 mm <sup>2</sup>



Each socket-outlet  
and each inlet should be  
connected to a wall box,  
a sleeve, a handle or a  
spacer to ensure correct  
operation of the closing  
mechanism.

SOCKET-OUTLET  
female  
**DS4**



INLET male  
**DS4**



Compatible with  
previous version using kit  
**394A396**

380-440 V AC	3P+E+ 2 pilots	3944013	3948013
660-690 V AC	3P+E+ 2 pilots	3944193	3948193
1 000 V AC	3P+E+ 2 pilots	3944223	3948223

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

OPTIONS	Cable section	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>		
	Socket-outlet ref. +843	
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>		
	399A541	
<b>INLET CAP IP66/IP67</b>		
	392A426	
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>		
	Socket-outlet ref.+R	
<b>ELECTROMAGNETIC COMPATIBILITY (EMC)</b>		
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.	
<b>CABLE AMPLIFIER LUGS</b>		
	Flexible 185 mm <sup>2</sup> Stranded 240 mm <sup>2</sup>	394A277-240
	Flexible 240 mm <sup>2</sup> Stranded 300 mm <sup>2</sup>	394A277-300
<b>SPACERS (BETWEEN THE WALL BOX OR PANEL)</b>		
	Depth 68 mm	5K7M0-68
	Depth 115 mm	5K7M0-115
<b>PADLOCKING/ELECTRO-MECHANICAL INTERLOCKING</b>		
	Socket-outlet reference+MIL. Check out the details on page 312	

SLEEVE		Reference
<b>METAL SLEEVE <sup>(1)</sup></b>		
	60°	597M6

(1) For use with amplifier tips, it is necessary to use a spacer of 68 mm minimum.

## ELECTRICAL INTERLOCKING

With such a current, disconnection under load is just not possible. Electrical interlocking with a switch or a pilot controlled contactor is required.

Note that we may customize the wall box with the following functions or devices:


- circuit breaker or differential switch,
- contactor,
- fuses,
- loop-in/loop-out configuration,
- Terminals fitted for single-pole cable use...

HANDLE	Cable outer Ø (min./max.)	Reference
<b>METAL HANDLE WITH INTEGRATED CABLE CLAMP</b>		
	40-50 mm	5K6P0D50
	51-60 mm	5K6P0D60
	61-70 mm	5K6P0D70
	71-80 mm	5K6P0D80
	81-90 mm	5K6P0D90


METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)		
	M40	5K6P0M40L
	M50	5K6P0M50L
	M63	5K6P0M63L
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND) - LARGE SIZE</b>		
	M63	796P0M63
	M75	796P0M75

BOXES		Cable outer Ø	Reference
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE + CORNET <sup>(1)</sup></b>			
	60°	M63	597E6M63
	60°	M75	597E6M75
<b>STAINLESS STEEL (+ EARTHING WIRE) + METAL SLEEVE + METAL CABLE GLAND (+ EARTHING WIRE)</b>			
	70°	35-46 mm	577C763M
	70°	48-65 mm	577C775M


## TYPICAL WIRING DIAGRAM OF THE DS4 CONTROL CIRCUIT



# DRAWINGS AND DIMENSIONS


**INLET**

A	B	C
420	188	217

**COUPLER SOCKET**


A	B	C	D
473	188	375	327

## WALL BOX MOUNTED SOCKET-OUTLET 70°



A	B	C	D	E1	E2
206	784	375	651	240	190

## PANEL MOUNTED SOCKET-OUTLET 60°



A	B	C1	C2	D	E
255	474	180	375	180	165

400A - 600A


# PF INDUSTRIAL PLUGS



## MECHANICAL FEATURES

**Pilot contacts :** designed to connect after and disconnect before the phase contacts.

**IK10 metal casing**  
excellent resistance to shocks.



**Lateral spring-loaded silver butt-contacts**  
Silver is an excellent conductor and the plug engagement cleans contacts automatically.

### Electromechanical interlocking mechanism

The locking mechanism guarantees safe and watertight connection and engages the pilot contacts.

**Safety shutter**  
IP2X/IPXXB (PFC), IP4X/IPXXD (PFQ).



## MECHANICAL AND ELECTRICAL LOCKING



Off load engagement



The male-female connection is automatically watertight.



Locking the plug in the socket closes the pilots and connects the main circuit.

PRESENTATION OF HIGH POWER INDUSTRIAL  
PLUG MOUNTING IS AVAILABLE ON OUR  
YOUTUBE CHANNEL




## ELECTRICAL INTERLOCKING

At this level of power, it is not possible to directly disconnect under load. Electrical interlocking with a switch or a pilot controlled contactor is required. Boxes with the following equipment are available upon request:

- circuit breaker or differential switch,
- contactor,
- fuses,
- loop-out enclosures,
- terminals for single pole cables...

## TYPICAL WIRING DIAGRAM OF THE PFC CONTROL CIRCUIT




PILOT CONTACTS	PFC4	PFC6
Pilot contacts	2	2
Pilot Amperage	10 A/400 V AC	20 A/400 V AC
Interlocking Type	Mechanical	Mechanical
Terminal Type	Solder/crimp	Screw

Notes: The mechanical locking of the plug to the socket-outlet, via the rotation of a cam, closes the pilot contacts. Failure to use a pilot/relay system can create an electrical shock hazard.

# 400 A

*U MAX / 690 V*

## INDUSTRIAL PLUG PFQ4



IP66  
IP67



95-240 mm<sup>2</sup> <sup>(1)</sup>  
95-240 mm<sup>2</sup> <sup>(2)</sup>



METAL



IK10



-40°C  
+60°C



6 AUX. +  
2 PIL.

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### OTHER FEATURES

Junction through mono or multi conductors cables

Auxiliary contacts (10 A/400 V)

6

Pilot contacts (10 A/400 V)

2

Flexible wiring auxiliaries/pilots

1,5 mm<sup>2</sup>

**SOCKET-OUTLET**  
female  
**PFQ4**



**INLET** male  
**PFQ4**



220-250 V AC	380-440 V AC	3P+N+E	4744017	4748017
380-400 V AC	660-690 V AC	3P+N+E	4744197	4748197

► Other currents, voltages, frequencies are available (see page 14).

BOXES STAINLESS STEEL 316L	Cable outer Ø	Reference
<b>WIRING FROM 95 TO 150 mm<sup>2</sup> CABLE GLAND INCLUDED</b>		
	40-50 mm	474A023050
	51-60 mm	474A023060
	61-70 mm	474A023070
	71-80 mm	474A023080
	81-90 mm	474A023090

BOXES STAINLESS STEEL 316L	Cable outer Ø	Reference
<b>WIRING FROM 150 TO 240 mm<sup>2</sup> CABLE GLAND INCLUDED</b>		
	40-50 mm	474A023550
	51-60 mm	474A023560
	61-70 mm	474A023570
	71-80 mm	474A023580
	81-90 mm	474A023590

On request: boxes for installation in ducts, boxes equipped with circuit breaker, earth-leakage switch, contactor,...

HANDLES	Cable outer Ø	Reference
<b>STRAIGHT</b>		
	46-50 mm	474A013-50
	51-55 mm	474A013-55
	56-60 mm	474A013-60
	61-65 mm	474A013-65
	66-70 mm	474A013-70
	71-75 mm	474A013-75
	76-80 mm	474A013-80
	81-85 mm	474A013-85
	86-90 mm	474A013-90

HANDLES	Cable outer Ø	Reference
<b>ANGLED 90°</b>		
	46-50 mm	474A913-50
	51-55 mm	474A913-55
	56-60 mm	474A913-60
	61-65 mm	474A913-65
	66-70 mm	474A913-70
	71-75 mm	474A913-75
	76-80 mm	474A913-80
	81-85 mm	474A913-85
	86-90 mm	474A913-90

## INFOS +

### STRAIGHT CONNECTION

use Ø 12 straight cable lugs and sleeves



3 cable lugs are delivered as a standard

### RIGHT ANGLE CONNECTION

Right angle connection using straight Ø 12 cable lugs and insulation sleeves




it is recommended to fit insulating sleeves to each lug.

ACCESSORIES AND OPTIONS	Reference
<b>KEY FOR LOCKING AND OPERATING PILOT CONTACTS</b>	
	473A393
<b>INLET LID</b>	
	474A126
<b>M12 CONNECTION PIECE*</b>	
	474A277

\*Wiring with straight cable lugs with terminals.


# DRAWINGS AND DIMENSIONS

PLUG ON 90° ANGLED HANDLE ON SOCKET OUTLET




A	B	C	E
471	301	196	145

PLUG ON STRAIGHT HANDLE ON SOCKET OUTLET



A	B	C	E
605	246	204	148

## SOCKET OUTLET ON WALL BOX




	A	B	C	E1	E2
95-150 mm <sup>2</sup>	713	510	389	460	458
150-240 mm <sup>2</sup>	1013	510	483	460	400/800



# 600 A

1 000 V  
U MAX / ■ ■ ■

## INDUSTRIAL PLUG PFC6



IP66  
IP67



95-240 mm<sup>2</sup><sup>(1)</sup>  
95-240 mm<sup>2</sup><sup>(2)</sup>



METAL



IK10



-40°C  
+60°C



2 AUX.  
+2 PIL.

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### OTHER FEATURES

Junction through mono or multi conductors cables

Auxiliary contacts (20 A/400 V)

2

Pilot contacts (20 A/400 V)

2

Flexible wiring auxiliaries/pilots

6 mm<sup>2</sup>

### SOCKET-OUTLET

female  
**PFC6**



**INLET** male  
**PFC6**



380-440 V AC	3P+E	4964013	4968013
220-250 V AC	380-440 V AC	3P+N+E	4964017
660-690 V AC		3P+E	4964193
380-400 V AC	660-690 V AC	3P+N+E	4964197
1000 V AC		3P+E	4964223

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

BOXES STAINLESS STEEL 316L	Cable outer Ø	Reference
<b>WIRING FROM 95 TO 150 mm<sup>2</sup> CABLE GLAND INCLUDED</b>		
	40-50 mm	496A023050
	51-60 mm	496A023060
	61-70 mm	496A023070
	71-80 mm	496A023080
	81-90 mm	496A023090

BOXES STAINLESS STEEL 316L	Cable outer Ø	Reference
<b>WIRING FROM 150 TO 240 mm<sup>2</sup> CABLE GLAND INCLUDED</b>		
	40-50 mm	496A023550
	51-60 mm	496A023560
	61-70 mm	496A023570
	71-80 mm	496A023580
	81-90 mm	496A023590

On request: boxes for installation in ducts, boxes equipped with circuit breaker, earth-leakage switch, contactor,...

HANDLES	Cable outer Ø	Reference
<b>STRAIGHT</b>		
	46-50 mm	496A013-50
	51-55 mm	496A013-55
	56-60 mm	496A013-60
	61-65 mm	496A013-65
	66-70 mm	496A013-70
	71-75 mm	496A013-75
	76-80 mm	496A013-80
	81-85 mm	496A013-85
	86-90 mm	496A013-90

HANDLES	Cable outer Ø	Reference
<b>ANGLED 90°</b>		
	40-50 mm	496A913-50
	51-60 mm	496A913-60
	61-70 mm	496A913-70
	71-80 mm	496A913-80
	81-90 mm	496A913-90

## INFOS +

### STRAIGHT CONNECTION

A right angled cable lug ( $\varnothing$  14) with insulated sleeve.



### RIGHT ANGLE CONNECTION

Straight cable lug ( $\varnothing$  14) with insulated sleeve.




it is recommended to fit  
insulating sleeves to each  
lug.

ACCESSORIES AND OPTIONS	Reference
<b>LOCKING KEY</b>	
	496A393
<b>INLET LID</b>	
	496A126


# DRAWINGS AND DIMENSIONS

PLUG ON 90° ANGLED HANDLE ON SOCKET OUTLET




A	B	C	E
540	373	266	190

PLUG ON STRAIGHT HANDLE ON SOCKET OUTLET



A	B	C	E
683	273	266	190

## SOCKET OUTLET ON WALL BOX



	A	B	C	E1	E2
95-150 mm <sup>2</sup>	713	510	390	460	458
150-240 mm <sup>2</sup>	1013	510	479	460	400/800





## SINGLE POLE CONNECTORS

75 A ➔ 250A

400 A

500 A

**CS**

**DSP400**

**CS1000**

Bayonet contact system

Self-cleaning contacts

GRP casing

IP66/IP67

GRP or metal casing

IP66/IP67

Visual and mechanical coding

Padlocking ring

GRP casing



MODEL	CURRENT	U MAX AC	MAX. NUM. AUX./PIL.
CS2	150A	50 V (Extra LV)	/
CS3	250A	50 V (Extra LV)	/
DSP400	400 A	500 V	2 PIL.
CS1000	500 A	1 000 V	/
SP	750 A	1 000 V	2 PIL.
DSP1250	1250 A	1 000 V	2 PIL.



750 A

SP

IP66/IP67

Visual and mechanical coding

Electromechanical interlocking system

Overmoulded GRP on metal casing

1250 A

DSP1250

IP66/IP67

Metal casing



DOWNLOAD ALL TECHNICAL SHEETS ON OUR  
WEBSITE **MARECHAL.COM**

#### SELECTION GUIDE

MATERIAL	IP	IK	PAGE
POLY	NA	IK08	112
POLY	NA	IK08	112
POLY METAL	IP66/IP67	IK09	116
POLY	IP66/IP67	IK08	124
POLY	IP66/IP67	IK08	130
METAL	IP66/IP67	IK10	132

# 75 A ➤ 250 A

50 V (EXTRA LV)  
U MAX

## SINGLE POLE POWER CONNECTOR CS



See below



GRP



IK08



-20° C  
+60° C

### OTHER FEATURES

Type CS	Wire cross-section (mm <sup>2</sup> )	I <sub>n</sub> rated current (A)	I <sub>max</sub> welding cycle (A) (A)	
			5 minutes cycles	
CS2	16	75	60 %	30 %
	25	100	100	150
	35	125	125	200
	50	150	150	250
CS3	50	150	200	300
	70	200	250	350
	95	250	300	400

\* Definition of 30% welding cycle: on a 5 min cycle, 30% of the time working (i.e. 1 min 30 s) and 70% off (i.e. 3 min 30 s).

**INLET**  
male with lug



**PLUG**  
male with lug



	<b>CS2</b>	<b>CS3</b>	<b>CS2</b>	<b>CS3</b>
Wire cross-section (mm <sup>2</sup> )				
16	4 2901 016		4 0201 016	
25	4 2901 030		4 0201 030	
35	4 2901 040		4 0201 040	
50	4 2901 050	4 3901 050	4 0201 050	4 0301 050
70		4 3901 075		4 0301 075
95		4 3901 100		4 0301 100
Screw type	4 2901 121	4 3901 121		

**SOCKET-OUTLET**  
female with lug



**COUPLER**  
**SOCKET** female  
with lug



	<b>CS2</b>	<b>CS3</b>	<b>CS2</b>	<b>CS3</b>
Wire cross-section (mm <sup>2</sup> )				
16	4 2401 016		4 2301 016	
25	4 2401 030		4 2301 030	
35	4 2401 040		4 2301 040	
50	4 2401 050	4 3401 050	4 2301 050	4 3301 050
70		4 3401 075		4 3301 075
95		4 3401 100		4 3301 100
Screw type	4 2401 121	4 3401 121		

## ADDITIONAL COPPER LUGS


**Lug choice depends on the cable :** the cross-section of the flexible cable mentioned in the table below is for information only. Please check dimensions as these may vary according to cable types and manufacturers.

Wiring (mm <sup>2</sup> )	Straight threaded M10*	Straight threaded M12*	Straight threaded M14*	Internal diameter (mm)	External diameter (mm)**
Flexible	Stranded	<b>CS2</b> <b>socket and coupler socket</b>	<b>CS3</b> <b>connector and plug</b>		
16	25	4 2301 416		6,6	9,5
25	35	4 2301 430		7,9	11
35	50	4 2301 440		9,2	12,5
50	70	4 2301 450	454A50D	11	15
70	95		454A70D	13,1	18
95	120		454A95D	14,5	19


\* Wiring with crimping lugs, according to NF C20-130 standard (for VDE 0220 standard, please contact us). Crimping: double hexagonal crimping is recommended.

\*\*Choose the crimping tool according to the external diameter of your lug.

# DRAWINGS AND DIMENSIONS


**SOCKET OUTLET**

	A	B	C	E
<b>CS2</b>	79	50	32	38
<b>CS3</b>	103	60	44	44

**PLUG**


	A	B
<b>CS2</b>	115	31
<b>CS3</b>	157	38

**CONNECTOR**



	A	B	C	E
<b>CS2</b>	89	50	32	38
<b>CS3</b>	146	60	44	44

**COUPLER SOCKET**



	A	B
<b>CS2</b>	152	31
<b>CS3</b>	204	38

400 A

## DSP400 SINGLE POLE CONNECTOR



### DSP400

- are single pole connectors which are safe, reliable and provide a high level of performance for all permanent high current applications. They withstand frequent overloads up to 400 A.

- Are robust connectors with outstanding durability.
- Are fitted with two pilot contacts for electrical interlocking.

### DSP400 SINGLE POLE CONNECTORS COMPLY WITH:

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation.

### THE HIGHEST POSSIBLE SAFETY

- IP4X/IPXXD (1 mm thread) socket to prevent any hazardous contact.
- Automatic IP66/IP67 watertightness.
- Two pilot contacts for electrical interlocking with an appropriate contactor.

### PERFORMANCES

- Thanks to the butt-contact technology, DSP400 withstands permanent current up to 400 A with 500 V AC or 750 V DC (600 kW).


### AN EASILY OPERABLE CONNECTOR

- Mechanical fool-proofing system between phases, neutral and earth.
- Visual identification by standard colours.
- Connection with terminal or threaded crimping lugs.

### DSP400 CHARACTERISATION

Permanent and non-intermittent on-load current permitted for a new DSP400, wired with an appropriate H 07 RN-F cable, and at a defined maximal ambient temperature.

- Tamb maxi : 60°C.
- Tamb maxi : 45°C.
- Tamb maxi : 30°C.



Up to 400 A/500 V

IP66/IP67

Temperature rating -40°C to +60°C



# 400 A

500 V  
U MAX

## SINGLE POLE POWER CONNECTOR DSP400

**NEW**

GRP OR METAL



500 V AC  
750 V DC



IP66  
IP67



50 - 240 mm<sup>2</sup> <sup>(1)</sup>  
70 - 300 mm<sup>2</sup> <sup>(2)</sup>



GRP  
METAL



IK09



-40 °C  
+60 °C



+2 PIL.



EMC  
METAL

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).  
300 mm<sup>2</sup> = 600 MCM.

### OTHER FEATURES

Pre-wired pilot circuit (4 mm<sup>2</sup>)

10 A/400 V

Live part protection

IP4X

Keying positions

7, mechanical and visual



**SOCKET-OUTLET** metal  
**DSP400**

**WITHOUT LUG**

**CONNECTOR** metal  
**DSP400**

**WITHOUT LUG**

**SOCKET-OUTLET** GRP  
**DSP400**

**WITHOUT LUG**

**CONNECTOR** GRP  
**DSP400**

**WITHOUT LUG**

### REFERENCES (UP TO 500 V AC)

#### COLOR coding

Type	Europe*	SOCKET-OUTLET metal DSP400	CONNECTOR metal DSP400	SOCKET-OUTLET GRP DSP400	CONNECTOR GRP DSP400
L1	Brown	3964001	3968001	3164001	3168001
L2	Black	3964002	3968002	3164002	3168002
L3	Grey	3964003	3968003	3164003	3168003
Neutral	Blue	396400N	396800N	316400N	316800N
Earth	Green	396400T	396800T	316400T	316800T
Positive	Red	396400P	396800P	316400P	316800P
Negative	Black	396400M	396800M	316400M	316800M

For products above 500 V  
(up to 1000 V)

contact us

contact us


contact us

contact us

\* The indicated references are valid for Europe and Japan. For other countries: add the suffix P80 for the USA/P67 for Australia and New Zealand/P40 for UK and South-Africa.

## COPPER LUGS

**Lug choice depends on the cable:** the cross-section of the flexible cable mentioned in the table below is for information only. Please check dimensions as these may vary according to cable types and manufacturers.



Wiring (mm <sup>2</sup> )		Straight with hole	Straight threaded M12	Internal diameter (mm)	External diameter (mm)*
Flexible	Stranded	Reference	Reference		
50	70	454A50C	454A50D	11	15
70	95	454A70C	454A70D	13,1	18
95	120	45AA95C	454A95D	14,5	19
120	150	454A12C	454A12D	16,2	21
150	185	454A15C	454A15D	18	24
185	240	454A18C	454A18D	20,6	26
240	300	454A24C	454A24D	23,1	29

For male contact, wiring with crimping lugs, according to NF C20-130 standard (for VDE 0220 standard, please contact us). Crimping: double hexagonal crimping is recommended.

\*Choose the crimping tool according to the external diameter of your lug.

OPTIONS	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	399A541
<b>INLET CAP IP66/IP67</b>	
	316A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	316A346
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Ref. socket poly + R
<b>ELECTROMAGNETIC COMPATIBILITY (EMC) </b>	
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.
<b>SPACER</b>	
	Depth 20 mm
	594M0-20

HANDLE	Input/ Cable outer Ø	Reference
<b>POLY HANDLE + POLY CABLE GLAND <sup>(1)</sup></b>		
	14-25 mm	514P032P
	18-32 mm	514P040P
	24-38 mm	514P050P
<b>POLY HANDLE (WITHOUT CABLE GLAND) <sup>(1)</sup></b>		
	M32	514P0M32
	M40	514P0M40
	M50	514P0M50
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND) <sup>(2)</sup></b>		
	M25	594P0M25
	M32	594P0M32
	M40	594P0M40
	M50	594P0M50

(1) Compatible for use with M12 straight threaded lugs up to reference 454A12D.

(2) Compatible for use with M12 straight threaded lugs. From reference 454A18D, a 20 mm spacer should be used.

SLEEVE		Reference
<b>POLY SLEEVE</b>		
	30°	514M3 <sup>[3]</sup>
	70°	514M7 <sup>[4]</sup>
<b>METAL SLEEVE</b>		
	0° [Straight]	594M0 <sup>[5]</sup>
	30°	594M3 <sup>[3]</sup>
	70°	594M7 <sup>[4]</sup>


(3) Compatible for use with all M12 straight threaded lugs.

(4) Compatible for use with all terminal lugs.

(5) Compatible for use with all lugs.


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C
252	228	105

COUPLER




A	B
405	228

PLUG ON 30° INCLINED SOCKET-OUTLET



A	B	C	E1	E2
278	280	105	87	122


PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	E
203	381	166	135


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
241	230	104	66

COUPLER




A	B
386	230

PLUG ON 30° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
279	257	102	136	88	122

PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	E1	E2
169	346	104	88	122

500 A

## CS1000 SINGLE POLE CONNECTOR



### CS1000

- are single pole connectors which are safe, reliable and provide a high level of performance for all high current applications. They withstand frequent overloads up to 500 A that depend on operating cycle.

- Are robust connectors with outstanding durability.

### CS1000 CONNECTORS COMPLY WITH:

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation.



USA and North America



Canada



Russia and Eurasia

### PERFECT SAFETY

- Socket-outlet: IP2X finger protection, without cap,
- IP66/IP67 watertightness with cap ; or upon connection,
- Locking mechanism preventing disconnection by accident.

### EASY CONNECTION

- Mechanical fool-proofing system between phases, neutral and earth,
- Standardised colour coding (according to local regulation),
- Replaceable crimping lug in case of cable damage.


### HIGH PERFORMANCE

- Thanks to its silver butt-contact technology the CS1000 connector withstands permanent current of 500 A/1 000 VAC or 1 500 V DC (wiring from 50 to 400 mm<sup>2</sup>).

### CS1000 CHARACTERISATION

Permanent and non-intermittent on-load current permitted for a new CS1000, wired with an appropriate H 07 RN-F cable, and at a defined maximal ambient temperature.

— Tamb maxi : 60°C.  
— Tamb maxi : 30°C.



Up to 500 A/1 000 V

IP66/IP67


Temperature rating -40 °C to +60 °C

Mechanical padlocking ring

IP66/IP67  
seal ring



Safety shutter  
(IP2X protection)



Bayonet operation

Mechanical keying position (Neutral here)


#### Spring Loaded Butt-Style Contacts

Ensures optimal contact force and superior electrical performance over thousands of operations.

#### Silver-Nickel Contact Material

Solid silver-nickel contact surfaces provide:

- superior conductivity,
- corrosion resistance,
- durability.



Protective Cap

Ensures IP66/IP67 watertightness when disconnected.

## 5 MECHANICAL KEYING POSITIONS (EUROPEAN COLOR CODING)

Earth



L1



L2/Negative



L3/Positive



Neutral



# 500 A

**1 000 V**  
U MAX / ■ ■ ■

## SINGLE POLE POWER CONNECTOR CS1000



(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### OTHER FEATURES

Icc : rated conditional short circuit current (kA)

20 kA during 250 ms

Number of operations

2000

Keying positions

5, mechanical and visual

### COLOR coding

**SOCKET-OUTLET**  
female  
**CS1000**  
**WITHOUT LUG**



**INLET** male  
**CS1000**  
**WITHOUT LUG**



Type	Europe*	Reference
L1	Brown	4534001
L2	Black	4534002
L3	Grey	4534003
Neutral	Blue	453400N
Earth	Green	453400T
Positive	Red	453400P
Negative	Black	453400M

\* The indicated references are valid for Europe and Japan. for UK, South-Africa and India : add the suffix P40.  
Color coding is as follows: L1 => Red / L2 => Yellow / L3 => Blue / Neutral => Black / Earth => Green / Positive => Red / Negative => Black.

<b>COLOR coding</b>		<b>SOCKET-OUTLET</b> female <b>CS1000</b> <b>WITHOUT LUG</b>	<b>INLET</b> male <b>CS1000</b> <b>WITHOUT LUG</b>
Type	<b>Australia and New Zealand</b>		
L1	Red		Reference
L2	White	4534001-P67	4538001-P67
L3	Blue	4534002-P67	4538002-P67
Neutral	Black	4534003-P67	4538003-P67
Earth	Green	453400N-P67	453800N-P67
Positive	Red	453400T-P67	453800T-P67
Negative	Black	453400P-P67	453800P-P67
		453400M-P67	453800M-P67
Type	<b>USA</b>		
L1	Black	4534001-P80	4538001-P80
L2	Red	4534002-P80	4538002-P80
L3	Blue	4534003-P80	4538003-P80
Neutral	White	453400N-P80	453800N-P80
Earth	Green	453400T-P80	453800T-P80
Positive	Red	453400P-P80	453800P-P80
Negative	Black	453400M-P80	453800M-P80

## COPPER LUGS

**Lug choice depends on the cable:** the cross-section of the flexible cable mentioned in the table below is for information only. Please check dimensions as these may vary according to cable types and manufacturers.



<b>Wiring (mm<sup>2</sup>)</b>	<b>Straight with hole</b>	<b>Straight threaded M12</b>	<b>Internal diameter (mm)</b>	<b>External diameter (mm)*</b>
Flexible	Stranded	Reference	Reference	
50	70	454A50C	454A50D	11
70	95	454A70C	454A70D	13,1
95	120	454A95C	454A95D	14,5
120	150	454A12C	454A12D	16,2
150	185	454A15C	454A15D	18
185	240	454A18C	454A18D	20,6
240	300	454A24C	454A24D	23,1
300	400	454A30C	454A30D	26,1
400	500	454A40C	454A40D	29,2


For male contact, wiring with crimping lugs, according to NF C20-130 standard [for VDE 0220 standard, please contact us]. Crimping: Double hexagonal crimping is recommended.

\*Choose the crimping tool according to the external diameter of your lug.

<b>OPTIONS</b>	<b>Reference</b>	<b>SLEEVE</b>	<b>Reference</b>
<b>PADLOCKING RING</b>			
	453A843		
<b>SLEEVE INCLINED 30° WITH ADAPTER PLATE</b>			
	The inclined sleeve is recommended to reduce cable weight effect.	453A027	
<b>HANDLE</b>	<b>Input/ Cable outer Ø</b>	<b>Reference</b>	
<b>HANDLE STRAIGHT</b>			
	M32/14-25 mm	453A753	
	M40/18-32 mm	453A783	
<b>HANDLE + MANDATORY ADAPTATION PLATE</b>			
Designed for lugs with part numbers starting from 454A24D.			
	454A753 (M50/17-38 mm) +	453A457-SP	
	454A783 (M63/35-48 mm) +	453A457-SP	


# DRAWINGS AND DIMENSIONS

## PLUG ON SOCKET-OUTLET



A	B	C	D
231	56	56	160


## PLUG ON 30° INCLINED SOCKET-OUTLET VERSION WITH HANDLE REF. 453A783 & 453A753



A	B	C	D	E1	E2
257	202	77	108	64	95

**PLUG ON 30° INCLINED SOCKET-OUTLET**

**VERSION WITH HANDLE REF. 454A783 + 453A457-SP (A, B) & 453A753 + 453A457-SP (F, G)**



A	B	C	D	E1	E2	F	G
305	238	77	108	63	95	263	213

750 A

## SP SINGLE POLE CONNECTOR



### SP

- are single pole connectors which are safe, reliable and provide a high level of performance for all high current applications. They withstand frequent overloads up to 750 A that depend on operating cycle.

- Are robust connectors with outstanding durability.
- Are fitted with an electromechanical interlocking and an electrical interlocking with pilot contact circuit.

### SP SINGLE POLE CONNECTORS COMPLY WITH:

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation.



Canada



Russia  
and Eurasia



Marine



Military  
(Mil-S-901D)

### THE HIGHEST POSSIBLE SAFETY


- IP2X socket-outlet when cap removed,
- Automatic IP66/IP67 watertightness when plug is connected.

### AN EASILY OPERABLE CONNECTOR

- Straight insertion of the plug into the socket-outlet without any rotation,
- Mechanical fool-proofing system between phases, neutral and earth,
- Visual identification by standard colours,
- Screwed crimping lugs facilitate cable replacement.

### PERFORMANCES

- Thanks to the butt-contact principle, the SP withstands continuously up to 750 A/1000 V AC or 1500 V DC (70 mm<sup>2</sup> to 630 mm<sup>2</sup> conductors), withstands at least 2 000 operations.




Reliable mechanical and electrical interlocking with pilot contact circuit.

### SP CHARACTERISATION

Permanent and non-intermittent on-load current permitted for a new SP, wired with an appropriate H 07 RN-F cable, and at a defined maximal ambient temperature.

- Tamb maxi : 60°C.
- Tamb maxi : 30°C.



Up to 750 A/1 000 V


IP66/IP67

Temperature rating -40 °C to +60 °C


Electromechanical interlocking system



#### INTERLOCKING ELECTRICAL WIRING DIAGRAM: INCREASED POWER WITH PARALLEL CONNECTION



#### INTERLOCKING ELECTRICAL WIRING DIAGRAM: LAST CONNECTION COMPLETES THE CIRCUIT



# 750 A

1 000 V  
U MAX / I

## SINGLE POLE POWER CONNECTOR SP



1 000 V AC  
1 500 V DC



IP66  
IP67



SEE  
TABLE



GRP



IK08



-40 °C  
+60 °C



+2 PIL.



### LEVER MECHANISM

**TO BE ORDERED SEPARATELY**

Compatible with socket  
or inlet since 2018

Lever mechanism :  
454A876

Draw base : 454A396



### OTHER FEATURES

Rated current

Consult us for intensities higher than 700 A

Short-circuit current Icc

20 kA for 250 ms

Number of operations

2000

Pre-wired pilot circuit

10 A/250 V

### COLOR coding

**SOCKET-OUTLET**  
female  
**SP**  
**WITHOUT LUG**



**INLET** male  
**SP**  
**WITHOUT LUG**



Type	Europe*	Reference	Reference
L1	Brown	4544001	4548001
L2	Black	4544002	4548002
L3	Grey	4544003	4548003
Neutral	Blue	454400N	454800N
Earth	Green	454400T	454800T
Positive	Red	454400P	454800P
Negative	Black	454400M	454800M

\* The indicated references are valid for Europe and Japan. for UK, South Africa and India : add the suffix P40.

Color coding is as follows: L1 => Red / L2 => Yellow / L3 => Blue / Neutral => Black / Earth => Green / Positive => Red / Negative => Black.

**SOCKET-OUTLET**  
 female  
**SP (700 A)**  
**WITHOUT LUG**

**INLET male**  
**SP (700 A)**  
**WITHOUT LUG**
**COLOR** coding

Type	Australia and New Zealand	Reference	Reference
L1	Red	4544001-P67	4548001-P67
L2	White	4544002-P67	4548002-P67
L3	Blue	4544003-P67	4548003-P67
Neutral	Black	454400N-P67	454800N-P67
Earth	Green	454400T-P67	454800T-P67
Positive	Red	454400P-P67	454800P-P67
Negative	Black	454400M-P67	454800M-P67

**TYPE** USA

Type	USA	Reference	Reference
L1	Black	4544001-P80	4548001-P80
L2	Red	4544002-P80	4548002-P80
L3	Blue	4544003-P80	4548003-P80
Neutral	White	454400N-P80	454800N-P80
Earth	Green	454400T-P80	454800T-P80
Positive	Red	454400P-P80	454800P-P80
Negative	Black	454400M-P80	454800M-P80

**LUGS**

**Lug choice depends on the cable:** the cross-section of the flexible cable mentioned in the table below is for information only. Please check dimensions as these may vary according to cable types and manufacturers.



Wiring (mm <sup>2</sup> )	Strand	Reference	Reference	Internal diameter (mm)	External diameter (mm)*
Flexible	Stranded				
50	70	454A50C	454A50D	11	15
70	95	454A70C	454A70D	13.1	18
95	120	45AA95C	454A95D	14.5	19
120	150	454A12C	454A12D	16.2	21
150	185	454A15C	454A15D	18	24
185	240	454A18C	454A18D	20.6	26
240	300	454A24C	454A24D	23.1	29
300	400	454A30C	454A30D	26.1	32
400	500	454A40C	454A40D	29.2	40
500	630	454A500C	454A500D	33.2	42
630	/	/	454A63D	37.6	52

For male contact, wiring with crimping lugs, according to NF C20-130 standard (for VDE 0220 standard, please contact us). Crimping: Double hexagonal crimping is recommended.

\*Select the crimping tool according to the outside diameter of your lug.

OPTIONS	Reference
<b>M12 CONNECTION PIECE*</b>	
	474A277

\*Wiring with straight cable lugs with terminals.


HANDLE	Input/ Cable outer Ø	Reference
<b>HANDLE STRAIGHT</b>		
	M50 17-38 mm	454A753
	M63 35-48 mm	454A783

SLEEVE	Reference
<b>SLEEVE INCLINED METAL 45°</b>	
	The inclined sleeve is recommended to reduce cable weight effect. 454A027

ACCESSORIES	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>	
	454A843

# DRAWINGS AND DIMENSIONS


PLUG ON SOCKET-OUTLET



A

<b>SP M50</b>	265
<b>SP M63</b>	291

PLUG ON 45° INCLINED SOCKET OUTLET



	A	B	C	D	E1	E2
<b>SP M50</b>	254	306	105	128	89	112
<b>SP M63</b>	279	330	105	128	89	112



1 250 A

## DSP1250 SINGLE POLE CONNECTOR



### DSP1250

- are single pole connectors which are safe, reliable and provide a high level of performance for all permanent high current applications. They withstand frequent overloads up to 1250 A.

- Are robust connectors with outstanding durability.
- Are fitted with a mechanical interlocking system.
- Are fitted with two pilot contacts for electrical interlocking.

### DSP1250 SINGLE POLE CONNECTORS COMPLY WITH:

- the European Directives Low Voltage, RoHS (affixing of CE marking), REACH European Regulation.

### THE HIGHEST POSSIBLE SAFETY

- IP2X/IPXXB (contact finger) socket to prevent any hazardous contact.
- Automatic IP66/IP67 watertightness.
- Mechanical locking system that prevents from inadvertent on-load breaking.
- Two pilot contacts for electrical interlocking with an appropriate contactor.

### AN EASILY OPERABLE CONNECTOR

- Mechanical fool-proofing system between phases, neutral and earth,
- Visual identification by standard colours,
- Connection with terminal or threaded crimping lugs.


### PERFORMANCES

- Thanks to the butt-contact technology, DSP1250 withstands permanent current up to 1 250 A with 1 000 V AC (1,2 MW) or 1 500 V DC (1,8 MW).

### DSP1250 CHARACTERISATION

Permanent and non-intermittent on-load current permitted for a new DSP1250, wired with an appropriate H 07 RN-F cable, and at a defined maximal ambient temperature.

- Tamb maxi : 60°C.
- Tamb maxi : 45°C.
- Tamb maxi : 30°C.



Up to 1 250 A/1 000 V

IP66/IP67

Temperature rating -40 °C à +60 °C

Electromechanical interlocking system



# 1250A

1 000 V  
U MAX

## SINGLE POLE POWER CONNECTOR DSP1250



1 000 V AC  
1 500 V DC



IP66  
IP67



50 - 630 mm<sup>2</sup><sup>(1)</sup>  
70 - 630 mm<sup>2</sup><sup>(2)</sup>



METAL



IK10



-40 °C  
+60 °C



+2 PIL.



EMC

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).  
630 mm<sup>2</sup> = 1250 MCM.

### OTHER FEATURES

Mechanical interlock	standard
Pre-wired pilot circuit (2.2 mm <sup>2</sup> )	5 A/400 V
Live part protection	IP2X
Keying positions	7, mechanical and visual

### REFERENCES (UP TO 690 V AC)



SOCKET-OUTLET  
metal **DSP1250**  
**WITHOUT LUG**



CONNECTOR metal  
**DSP1250**  
**WITHOUT LUG**



Each inlet should be connected to a wall box, a sleeve, a handle or a spacer to ensure correct operation of the closing mechanism.

Type	Europe*		
L1	Brown	3924001	3928001
L2	Black	3924002	3928002
L3	Grey	3924003	3928003
Neutral	Blue	392400N	392800N
Earth	Green	392400T	392800T
Positive	Red	392400P	392800P
Negative	Black	392400M	392800M
For products above 690 V (up to 1000 V)		Reference + 155	Reference + 155

\* The indicated references are valid for Europe and Japan. For other countries: add the suffix P80 for the USA/P67 for Australia and New Zealand/P40 for UK and South-Africa.

## COPPER LUGS

**Lug choice depends on the cable:** the cross-section of the flexible cable mentioned in the table below is for information only. Please check dimensions as these may vary according to cable types and manufacturers.



Wiring (mm <sup>2</sup> )		Straight with hole	Straight threaded M12	Internal diameter (mm)	External diameter (mm)*
Flexible	Stranded	Reference	Reference		
50	70	454A50C	454A50D	11	15
70	95	454A70C	454A70D	13.1	18
95	120	45AA95C	454A95D	14.5	19
120	150	454A12C	454A12D	16.2	21
150	185	454A15C	454A15D	18	24
185	240	454A18C	454A18D	20.6	26
240	300	454A24C	454A24D	23.1	29
300	400	454A30C	454A30D	26.1	32
400	500	454A40C	454A40D	29.2	40
500	630	454A500C	454A500D	33.2	42
630	/	/	454A63D	37.6	52

For male contact, wiring with crimping lugs, according to NF C20-130 standard (for VDE 0220 standard, please contact us). Crimping: Double hexagonal crimping is recommended.

\*Choose the crimping tool according to the external diameter of your lug.

OPTIONS	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	399A541
<b>INLET CAP IP66/IP67</b>	
	392A426
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Socket-outlet ref.+R
<b>ELECTROMAGNETIC COMPATIBILITY (EMC)</b>	
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.
<b>SPACERS (BETWEEN THE WALL BOX OR PANEL)</b>	
	Depth 68 mm
	Depth 115 mm
<b>PADLOCKING/ELECTRO-MECHANICAL INTERLOCKING</b>	
	Socket-outlet reference+MIL. Check out the details on page 312

SLEEVE		Reference
METAL SLEEVE		
	60°	596M6 <sup>[1]</sup>
<b>HANDLE</b>		
ELASTOMER HANDLE WITH GLAND <sup>(3)</sup>		
	25-35 mm	556P0D35
	35-45 mm	556P0D45
	45-49 mm	556P0D49
<b>METAL HANDLE WITH INTEGRATED CABLE CLAMP <sup>(4)</sup></b>		
	40-50 mm	5K6P0D50
	51-60 mm	5K6P0D60
	61-70 mm	5K6P0D70
	71-80 mm	5K6P0D80
	81-90 mm	5K6P0D90
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND) <sup>(4)</sup></b>		
	M40	5K6P0M40L
	M50	5K6P0M50L
	M63	5K6P0M63L
	M75	5K6P0M75L
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND) - LARGE SIZE <sup>(4)</sup></b>		
	M63	796P0M63
	M75	796P0M75


[1] Compatible for use with all straight terminal lugs.

[2] Compatible for use with M12 straight threaded lugs. From reference 454A40D, a 68 mm minimum spacer should be used.


[3] Compatible for use with M12 straight threaded lugs. From reference 454A24D, a 68 mm minimum spacer should be used.

[4] Compatible for use with all M12 straight threaded lugs.

# DRAWINGS AND DIMENSIONS


**PLUG**

A	B	C
475	147	147

**COUPLER SOCKET**

A	B	C
463	188	340

**SOCKET OUTLET INCLINED AT 60°**



# MULTICONTACT CONNECTORS

**7 CONTACTS**  
25 A

**PN7C**

**7 CONTACTS**  
50 A/100 A

**DS7C3/6**

**9 CONTACTS**  
30 A

**DN9C**

**12 CONTACTS**  
16 A

**PN12C**



MODEL	MAX NB OF CONTACTS	CURRENT	U MAX AC
PN7C	6+E (screw-type)	25 A	500 V
DS7C3	6+E (screw-type)	50 A	500 V
DS7C6	6+E (screw-type)	100 A	500 V
DN9C	8+E (screw-type)	30 A	415 V
PN12C	11+E (welding/crimping)	16 A	480 V
DSN12C	11+E (welding/crimping)	16 A	480 V
DN20C	19+E (screw-type)	25 A	415 V
DSN24C	23+E (welding/crimping)	16 A	480 V
DSN37C	36+E (welding/crimping)	16 A	480 V

DOWNLOAD ALL TECHNICAL SHEETS ON OUR  
WEBSITE **MARECHAL.COM**

## SELECTION GUIDE

**12 CONTACTS**  
**16 A**

**DSN12C**



**20 CONTACTS**  
**25 A**

**DN20C**



**24 CONTACTS**  
**16 A**

**DSN24C**



**37 CONTACTS**  
**16 A**

**DSN37C**



MULTICONTACT

MATERIAL	IP	EMC	IK	PAGE
POLY METAL	IP66/IP67	Yes (metal)	IK09	144
METAL	IP66/IP67	Yes	IK09	148
POLY METAL	IP66/IP67	Yes (metal)	IK09	152
METAL	IP54/IP55	Yes	IK09	156
POLY METAL	IP66/IP67	Yes (metal)	IK09	160
POLY	IP66/IP67	/	IK09	164
METAL	IP54/IP55	/	IK09	168
POLY	IP66/IP67	/	IK09	172
POLY	IP66/IP67	/	IK09	176

12 ➡ 37 CONTACTS

# CRIMPING CONTACTS

## FOR PN12C/DSN12C/DSN24C/DSN37C

### ECONOMIC AND TECHNICAL ADVANTAGES

Crimping ensures an economical and sustainable solution through installation time saving and quality of connection.

- No need for soldering performance qualifications.
- High resistance to vibrations.
- Handling more than 5000 operations: a high durability and quality of connection guaranteed.

ACCESSORIES AND OPTIONS	DESIGNATION	REFERENCE
	Bag of 13 females contacts	01AA213
	Bag of 13 males contacts 01AA113 (PN12C/DSN12C) 61CA113 (DSN24C/DSN37C)	
	Multi-Contact removal tool	61CA593
	European crimping tool	61CA500
	Helavia sleeve expansion tool	61CA400
	Bag of 13 heat shrink insulation sleeves	61CA083

### FAST WIRING

- Cable conductors: 1 mm<sup>2</sup> to 2,5 mm<sup>2</sup>
- Before wiring, add a heat-shrink sleeve or insulating sleeve on each conductor..
- After wiring, cover the visible portion of the contact with the sleeve.
- Crimp the contact with a KNIPEX crimping tool P/N° 61CA500 or a GREENLEE crimping tool P/N° 45505.
- Use the 4 mm<sup>2</sup> footprint whatever the conductor cross-section.
- Perform double crimping in compliance with NF C 20-130 and CEI 60352-2 standards.
- Conductors can equally be soldered.

### INFOS +

Leaving 2 contacts unused can give 9 different keying positions (on socket outlet side or mobile plug side) using the two specific stopping plugs supplied.

# SIMPLE ASSEMBLY AND DISASSEMBLY

## ASSEMBLY

To insert contacts when they have been wired is simple.  
Push wired contact into rear of insulator until it stops to complete the installation.




## DISASSEMBLY


To remove, use the tool provided.  
Push tool from front onto contact until tool stops.  
Contact is then released at rear of insulator.



Socket-outlet side



Connector side



# 7 CONTACTS

25 A  500 V  
U MAX

## MULTICONTACTS CONNECTORS PN7C



IP66  
IP67



1-4 mm<sup>2</sup> <sup>(1)</sup>  
1-6 mm<sup>2</sup> <sup>(2)</sup>



GRP  
METAL



IK09



-40 °C  
+60 °C



EMC  
METAL

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### OTHER FEATURES

Σ of currents (contacts)

≤ 130 A

Terminals wiring

screw-type



**SOCKET-OUTLET**  
female  
**PN7C**



**INLET** male  
**PN7C**



GRP devices are not compatible with metal devices.

50 V AC	6P (16 A)	01P4060	01P8060
50 V AC	7P (16 A)	01P4070	01P8070
500 V AC	5P+E (25 A)	01P4051	01P8051
500 V AC	6P+E (16 A)	01P4061	01P8061



**SOCKET-OUTLET**  
female  
**PN7C**



**INLET** male  
**PN7C**



For a black colour GRP housing replace the second reference character with 5.


50 V AC	6P (16 A)	09P4060	09P8060
50 V AC	7P (16 A)	09P4070	09P8070
480 V AC	5P+E (25 A)	09P4051	09P8051
480 V AC	6P+E (16 A)	09P4061	09P8061

OPTIONS	Reference
<b>LOCKING FOR 1 PADLOCK Ø 4 mm (WITHOUT SHAFT)</b>	
	Ref. + 843
<b>SCREW LOCKING IMPRINT BTR 2,5</b>	
	Ref. + 22
<b>INLET CAP IP66/IP67</b>	
	01NA426
<b>REVERSED INTERIOR AND CONTACTS</b>	
	The connector is supplied with a rubber inlet cap.
Ref. conn. + 001 Ref. socket + 001	
<b>180° OPENING LID</b>	
	Ref. socket + 10
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Socket-outlet ref.+R
<b>180° OPENING + SELF-RETURNING LID</b>	
	Ref. socket + 18
<b>ELECTROMAGNETIC COMPATIBILITY (EMC) ● NEW</b>	
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.
<b>PRODUCTS AVAILABLE IN BLACK ●</b>	
The black dot means these products are also available in black color. Replace the second character of the product reference with 5	
<b>PRODUCT WITH ANTI-BACTERIAL TREATMENT ● NEW</b>	
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.	

BOXES	$\angle x^\circ$	Input	Ref.
<b>POLY BOX ●</b>			
	0° [Straight]	M20	511B0M20
	0° [Straight]	M25	511B0M25
	30°	M20	511B3M20
	30°	M25	511B3M25
<b>POLY BOX + POLY SLEEVE</b>			
	70°	Without hole	511C7000
	70°	Hole Ø 20	511C7M20
Earth bar ref. : 51AA089	70°	Hole Ø 25	511C7M25
	70°	Hole Ø 32	511C7M32
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M20	511C3M20
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE ●</b>			
	45°	M20	591C4M20
	45°	M25	591C4M25
	45°	M32	591C4M32
Cable glands are not delivered with the boxes.			
HANDLE	Input/ Cable outer Ø	Ref.	
<b>POLY HANDLE WITH GLAND ● ●</b>			
	9-18 mm	511P0D18	
	5-21 mm	511P0D21	
	9-18 mm	511P6D18	
<b>POLY HANDLE + POLY CABLE GLAND ● ●</b>			
	5-12 mm	511P020P	
	9-18 mm	511P025P	
	14-25 mm	511P032P	
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>			
	7-13 mm	591P020M	
	8-16 mm	591P025M	
	16-24 mm	591P032M	
<b>POLY HANDLE (WITHOUT CABLE GLAND) ●</b>			
	M20	511P0M20	
	M25	511P0M25	
	M32	511P0M32	
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND) ●</b>			
	M20	591P0M20	
	M25	591P0M25	
	M32	591P0M32	


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




	A	B	C	E
<b>Straight handle</b>	127	140	58	42
<b>Angled handle</b>	117	138	61	42

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




	A	B	C	D	E1	E2
<b>Straight handle</b>	178	176	68	90	36/56	78
<b>Angled handle</b>	153	176	68	90	36/56	78

## PLUG ON 30° INCLINED SOCKET-OUTLET



	A	B	C	D	E1	E2
<b>Straight handle</b>	160	170	77	108	63	95
<b>Angled handle</b>	133	165	77	108	63	95

## COUPLER




	A	B	C
<b>Straight handle</b>	208	132	58

# 7 CONTACTS

50 A  500 V  
U MAX

## DECONTACTOR™ DS7C3



(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Comply with IEC/EN 60309-1 standards

50 A/500 V

Load-break capability according to IEC/EN 60947-3/AC-22

50 A/500 V

### OTHER FEATURES

Terminals wiring

screw-type

Flexible and stranded wiring (min.-max.)

2,5-10 mm<sup>2</sup>



**SOCKET-OUTLET**  
female  
**DS7C3**



**INLET** male  
**DS7C3**



50 A/max 500 V AC

6P+E

3934561

3938561

50 A/max 500 V AC  
Auxiliaries 10 A/400 V

6P+E+3 aux.

3934561972

3938561972



**SOCKET-OUTLET**  
female  
**DS7C3**



**INLET** male  
**DS7C3**



50 A/max 500 V AC

6P+E

3934561

3938561

50 A/max 500 V AC  
Auxiliaries 10 A/400 V

6P+E+3 aux.

3934561972

3938561972

OPTIONS	Reference		
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>			
	Socket-outlet ref. +843		
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>			
	399A541		
<b>LARGER RELEASE BUTTON</b>			
	Ref. socket +453		
<b>INLET CAP IP66/IP67</b>			
	316A426		
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>			
	316A346		
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>			
	Ref. socket poly + R		
<b>IP55 METAL LOCKABLE SELF-CLOSING LID FOR INLET</b>			
	396A226		
<b>ELECTROMAGNETIC COMPATIBILITY (EMC)</b>			
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.		
<b>SELF-EJECTION</b>			
	See page 192		
HANDLE	Input/Cable outer Ø	Reference	Self-ejection
<b>ELASTOMER HANDLE WITH GLAND</b>			
	18-25 mm	554P0D25L	Ref. +443
	25-35 mm	554P0D35L	Ref. +443
	35-45 mm	554P0D45L	Ref. +443
	45-49 mm	554P0D49L	Ref. +443
<b>POLY HANDLE WITH GLAND</b>			
	13-35 mm	514P0D35	/
<b>POLY HANDLE + POLY CABLE GLAND</b>			
	14-25 mm	514P032P	Ref. +443
	18-32 mm	514P040P	Ref. +443
	24-38 mm	514P050P	Ref. +443
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b>			
	M32	514P0M32	Ref. +443
	M40	514P0M40	Ref. +443
	M50	514P0M50	/
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M25	594P0M25	/
	M32	594P0M32	/
	M40	594P0M40	/
	M50	594P0M50	/

HANDLE	Input/Cable outer Ø	Reference
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>		
	8-16 mm	594P025M
	16-24 mm	594P032M
	22-32 mm	594P040M
	34-44 mm	594P050M


BOXES	$\Delta x^\circ$	Input	Reference
<b>POLY BOX</b>			
	30°	M32	514B3M32
	30°	M40	514B3M40
<b>METAL BOX (+ EARTHING WIRE)</b>			
	20°	M25	594B2M25
	20°	M32	594B2M32
	20°	M40	594B2M40
<b>POLY BOX + POLY SLEEVE</b>			
	70°	Without hole	514C7000
	70°	Ø 32 mm drill hole	514C7M32
Earth bar ref. : 51AA089	70°	Ø 40 mm drill hole	514C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M25	514C3M25
	30°	M32	514C3M32
	30°	M40	514C3M40
	30°	M50	514C3M50
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M25	594C3M25
	30°	M32	594C3M32
	30°	M40	594C3M40
	30°	M50	594C3M50
	0° [Straight]	M25	594C0M25
	0° [Straight]	M32	594C0M32
	0° [Straight]	M40	594C0M40
	0° [Straight]	M50	594C0M50
	70°	M25	594C7M25
	70°	M32	594C7M32
	70°	M40	594C7M40
	70°	M50	594C7M50

Cable glands are not delivered with the boxes.

SLEEVE	$\Delta x^\circ$	Reference	
		POLY	METAL
	0° [Straight]	/	594M0
	30°	514M3	594M3
	70°	514M7	594M7


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
203	175	95	66

COUPLER




A	B
309	127

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




A	B	C	E1	E2
260	260	105	88	122

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
242	333	178	166	157	146

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
279	257	102	136	88	122

A	B	C	E1	E2
169	346	104	88	88



# 7 CONTACTS

100 A  500 V  
U MAX

## CONNECTOR DS7C6



(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### OTHER FEATURES

Terminals wiring

screw-type

Stranded or flexible auxiliary wiring (min.-max.)

2 mm<sup>2</sup>



Finger drawplates  
included



**SOCKET-OUTLET**  
female  
**DS7C6**



**INLET** male  
**DS7C6**



100 A/max 500 V AC	6P+E	3164561	3168561
Auxiliaries 10 A/500 V AC	+ 2 contacts	Ref. + 262	Ref. + 262
Auxiliaries 10 A/500 V AC	+ 4 contacts	Ref. + 264	Ref. + 264
Auxiliaries 10 A/500 V AC	+ 6 contacts	Ref. + 976	Ref. + 976



**SOCKET-OUTLET**  
female  
**DS7C6**



**INLET** male  
**DS7C6**



100 A/max 500 V AC	6P+E	3964561	3968561
Auxiliaries 10 A/500 V AC	+ 2 contacts	Ref. + 262	Ref. + 262
Auxiliaries 10 A/500 V AC	+ 4 contacts	Ref. + 264	Ref. + 264
Auxiliaries 10 A/500 V AC	+ 6 contacts	Ref. + 976	Ref. + 976

OPTIONS	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	399A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	316A426
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Ref. socket poly + R
<b>IP55 METAL LOCKABLE SELF-CLOSING LID FOR INLET</b>	
	396A226
<b>ELECTROMAGNETIC COMPATIBILITY (EMC)</b> <span style="background-color: #d9534f; color: white; padding: 2px;">NEW</span>	
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.

HANDLE	Input/Cable outer Ø	Reference
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>		
	8-16 mm	594P025M
	16-24 mm	594P032M
	22-32 mm	594P040M
	34-44 mm	594P050M

BOXES	$\Delta x^\circ$	Input	Reference
<b>POLY BOX</b>			
	30°	M32	514B3M32
	30°	M40	514B3M40
<b>METAL BOX (+ EARTHING WIRE)</b>			
	20°	M25	594B2M25
	20°	M32	594B2M32
	20°	M40	594B2M40
<b>POLY BOX + POLY SLEEVE</b>			
	70°	Without hole	514C7000
Earth bar ref. : 51AA089	70°	Ø 32 mm drill hole	514C7M32
	70°	Ø 40 mm drill hole	514C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M25	514C3M25
	30°	M32	514C3M32
	30°	M40	514C3M40
	30°	M50	514C3M50
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M25	594C3M25
	30°	M32	594C3M32
	30°	M40	594C3M40
	30°	M50	594C3M50


HANDLE	Input/ Cable outer Ø	Reference
<b>ELASTOMER HANDLE WITH GLAND</b>		
	18-25 mm	554P0D25L
	25-35 mm	554P0D35L
	35-45 mm	554P0D45L
	45-49 mm	554P0D49L
<b>POLY HANDLE WITH GLAND</b>		
	13-35 mm	514P0D35
<b>POLY HANDLE + POLY CABLE GLAND</b>		
	14-25 mm	514P032P
	18-32 mm	514P040P
	24-38 mm	514P050P
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b>		
	M32	514P0M32
	M40	514P0M40
	M50	514P0M50
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>		
	M25	594P0M25
	M32	594P0M32
	M40	594P0M40
	M50	594P0M50

SLEEVE	$\Delta x^\circ$	Reference
		POLY      METAL
	0° (Straight)	/ 594M0
	30°	514M3 594M3
	70°	514M7 594M7

Cable glands are not delivered with the boxes.


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
257	238	141	66

COUPLER




A	B
404	238

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




A	B	C	E1	E2
353	273	150	125	97

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
252	374	145	156	125	97

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	E1	E2
278	263	141	87	122

A	B	C	E1	E2
177	365	141	87	122



# 9 CONTACTS

30 A   
U MAX / 

## MULTICONTACTS CONNECTORS DN9C



IP54  
IP55



1-6 mm<sup>2</sup> <sup>(1)</sup>  
1,5-10 mm<sup>2</sup> <sup>(2)</sup>



METAL



IK09



-40 °C  
+60 °C



EMC

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### OTHER FEATURES

IP protection plug connected

IP54

IP protection lid closed

IP55

Σ of currents (contacts)

≤ 210 A

Terminals wiring

screw-type

**SOCKET-OUTLET**  
female  
**DN9c**



**INLET** male  
**DN9c**



415 V AC

8P+E

1914081

1918081

► The contacts can be assigned either power or signal.


OPTIONS	Reference	
<b>LOCKING PIN FOR 3 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>		
	Ref. + 844	
<b>LARGER RELEASE BUTTON</b>		
	Ref. socket + 453	
<b>INLET CAP</b>		
	191A126	
<b>180° OPENING LID</b>		
	Ref. socket + 10	
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>		
	Socket-outlet ref.+R	
<b>180° OPENING + SELF-RETURNING LID</b>		
	Ref. socket + 18	
<b>IP66/IP67 SOCKET-OUTLET AND INLET</b>		
	Ref. + 600	
<b>ELECTROMAGNETIC COMPATIBILITY (EMC) </b>		
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.	
<b>PRODUCT WITH ANTI-BACTERIAL TREATMENT </b>		
	This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.	
HANDLE	Input/ Cable outer Ø	Ref.
<b>POLY HANDLE WITH GLAND </b>		
	10-30 mm	513P0D30
<b>POLY HANDLE + POLY CABLE GLAND </b>		
	9-18 mm	513P025P
	14-25 mm	513P032P
	18-32 mm	513P040P
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>		
	7-13 mm	593P020M
	8-16 mm	593P025M
	16-24 mm	593P032M
	22-32 mm	593P040M
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b>		
	M20	513P0M20
	M25	513P0M25
	M32	513P0M32
	M40	513P0M40
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND) </b>		
	M20	593P0M20
	M25	593P0M25
	M32	593P0M32
	M40	593P0M40

BOÎTIERS		Input	Ref.
<b>POLY BOX</b>			
	30°	M25	513B3M25
<b>METAL BOX (+ EARTHING WIRE) </b>			
	20°	M20	593B2M20
	20°	M25	593B2M25
	20°	M32	593B2M32
<b>POLY BOX + POLY SLEEVE</b>			
	70°	Without hole	513C7000
	70°	Ø 25 mm drill hole	513C7M25
	70°	Ø 32 mm drill hole	513C7M32
	70°	Ø 40 mm drill hole	513C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M20	513C3M20
	30°	M25	513C3M25
	30°	M32	513C3M32
	30°	M40	513C3M40
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE </b>			
	30°	M20	593C3M20
	30°	M25	593C3M25
	30°	M32	593C3M32
	30°	M40	593C3M40
	0° [Straight]	M20	593C0M20
	0° [Straight]	M25	593C0M25
	0° [Straight]	M32	593C0M32
	0° [Straight]	M40	593C0M40
	70°	M20	593C7M20
	70°	M25	593C7M25
	70°	M32	593C7M32
	70°	M40	593C7M40
<b>SLEEVE</b>			
<b>POLY SLEEVE</b>			
	30°		513M3
	70°		513M7
<b>METAL SLEEVE </b>			
	0° [Straight]		593M0
	30°		593M3
	70°		593M7

Cable glands are not delivered with the boxes.


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
184	156	80	55

COUPLER




A	B
285	156

PLUG ON 30° WALL MOUNTED SOCKET OUTLET







A	B	C	D	E1	E2
239	218	89	100	77	88

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
200	265	110	114	94	70

PLUG ON 30° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
210	176	77	108	63	95

A	B	C	D	E1	E2
141	262	77	108	63	95



# 12 CONTACTS

16 A

480 V  
U MAX

## MULTICONTACT CONNECTORS PN12C



(1) Flexible wiring (min.-max.).

### OTHER FEATURES

Impulse withstand voltage	5 kV
Contact resistance	< 2 mΩ
Permitted current range	4-20 mA/16 A
Σ of currents (contacts)	≤ 110 A
Terminals wiring	To weld/crimp
Butt contacts	Silver-nickel tips
Contact protection	Silvering
Load cycles	> 5 000 cycles
Vibrations	Frequency 5-1000 Hz, 1g/90 minutes on each critical frequency according to IEC 6068-2-6

For a black colour GRP housing replace the second reference character with 5 (GRP version only).

GRP devices are not compatible with metal devices.

**SOCKET-OUTLET**  
female  
**PN12C**



**INLET** male  
**PN12C**



	480 V AC	12 contacts	01A4001	01A8001
	480 V AC	12 contacts	09A4001	09A8001


► Each product is supplied with 1 bag of 13 contacts, supplied with insulation sleeves and ferrules (see p.142 or the accessories page for more details).

OPTIONS	Reference
<b>LOCKING OPTION FOR 1 PADLOCKS Ø 4mm (PADLOCK NOT SUPPLIED)</b>	
	Ref. + 843
<b>SCREW LOCKING IMPRINT BTR 2,5</b>	
	Ref. + 22
<b>INLET CAP IP66/IP67</b>	
	01NA426
<b>REVERSED INTERIOR AND CONTACTS</b>	
	The connector is supplied with a rubber inlet cap. Ref. conn. + 001 Ref. socket + 001
<b>180° OPENING LID</b>	
	Ref. socket + 10
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Socket-outlet ref.+R
<b>180° OPENING + SELF-RETURNING LID</b>	
	Ref. socket + 18
<b>ELECTROMAGNETIC COMPATIBILITY (EMC) </b>	
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.
<b>BAG OF 13 FEMALES CONTACTS</b>	
	01AA213
<b>BAG OF 13 MALES CONTACTS</b>	
	01AA113
<b>PRODUCTS AVAILABLE IN BLACK </b>	
The black dot means these products are also available in black color. Replace the second character of the product reference with 5	
<b>PRODUCT WITH ANTI-BACTERIAL TREATMENT </b>	
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.	
SLEEVE	Reference
<b>POLY SLEEVE </b>	
	30° 511M3
	70° 511M7
<b>METAL SLEEVE </b>	
	0° (Straight) 591M0
	30° 591M3
	45° 591M4

BOXES		Input	Ref.
<b>POLY BOX </b>			
	0° (Straight)	M20	511B0M20
	0° (Straight)	M25	511B0M25
	30°	M20	511B3M20
	30°	M25	511B3M25
<b>POLY BOX + POLY SLEEVE</b>			
	70°	Without hole	511C7000
	70°	Hole Ø 20	511C7M20
Earth bar ref. : 51AA089	70°	Hole Ø 25	511C7M25
	70°	Hole Ø 32	511C7M32
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M20	511C3M20
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE </b>			
	45°	M20	591C4M20
	45°	M25	591C4M25
	45°	M32	591C4M32
Cable glands are not delivered with the boxes.			
HANDLE	Input/ Cable outer Ø	Ref.	
<b>POLY HANDLE WITH GLAND </b>			
	9-18 mm	511P0D18	
	5-21 mm	511P0D21	
	60° 9-18 mm	511P6D18	
<b>POLY HANDLE + POLY CABLE GLAND </b>			
	5-12 mm	511P020P	
	9-18 mm	511P025P	
	14-25 mm	511P032P	
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>			
	7-13 mm	591P020M	
	8-16 mm	591P025M	
	16-24 mm	591P032M	
<b>POLY HANDLE (WITHOUT CABLE GLAND) </b>			
	M20	511P0M20	
	M25	511P0M25	
	M32	511P0M32	
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND) </b>			
	M20	591P0M20	
	M25	591P0M25	
	M32	591P0M32	


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




	A	B	C	E
<b>Straight handle</b>	127	140	58	42
<b>Angled handle</b>	117	138	61	42

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




	A	B	C	D	E1	E2
<b>Straight handle</b>	178	176	68	90	36/56	78
<b>Angled handle</b>	153	176	68	90	36/56	78

## PLUG ON 30° INCLINED SOCKET-OUTLET



	A	B	C	D	E1	E2
<b>Straight handle</b>	160	170	77	108	63	95
<b>Angled handle</b>	133	165	77	108	63	95

## COUPLER



	A	B	C
<b>Straight handle</b>	208	132	58

# 12 CONTACTS

16 A

480 V  
U MAX

## MULTICONTACT CONNECTORS DSN12C



IP66  
IP67  
IP69



1-2,5 mm<sup>2</sup> (1)



GRP



IK09



-40 °C  
+60 °C

(1) Flexible wiring (min.-max.).

### OTHER FEATURES

Impulse withstand voltage	5 kV
Contact resistance	< 2 mΩ
Permitted current range	4-20 mA/16 A
Σ des courants (contacts)	≤ 110 A
Terminals wiring	To weld/crimp
Butt contacts	Silver-nickel tips
Contact protection	Silvering
Load cycles	> 5 000 cycles
Vibrations	Frequency 5-1000 Hz, 1g/90 minutes on each critical frequency according to IEC 6068-2-6

### SOCKET-OUTLET

female  
**DSN12C**



**INLET** male  
**DSN12C**



For a black colour  
housing replace the second  
reference character with 5.

480 V AC

12 contacts

61A4001

61A8001


► Each product is supplied with 1 bag of 13 contacts, supplied with insulation sleeves and ferrules (voir p. 142 or the accessories page for more details).

OPTIONS	Reference
LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)	
	Ref. + 843
LARGER RELEASE BUTTON	
	Ref. socket + 453
IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)	
	611A346
INLET CAP IP66/IP67	
	611A426
IP40 SELF RETURNING LID (MANUAL CLOSING)	
	Socket-outlet ref.+R
SELF-EJECTION	
	See page 192
BAG OF 13 FEMALES CONTACTS	
	01AA213
BAG OF 13 MALES CONTACTS	
	01AA113
PRODUCTS AVAILABLE IN BLACK ●	
The black dot means these products are also available in black color. Replace the second character of the product reference with 5	
PRODUCT WITH ANTI-BACTERIAL TREATMENT ● NEW	
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.	
SLEEVE	Reference
POLY SLEEVE ●	
	30° 511M3
	70° 511M7
METAL SLEEVE	
	0° (Straight) 591M0
	30° 591M3

BOXES	$\angle x^\circ$	Input	Reference
POLY BOX ●			
	30°	M20	511B3M20
	30°	M25	511B3M25
POLY BOX + POLY SLEEVE (BLACK VERSION SEE ACCESSORIES DXN1 PAGE 239)			
	70°	Without hole	511C7000
	70°	Hole Ø 20	511C7M20
Earth bar ref. : 51AA089	70°	Hole Ø 25	511C7M25
	70°	Hole Ø 32	511C7M32
METAL BOX (+ EARTHING WIRE) + POLY SLEEVE			
	30°	M20	511C3M20
Cable glands are not delivered with the boxes.			
HANDLE	Input/ Cable outer Ø	Reference	Self-ejection
POLY HANDLE WITH GLAND ● ●			
	9-18 mm	511P0D18	/
	5-21 mm	511P0D21	/
	60° 9-18 mm	511P6D18	/
POLY HANDLE + POLY CABLE GLAND ● ●			
	5-12 mm	511P020P	Ref. +443 (10-14 mm)
	9-18 mm	511P025P	Ref. +443 (12-18 mm)
	14-25 mm	511P032P	Ref. +443
POLY HANDLE (WITHOUT CABLE GLAND) ●			
	M20	511P0M20	/
	M25	511P0M25	/
	M32	511P0M32	/


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
147	134	58	42

COUPLER




A	B
231	89

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
196	180	68	90	36/56	78

A	B	C	D	E1	E2
200	244	138	126	117	105.5

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
177	175	77	108	63.5	95

A	B	C	D	E
131	244	126	126	95



# 20 CONTACTS

25 A   
U MAX / 

## MULTICONTACT CONNECTORS DN20C



IP54  
IP55



1-6 mm<sup>2</sup> <sup>(1)</sup>  
1,5-10 mm<sup>2</sup> <sup>(2)</sup>



METAL



IK09



-40 °C  
+60 °C



EMC

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### OTHER FEATURES

IP protection plug connected

IP54

IP protection lid closed

IP55

Σ of currents (contacts)

≤ 350 A

Terminals wiring

screw-type

**SOCKET-OUTLET**  
female  
**DN20c (25 A)**



**INLET** male  
**DN20c (25 A)**



415 V AC

19P+E

1964191

1968191

OPTIONS	Reference
<b>LOCKING PIN FOR 3 PADLOCKS Ø 8 mm (PADLOCKS NOT SUPPLIED)</b>	
	Ref. + 844
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket + 453
<b>INLET CAP</b>	
	196A126
<b>180° OPENING LID</b>	
	Ref. socket + 10
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Socket-outlet ref.+R
<b>180° OPENING + SELF-RETURNING LID</b>	
	Ref. socket + 18
<b>CLOSING MECHANISM</b>	
	Draw lever only 196A376 Draw plate only 196A396
<b>IP66/IP67 SOCKET-OUTLET AND INLET</b>	
	Ref. + 600
<b>ELECTROMAGNETIC COMPATIBILITY (EMC)</b>	
	Please order a metal threaded accessory herewith, together with a EMC cable gland to be found on page 318.
<b>PRODUCT WITH ANTI-BACTERIAL TREATMENT</b>	
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.	

HANDLE	Input/ Cable outer Ø	Reference
<b>ELASTOMER HANDLE WITH GLAND</b>		
	18-25 mm	555P0D25
	25-35 mm	555P0D35
	35-45 mm	555P0D45
	45-49 mm	555P0D49
<b>POLY HANDLE + POLY CABLE GLAND</b>		
	14-25 mm	515P032P
	18-32 mm	515P040P
	24-38 mm	515P050P
	35-48 mm	515P063P
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>		
	16-24 mm	595P032M
	22-32 mm	595P040M
	34-44 mm	595P050M
	35-48 mm	595P063M
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b>		
	M50	515P0M50
	M63	515P0M63

HANDLE	Input/ Cable outer Ø	Reference
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>		
	M32	595P0M32
	M40	595P0M40
	M50	595P0M50
	M63	595P0M63


BOXES		Input	Reference
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M32	515C3M32
	30°	M40	515C3M40
	30°	M50	515C3M50
	30°	M63	515C3M63
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M32	595C3M32
	30°	M40	595C3M40
	30°	M50	595C3M50
	30°	M63	595C3M63
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE + CORNET</b>			
	0° (Straight)	M32	595C0M32
	0° (Straight)	M40	595C0M40
	0° (Straight)	M50	595C0M50
	0° (Straight)	M63	595C0M63
	70°	M32	595C7M32
	70°	M40	595C7M40
	70°	M50	595C7M50
	70°	M63	595C7M63
<b>POLY SLEEVE</b>			
	30°	M50	595E0M50
	30°	M50	595E3M50
	30°	M63	595E3M63
	70°	M50	595E7M50
	70°	M63	595E7M63

Cable glands are not delivered with the boxes.

SLEEVE		Reference
<b>POLY SLEEVE</b>		
	30°	515M3
<b>METAL SLEEVE</b>		
	0° (Straight)	595M0
	30°	595M3
	70°	595M7


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
308	246	118	81

COUPLER




A	B
486	246

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




A	B	C	E1	E2
449	272	190	170	108

PLUG ON 70° INCLINED SOCKET OUTLET



A	B	C	D	E
217	421	141	141	124

## PLUG ON 70° WALL MOUNTED SOCKET OUTLET



A	B	C	D	E1	E2
309	419	190	142	170	108



# 24 CONTACTS

16 A  U MAX

## MULTICONTACT CONNECTORS DSN24C



IP66  
IP67



1-2,5 mm<sup>2</sup> (1)



GRP



IK09



-40°C  
+60°C

(1) Flexible wiring (min.-max.).

### OTHER FEATURES

Impulse withstand voltage	5 kV
Contact resistance	< 2 mΩ
Permitted current range	4-20 mA/16 A
Σ of currents (contacts)	≤ 230 A
Terminals wiring	To weld/crimp
Butt contacts	Silver-nickel tips
Contact protection	Silvering
Load cycles	> 5 000 cycles
Vibrations	Frequency 5-1000 Hz, 1g/90 minutes on each critical frequency according to IEC 6068-2-6

**SOCKET-OUTLET**  
female  
**DSN24C**



**INLET** male  
**DSN24C**



For a black colour  
housing replace the second  
reference character with 5.

480 V AC

24 contacts

61B4002

61B8002

► Each product is supplied with 2 bags of 13 contacts, supplied with insulation sleeves and ferrules (voir p. 142 or the accessories page for more details).

OPTIONS	Reference	
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)</b>		
	Ref. + 843	
<b>LARGER RELEASE BUTTON</b>		
	Ref. socket + 453	
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>		
	613A346	
<b>INLET CAP IP66/IP67</b>		
	613A426	
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>		
	Socket-outlet ref.+R	
<b>BAG OF 13 FEMALES CONTACTS</b>		
	01AA213	
<b>BAG OF 13 MALES CONTACTS</b>		
	61CA113	
<b>PRODUCTS AVAILABLE IN BLACK</b> ●		
The black dot means these products are also available in black color. Replace the second character of the product reference with 5		
<b>PRODUCT WITH ANTI-BACTERIAL TREATMENT</b> ● <span style="background-color: orange; padding: 2px;">NEW</span>		
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.		
<b>SLEEVE</b>	$\angle x^\circ$	Reference
<b>POLY SLEEVE</b> ●		
	30°	512M3
	70°	512M7
<b>METAL SLEEVE</b>		
	0° (Straight)	592M0
	30°	592M3


BOXES	$\angle x^\circ$	Input	Reference
<b>POLY BOX</b> ●			
	30°	M20	512B3M20
	30°	M25	512B3M25
<b>METAL BOX (+ EARTHING WIRE)</b>			
	20°	M20	592B2M20
	20°	M25	592B2M25
<b>POLY BOX + POLY SLEEVE (BLACK VERSION SEE ACCESSORIES DXN3 PAGE 253)</b>			
	70°	Without hole	512C7000
	70°	Ø 20 mm drill hole	512C7M20
	70°	Ø 25 mm drill hole	512C7M25
Earth bar ref. : 51AA089	70°	Ø 32 mm drill hole	512C7M32
	70°	Ø 40 mm drill hole	512C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M20	512C3M20
	30°	M25	512C3M25
	30°	M32	512C3M32
	30°	M40	512C3M40
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M20	592C3M20
	30°	M25	592C3M25
	30°	M32	592C3M32
	0° (Straight)	M20	592C0M20
	0° (Straight)	M25	592C0M25
	0° (Straight)	M32	592C0M32

Cable glands are not delivered with the boxes.

HANDLE	Input/ Cable outer Ø	Reference
<b>POLY HANDLE WITH GLAND</b> ● ●		
	5-21 mm	512P0D21
<b>POLY HANDLE + POLY CABLE GLAND</b> ● ●		
	5-12 mm	512P020P
	9-18 mm	512P025P
	14-25 mm	512P032P
	18-32 mm	512P040P
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>		
	7-13 mm	592P020M
	8-16 mm	592P025M
	16-24 mm	592P032M
<b>POLY HANDLE (WITHOUT CABLE GLAND)</b> ●		
	M20	512P0M20
	M25	512P0M25
	M32	512P0M32
	M40	512P0M40
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>		
	M20	592P0M20
	M25	592P0M25
	M32	592P0M32


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET





A	B	C	E
171	171	77	48

COUPLER





A	B
265	116

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
213	191	84	84	70	70

A	B	C	D	E1	E2
207	262	138	126	117	105.5

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
195	191	77	108	63	95

A	B	C	D	E
138	262	126	126	95



# 37 CONTACTS

16 A 

## MULTICONTACT CONNECTORS DSN37C



IP66  
IP67



1-2,5 mm<sup>2</sup> (1)



GRP



IK09



-40 °C  
+60 °C

(1) Flexible wiring (min.-max.).



For metal versions,  
contact us.

### OTHER FEATURES

Impulse withstand voltage	5 kV
Contact resistance	< 2 mΩ
Permitted current range	4-20 mA/16 A
Σ of currents (contacts)	≤ 360 A
Terminals wiring	To weld/crimp
Butt contacts	Silver-nickel tips
Contact protection	Silvering
Load cycles	> 5 000 cycles
Vibrations	Frequency 5-1000 Hz, 1g/90 minutes on each critical frequency according to IEC 6068-2-6

**SOCKET-OUTLET**  
female  
**DSN37C**



**INLET** male  
**DSN37C**

For a black colour  
housing replace the second  
reference character with 5.

480 V AC

37 contacts

61C4003

61C8003


► Each product is supplied with 3 bags of 13 contacts, supplied with insulation sleeves and ferrules (voir p. 142 or the accessories page for more details).

OPTIONS	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)</b>	
	Ref. + 843
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket + 453
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES)</b>	
	616A346
<b>INLET CAP IP66/IP67</b>	
	616A426
<b>IP40 SELF RETURNING LID (MANUAL CLOSING)</b>	
	Socket-outlet ref.+R
<b>REVERSED INTERIOR AND CONTACTS</b>	
	Ref. conn. + 001 Ref. socket + 001
<b>BAG OF 13 FEMALES CONTACTS</b>	
	01AA213
<b>BAG OF 13 MALES CONTACTS</b>	
	61CA113
<b>PRODUCTS AVAILABLE IN BLACK ●</b>	
The black dot means these products are also available in black color. Replace the second character of the product reference with 5	
<b>PRODUCT WITH ANTI-BACTERIAL TREATMENT ● NEW</b>	
This sticker means that the product is also available with an antibacterial treatment. Add the suffix AG to the reference. For more information on anti-bacterial treated handles please consult us.	
SLEEVE	Reference
<b>POLY SLEEVE ●</b>	
	30° 513M3
	70° 513M7
<b>METAL SLEEVE</b>	
	0° (Straight) 593M0
	30° 593M3
	70° 593M7

BOÎTIERS	$\Delta x^\circ$	Input	Reference
<b>POLY BOX ●</b>			
	30°	M25	513B3M25
<b>METAL BOX (+ EARTHING WIRE)</b>			
	20°	M20	593B2M20
	20°	M25	593B2M25
	20°	M32	593B2M32
<b>POLY BOX + POLY SLEEVE (BLACK VERSION SEE ACCESSORIES DXN6 PAGE 259)</b>			
	70°	Without hole	513C7000
	70°	Ø 25 mm drill hole	513C7M25
Earth bar ref. : 51AA089	70°	Ø 32 mm drill hole	513C7M32
	70°	Ø 40 mm drill hole	513C7M40
<b>METAL BOX (+ EARTHING WIRE) + POLY SLEEVE</b>			
	30°	M20	513C3M20
	30°	M25	513C3M25
	30°	M32	513C3M32
	30°	M40	513C3M40
<b>METAL BOX (+ EARTHING WIRE) + METAL SLEEVE</b>			
	30°	M20	593C3M20
	30°	M25	593C3M25
	30°	M32	593C3M32
	30°	M40	593C3M40
	0° (Straight)	M20	593C0M20
	0° (Straight)	M25	593C0M25
	0° (Straight)	M32	593C0M32
	0° (Straight)	M40	593C0M40
	70°	M20	593C7M20
	70°	M25	593C7M25
	70°	M32	593C7M32
	70°	M40	593C7M40
Cable glands are not delivered with the boxes.			
HANDLE	Input/ Cable outer Ø	Reference	
<b>POLY HANDLE WITH GLAND ●</b>			
	10-30 mm	513P0D30	
<b>POLY HANDLE + POLY CABLE GLAND ●</b>			
	9-18 mm	513P025P	
	14-25 mm	513P032P	
	18-32 mm	513P040P	
<b>METAL HANDLE WITH METAL GLAND (+ EARTHING WIRE)</b>			
	7-13 mm	593P020M	
	8-16 mm	593P025M	
	16-24 mm	593P032M	
	22-32 mm	593P040M	
<b>POLY HANDLE (WITHOUT CABLE GLAND) ●</b>			
	M20	513P0M20	
	M25	513P0M25	
	M32	513P0M32	
	M40	513P0M40	
<b>METAL HANDLE METRIC THREAD ENTRY (WITHOUT CABLE GLAND)</b>			
	M20	593P0M20	
	M25	593P0M25	
	M32	593P0M32	
	M40	593P0M40	


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET





A	B	C	E
184	195	84	55

COUPLER





A	B
286	122

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
238	225	89	100	77	88

A	B	C	D	E1	E2
239	317	178	166	157	146

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
212	219	77	108	63	95


A	B	C	D	E
170	317	166	166	135



# MOBILE APPLICATIONS

**20 A**

**RETTBOX® ONE**  
WITH OR WITHOUT AIR



**20 A/32 A**

**RETTBOX® S**  
WITH OR WITHOUT AIR



**20 A ➤ 150 A**

**SELF-EJECTION DECONTACTOR™**



MODEL	CURRENT	U MAX AC	MAX NB OF CONTACTS	NB AUX./PIL. MAX
RETTBOX® ONE	20 A	440 V	4+E	3 AUX.
RETTBOX® S	20 A/32 A	440 V	4+E	2 AUX.
SELF-EJECTION DECONTACTOR™		↔	Depending on reference	➤
PN ANTI ENGINE START UP	30 A	250 V	2+E	2 AUX.
DISTRIBUTION BOXES	20 A ➤ 90 A	400 V	4+E	4 AUX.

DOWNLOAD ALL TECHNICAL SHEETS ON OUR  
WEBSITE **MARECHAL.COM**

## SAFE POWER SUPPLY FOR AUXILIARY CHARGING DEVICES

30 A

### PN ANTI ENGINE START UP PLUG



20 A ➤ 90 A

### DISTRIBUTION BOXES




MOBILE  
APPLICATIONS

DECONTACTOR™	MATIÈRE	IP	COMPRESSED AIR SUPPLY OPTION	PAGE
Yes	POLY METAL	IP55	AIR Version	180
Yes	POLY	IP54	AIR Version	190
Yes	Depending on reference		No	192
/	POLY METAL	IP55	No	196
Yes	POLY METAL	IP66	No	198

20 A/32 A

## RETTBOX® ONE SERIES ELECTROMAGNETIC SELF-EJECTION


### RETTBOX® ONE



### INFOS +

#### ENSURE SPEED AND SAFETY

- ① Loading box connected to the electrical system of the vehicle.
- ② Automatic ejection of the coupler socket upon start-up of the vehicle by way of an electric solenoid.
- ③ Protection against water and dust by means of a self-closing cover.




RETTBOX® ONE complies with the following standards:

- European Low Voltage Directive and RoHS, European REACH Regulation.
- IEC/EN 60309-1 and IEC/EN 60670.

## CONNECTION DIAGRAM BY TYPE

Power supply with 230 V AC or 400 V AC on-board battery charger.



FIND ALL THE INFORMATION ABOUT THE  
RETTBOX® ONE ON OUR YOUTUBE CHANNEL



# 20A

440 V  
U MAXI

## RETTBOX® ONE

ELECTROMAGNETIC SELF-EJECTION



IP55



1,5 - 6 mm<sup>2</sup> <sup>(1)</sup>



GRP  
STAINLESS ►  
STEEL



IK08  
►  
IK10



- 40 °C  
+ 60 °C



3 AUX.

(1) Flexible wiring (min.-max.)

### RETTBOX® ONE (20 A)

220 - 250 V AC	1P+N+E	With 12 V relay and male inlet	6116015RK412U	6113015RK4L
220 - 250 V AC	1P+N+E	With 24 V relay and male inlet	6116015RK424U	6113015RK4L
220 - 250 V AC	1P+N+E+2 aux.	With 12 V relay and male inlet	6116175RK412U	6113175RK4L
220 - 250 V AC	1P+N+E+2 aux.	With 24 V relay and male inlet	6116175RK424U	6113175RK4L
24 V DC	2P DC*	With 24 V relay and male inlet	6116089RK424U	6113089RK4L
12 V DC	2P DC*	With 12 V relay and male inlet	6116059RK412U	6113059RK4L

\*LED not available for these configurations.

(2) All versions are available in 4, 8 and 12 m, contact us for the references.



**ENCLOSURE WITH INLET**  
supplied with 4 m cable <sup>(2)</sup>



**COUPLER SOCKET**  
pre-wired, cable 4 m  
included <sup>(2)</sup>

**OTHER FEATURES****RETTBOX® ONE (20 A)**

Front	stainless steel
Box	GRP
Front dimensions (W x H) in mm	114 X 184
Cut-out dimensions on vehicle's frame (W x H x D) in mm	83 X 163 x 94
Auxiliary contacts in option	2 Aux
Weight (excluding coupler socket)	1 200 g
Built-in DECONTACTOR™	20 A

**DOWNLOAD THE RETTBOX® ONE USER MANUAL  
FROM OUR WEBSITE MARECHAL.COM**

**INFOS +****LED CONTROL LIGHT**

RETTBOX® ONE (20 A, 230 V) feature a LED signal light that indicates the presence of charging voltage.

**OPTIONS****Reference****LEATHER PULL-GRIP (COUPLER SOCKET)**

611AZIE



**CEILING BRACKET MADE OF STAINLESS STEEL**

RETTBOX® ONE 20 A

611AHUTRRR L

**DRAWINGS  
AND DIMENSIONS**

A	B	C	D	E	F	G	H	J
RETTBOX® ONE 20 A	184	114	184	89	114	163	94	152




# 20A/32A

440 V  
U MAX

## RETTBOX® ONE AIR

### ELECTROMAGNETIC SELF-EJECTION



IP55



1,5 - 6 mm<sup>2</sup> <sup>(1)</sup>



GRP  
STAINLESS  
STEEL



IK08  
IK10



- 40 °C  
+ 60 °C



3 AUX.



(1) Flexible wiring (min.-max.)

#### RETTBOX® ONE AIR (20 A)

220 - 250 V AC	1P+N+E	With 12 V relay and male inlet	6116015AK412U	6113015AK4L
220 - 250 V AC	1P+N+E	With 24 V relay and male inlet	6116015AK424U	6113015AK4L
220 - 250 V AC	1P+N+E+1 aux.	With 12 V relay and male inlet	6116215AK412U	6113215AK4L
220 - 250 V AC	1P+N+E+1 aux.	With 24 V relay and male inlet	6116215AK424U	6113215AK4L
24 V DC	2P DC*	With 24 V relay and male inlet	6116089AK424U	6113089AK4L
12 V DC	2P DC*	With 12 V relay and male inlet	6116059AK412U	6113059AK4L
Cable only (per metre): 611AKOM				

\*LED not available for these configurations.

(2) All versions are available in 4, 8 and 12 m, contact us for the references.



#### RETTBOX® ONE AIR (32 A)

200 - 250 V AC	1P+N+E+3 aux.	With 24 V relay and male inlet	3816187AK424U	3813187AK4L
380 - 440 V AC	3P+N+E+1 aux.	With 24 V relay and male inlet	3816247AK424U	3813247AK4L
Cable only (per metre): 381AKOM				

(2) All versions are available in 4, 8 and 12 m, contact us for the references.

**ENCLOSURE WITH INLET**  
supplied with 4 m cable -  
compressed air conduct up to 13 bars<sup>(2)</sup>

**COUPLER SOCKET**  
pre-wired, cable 4 m  
included <sup>(2)</sup>

**ENCLOSURE WITH INLET**  
supplied with 4 m cable -  
compressed air conduct up to 13 bars<sup>(2)</sup>

**COUPLER SOCKET**  
pre-wired, cable 4 m  
included <sup>(2)</sup>

## OTHER FEATURES

	RETTBOX® ONE AIR (20 A)	RETTBOX® ONE AIR (32 A)
Front	stainless steel	stainless steel
Box	GRP	stainless steel
Front dimensions (W x H) in mm	114 X 184	132 X 188
Cut-out dimensions on vehicle's frame (W x H x D) in mm	83 X 163 x 94	103 X 173 x 145
Auxiliary contacts in option	1 Aux	3 Aux
Weight (excluding coupler socket)	1200 G	3200 G
Built-in DECONTACTOR™	20A	32A
Compressed air duct	up to 13 bars	up to 13 bars

DOWNLOAD THE RETTBOX® USER MANUAL  
FROM OUR WEBSITE  
[MARECHAL.COM](http://MARECHAL.COM)



## INFOS +

### LED CONTROL LIGHT

RETTBOX® ONE AIR (20 A, 230 V) feature a LED signal light that indicates the voltage presence.



## OPTIONS

## Reference

### LEATHER PULL-GRIP (COUPLER SOCKET)



611AZIE

### CEILING BRACKET MADE OF STAINLESS STEEL



RETTBOX® ONE AIR 20 A


611AHUTAAA L

RETTBOX® ONE AIR 32 A

381AHUTAAA L

## DRAWINGS AND DIMENSIONS

	A	B	C	D	E	F	G	H	J
RETTBOX® ONE AIR 20 A	184	114	184	89	114	163	94	152	83
RETTBOX® ONE AIR 32 A	188	132	197	140	151	173	116	169	103




20 A/32 A

# RETTBOX® S SERIES

## ELECTROMAGNETIC SELF-EJECTION


WITH OR WITHOUT AIR

### RETTBOX® S



### VOLTAGE PRESENCE AND AUXILIARY BATTERY CHARGING LIGHT INDICATORS

Figure 1: with an external battery charger.  
12 V DC or 24 V DC power supply.




RETTBOX® S is a professional use compact and load-breaking self-ejecting socket-outlet.

The best in class industrial socket-outlet providing power to all equipment on-board a vehicle.

RETTBOX® S complies with the following standards:


- European Low Voltage Directive and RoHS, European REACH Regulation.
- IEC/EN 61984, IEC/EN 60947-3.

Figure 2: with an on-board vehicle charger.  
up to 480 V AC power supply.



#### OPTIONAL

Order a 12 V DC/24 V DC yellow LED battery charging indicator. Reference : 151ALED-24J



# 20A/32A

**RETTBOX® S**

ELECTROMAGNETIC SELF-EJECTION

480 V  
U MAXI

NEW

WITH OR WITHOUT AIR



(1) Flexible wiring (min.-max.)



Cable is not included

**RETTBOX® S (20A)**  
**RETTBOX® S AIR (20 A)\***



BOX\*



**COUPLER SOCKET**  
straight<sup>(2)\*</sup> angled 60°<sup>(3)</sup>



220 - 250 V AC	6P+E	With solenoid coil 12/24 V DC and male connector	1516016	1513016	15C3016
24 V DC	6P+E	With solenoid coil 12/24 V DC and male connector	1516046	1513046	15C3046
12 V DC	6P+E	With solenoid coil 12/24 V DC and male connector	1516026	1513026	15C3026

(2) Input/Cable outer Ø 5-21 mm - (3) Input/Cable outer Ø 9-18 mm, no Air version available.  
\* For AIR version, change the 0 of the product reference by A.



BOX\*



**COUPLER SOCKET**  
straight<sup>(2)\*</sup> angled 60°<sup>(3)</sup>



**RETTBOX® S (32 A)**  
**RETTBOX® S AIR (32 A)\***

380 - 480 V AC	6P+E	With solenoid coil 12/24 V DC and male connector	1536036	1533036	15C3036
----------------	------	--	---------	---------	---------

(2) Input/Cable outer Ø 5-21 mm - (3) Input/Cable outer Ø 9-18 mm, no Air version available.  
\* For AIR version, change the 0 of the product reference by A.

### OTHER FEATURES

	RETTBOX® S (20 A)	RETTBOX® S (32 A)	RETTBOX® S AIR (20 A)	RETTBOX® S AIR (32 A)
Box material	GRP	GRP	GRP	GRP
Front dimensions (W x H) in mm	120 x 120	120 x 120	120 x 120	120 x 120
IP Box	IP54	IP54	IP54	IP54
IP : mobile socket-outlet without plug cap	IP2X	IP2X	IP2X	IP2X
IP : mobile socket-outlet with plug cap	IP44	IP44	IP44	IP44
Cut-out dimensions on vehicle's frame (W x H x D) in mm	86 x 82 x 83	86 x 82 x 83	86 x 82 x 83	86 x 82 x 83
Weight (excluding coupler socket)	400 g	400 g	407 g	407 g
AIR Version	/	/	up to 13 bars	up to 13 bars

### OPTIONS



Order a 12/24 V yellow LED battery charging indicator.  
Reference : 151ALED-24J.





Contact us for wall installation  
with a box 120x120x91.

Cable available per meter

381AKOM : 32 A cable, 1 air duct  
+ 5G6mm² [4P+T] + 2 x 2.5mm² for auxiliaries

611AKOM: 20 A cable, 1 compressed air duct  
+ 4G2.5mm² [3P+T] + 2 x 1.5mm² for auxiliaries

## DRAWINGS AND DIMENSIONS



A	B	C	D	E	F	G	H
120	75	66	16	96	156	77	109

**20 A ➤ 150 A**

## DSN/DS/DXN RANGES MECHANICAL SELF-EJECTING


### FIXED ELECTRIC POWER SUPPLY



Step 1: self-ejection system at rest.



Step 2: the traction acts on the electrical cable and the rope. The ejection lever gradually raises the latch.



Step 3: the latch is fully raised by the ejection lever, causing the automatic ejection of the plug.

## OPERATION SEQUENCE

Self-ejection systems avoid damage to the electrical installation when the mobile equipment is moved without removing the supply connection. They are designed to automatically release the mobile socket outlet or inlet thanks to a cord attached to the locking latch and the power supply cable.


### MOBILE POWER SUPPLY SOURCE



Step 1: Self-ejection system at rest.



Step 2: The traction acts on the electrical cable and the rope. The latch rises gradually.



Step 3: The latch is fully raised, causing the automatic ejection of the socket.


# MECHANICAL SELF-EJECTING

## DSN/DS1/DS3/DS6/DXN



FIXED ELECTRIC  
POWER SUPPLY

EJECTING PLUG  
(INLET + HANDLE)



EJECTION RELEASE LEVER

EJECTION RELEASE LEVER

**INDUSTRIAL RANGE**

**DSN\***

**DS1/DS3/DS6\***  
(contact us for metal version  
of DS9 and DS2)

**DXN\***


<b>①</b> Socket-outlet	Ref. +352	Ref. +352	Ref. +352
<b>②</b> Inlet	Standard	Standard	Standard
<b>③</b> Poly handles + eyelet	Ref. +443	Ref. +443	See references in DXN accessories page.
<b>④</b> Tension cord	311A336	311A336	251A336
<b>⑤</b> Mechanism	611A338 (DSN1) 613A338 (DSN3) 616A338 (DSN6)	311A338 (DS1) 313A338 (DS3) 316A338 (DS6)	251A338 (DXN1) 253A338 (DXN3) 256A338 (DXN6)

\* See the relevant product pages for the references of the plugs, socket-outlets and handles.

## MOBILE POWER SUPPLY SOURCE



### EJECTING COUPLER SOCKET (HANDLE + SOCKET-OUTLET)



INDUSTRIAL RANGE		ATEX RANGE	
DSN*	DS1/DS3/DS6*	DXN*	
① Inlet	Standard	Standard	Standard
② socket outlet with ejection release lever	Ref. +354	Ref. +354	Ref. +354
③ Poly handles + eyelet	Ref. +443	Ref. +443	See references in DXN accessories page.
④ Tension cord	311A336	311A336	251A336

To fix the connector directly without a sleeve, please use a socket-outlet with a 180° opening option.

\* See the relevant product pages for the references of the plugs, socket-outlets and handles.

# 30 A

230 V  
U MAX / ■ ■ ■

## ANTI ENGINE START UP PLUG PN



IP55



1-6 mm<sup>2</sup><sup>(1)</sup>  
1,5-10 mm<sup>2</sup><sup>(2)</sup>



GRP  
METAL



IK09  
IK09



-40 °C  
+60 °C

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### OTHER FEATURES

Reversed interior and contacts.

This PN features a special wiring configuration that prevents the vehicle from starting-up, if the plug is still connected. Safe operation is ensured and unintentional pull-out of the power supply system is avoided.



GRP devices are not compatible with metal devices.

Standard self closing/self returning lid



**SOCKET-OUTLET**  
on cable side  
(cap is included)  
**PN**

### VEHICLE INLET PN


		With latch	Without latch	
GRP	220-250 V AC	1P+N+E +2aux.	0124017825A	0124017001A
METAL	220-250 V AC	1P+N+E +2aux.	0924017825A	0928017001A

HANDLE	Cable outer Ø	Reference
<b>POLY HANDLE WITH GLAND</b>		
	9-18 mm	511P0D18

HANDLE	Cable outer Ø	Reference
<b>POLY HANDLE WITH GLAND</b>		
	60°	9-18 mm 511P6D18

## DRAWINGS AND DIMENSIONS

### PLUG ON SOCKET-OUTLET




	A	B	C	E
<b>Straight handle</b>	127	140	58	42
<b>Angled handle</b>	117	138	61	42

### INFOS +

#### WIRING DIAGRAM FOR THE VEHICLE-MOUNTED SOCKET-OUTLET (230 V AC)

(for information only)



# 20A >> 90A

400 V  
U MAX

## DISTRIBUTION BOXES



POWER SUPPLY FOR  
AUXILIARY BATTERIES,  
AIR-CONDITIONNING UNITS,  
TRAILERS, TANKERS...

### SAFE ELECTRICAL CONNECTIONS

our boxes ensure the safety of operators and the protection of mobile electrical installations.



IP66  
IP69<sup>(1)</sup>



GRP



IK09



-40 °C  
+60 °C

(1) IP44 with domestic socket-outlets

### OTHER FEATURES CD BOXES

Fastenings	Captive stainless steel screws
Wiring capacity	2 x 1,5 mm <sup>2</sup> to 5 x 35 mm <sup>2</sup>
Cable entries	M50 max..
Housing dimensions (W x H x D) in mm	345 x 225 x 156
Assembly	10 modules max..

### LIQUID GAS TRANSFER BOX TECHNICAL FEATURES

Protection	30 mA
Earthing connection of the lorry is ensured.	
Fixation	300 x 300 mm
Height	470 mm
Depth	250 mm
Cable glands	M40 IP68 (Ø 20 to 32 mm)



other  
configurations,  
circuit protection  
or dimensions are  
available on request.  
Please contact us.

**EXAMPLES OF APPLICATIONS : PRE-WIRED BOX WITH DIFFERENTIAL PROTECTION FOR REMOTE POWER SUPPLY.**

Contact us for the references.

CD box and RETTBOX®S for the power supply of a rescue vehicle.



CD box and self-ejection plug for the power supply of a refrigerated vehicle.



Liquid gas transfer box for power supply of a tanker.



Specific documentation is available for these applications.

# DISTRIBUTION AND JUNCTION BOXES

## DISTRIBUTION AND JUNCTION

### CD DISTRIBUTION BOX



P. 202

### B2 JUNCTION BOXES



P. 204

### SB JUNCTION BOXES



P. 206

From 16 A up to 90 A  
Differential protection  
30 mA  
IP66/IP69  
water-and dust-tight  
Composed of two parts  
fixed on hinges  
Prewired with easy access  
to the connection terminals

IP66/IP67  
water-and dust-tight  
2 Dimensions  
(120x120x91 mm  
and 160x160x91 mm)  
Up to two drilled hole per  
side (M40 max.)  
Option with hinged lid.

Ideal solution for corrosive  
environment.  
AISI 316L stainless steel.  
Max. dimensions  
950x750x200mm  
Hinged lid.  
Internal mounting plate  
included.  
Optional drilled holes  
up to M80.



## SELECTION GUIDE

### CUSTOMISED SOLUTIONS

#### BOXES



P. 208

#### EXTENSIONS



#### CABLE REELS



In direct connection with its production of industrial electrical socket-outlets, MARECHAL ELECTRIC has the internal skills to offer you complete customized solutions. From cable assemblies to power distribution boxes.

BOXES



SOLUTIONS FOR TUNNEL APPLICATIONS  
PLEASE REFER TO PAGE 210



# 16 A >> 90 A

440 V  
U MAX

## DISTRIBUTION BOXES CD



IP66  
IP69<sup>(1)</sup>



GRP



IK09



-40 °C  
+60 °C

(1) IP44 with domestic socket-outlets



**Pre-wired boxes.  
For empty version,  
contact us.**

### OTHER FEATURES

Fastenings

Captive stainless steel screws

Wiring capacity

2 x 1,5 mm<sup>2</sup> to 5 x 35 mm<sup>2</sup>

Cable entries

M50 max.

Housing dimensions (HxWxD) in mm

342 x 225 x 156

Assembly

10 modules max.




**DECONTACTOR™ DSN1**

16 A - 1P+N+E  
220-250 V



**DECONTACTOR™ DSN3**

32 A - 3P+N+E  
220-250 V/380-440 V



### Protection

- Main switch with RCD 30 mA 1x40 A 3P+N
- Circuit breaker PC1 : 1x16 A 1P+N
- Circuit breaker PC2 : 1x32 A 3P+N

### Terminal

3P+N+E 16 mm<sup>2</sup>

### Cable gland

M32 Poly (14-25 mm)

## INSIDE BOX COMPOSITION

Box	Main switch with RCD 30 mA	Circuit breaker Socket 1	Circuit breaker Socket 2	Terminal	Cable gland mm
<b>CD1</b>		1x16A 1P+N 30 mA		1P+N+E 16 mm <sup>2</sup>	M25 POLY [9-18]
<b>CD2</b>	1x25A 1P+N	1x16A 1P+N	1x16A 1P+N	1P+N+E 16 mm <sup>2</sup>	M25 POLY [9-18]
<b>CD3</b>		1x16A 3P+N 30 mA		3P+N+E 16 mm <sup>2</sup>	M25 POLY [9-18]
<b>CD4</b>		1x16A 3P 30 mA		3P+E 16 mm <sup>2</sup>	M25 POLY [9-18]
<b>CD5</b>	1x25A 3P+N	1x16A 3P+N	1x16A 3P+N	3P+N+E 16 mm <sup>2</sup>	M25 POLY [9-18]
<b>CD6*</b>		+ 2 fuses 6A Gg		1P+N+E 16 mm <sup>2</sup>	M25 POLY [9-18]
<b>CD7</b>	1x25A 1P+N	1x16A 1P+N	1x16A 1P+N	1P+N+E 16 mm <sup>2</sup>	M25 POLY [9-18]
<b>CD8</b>		1x32A 1P+N 30 mA		1P+N+E 16 mm <sup>2</sup>	M32 POLY [14-25]
<b>CD9</b>	1x40A 1P+N	1x32A 1P+N	1x32A 1P+N	3P+N+E 16 mm <sup>2</sup>	M32 POLY [14-25]
<b>CD10</b>		1x32A 3P+N 30 mA		3P+N+E 16 mm <sup>2</sup>	M32 POLY [14-25]
<b>CD11</b>	1X40A 3P+N	1x32A 3P+N	1x32A 3P+N	3P+N+E 16 mm <sup>2</sup>	M32 POLY [14-25]
<b>CD12</b>	1x40A 3P+N	1x16A 1P+N	1x32A 3P+N	3P+N+E 16 mm <sup>2</sup>	M32 POLY [14-25]
<b>CD13</b>	1x40A 3P+N	1x16A 1P+N	1x32A 3P+N	3P+N+E 35 mm <sup>2</sup>	M40 POLY [18-32]
<b>CD14</b>	1x40A 3P+N	1x16A 1P+N	1x32A 3P+N	3P+N+E 16 mm <sup>2</sup>	M32 POLY [14-25]
<b>CD15</b>		1x63A 3P+N 30 mA		3P+N+E 16 mm <sup>2</sup>	M40 POLY [18-32]
<b>CD16*</b>	1x25A 3P+N	+ 2 fuses 6A Gg	1x16A 3P+N	3P+N+E 16 mm <sup>2</sup>	M32 POLY [14-25]

\* CD6 and CD16 boxes are equipped with a 160 VA 230 V/24 V transformer. Maximum operating temperature: 40 °C

Type	French standard socket <b>16 A - 230 V</b>	<b>16 A socket</b>		<b>16 A socket</b>		<b>32 A socket</b>		<b>63 A socket</b>		Associated* <b>MARECHAL® DECONTACTOR™</b>	
		24 V	220-250 V	380-440 V	220-250 V 380-440 V	220-250 V	220-250 V 380-440 V	220-250 V	220-250 V 380-440 V	DSN range	DS range
Box	2P+E	2P	1P+N+E	3P+E	3P+N+E	1P+N+E	3P+N+E	3P+N+E	DSN range	DS range	
<b>CD1</b>				1					6114015CD1	3114015CD1	
<b>CD2</b>				2					6114015CD2	3114015CD2	
<b>CD3</b>					1				6114017CD3	3114017CD3	
<b>CD4</b>				1					6114013CD4	3114013CD4	
<b>CD5</b>					2				6114017CD5	3114017CD5	
<b>CD6</b>		1							611408ACD6	311408ACD6	
<b>CD7</b>	1		1						6114015CD7	3114015CD7	
<b>CD8</b>						1			6134015CD8	3134015CD8	
<b>CD9</b>						2			6134015CD9	3134015CD9	
<b>CD10</b>							1		6134017CD10	3134017CD10	
<b>CD11</b>							2		6134017CD11	3134017CD11	
<b>CD12</b>			1				1		6134017CD12	3134017CD12	
<b>CD13</b>			1				1		6134017CD13	3134017CD13	
<b>CD14</b>	1						1		6134017CD14	3134017CD14	
<b>CD15</b>			1	(PN range)			1		1	6164017CD15	
<b>CD16</b>			1				1			6114017CD16	3114017CD16

\* CD6 and CD16 boxes are equipped with a 160 VA 230V/24V transformer. Maximum operating temperature: 40 °C.

## INFOS +

The CD box can be mounted on a support.  
Support frame ref.: 9CHAS-CD



Other configurations on request.  
Please contact us where applications require more than 2 outlets.

# JUNCTION BOXES B2



IP66  
IP67



2 x 1,5 mm<sup>2</sup>  
» 5 x 35 mm<sup>2</sup>



GRP



IK08



-40 °C  
+60 °C

## OTHER FEATURES

Fastenings

Captive stainless steel screws

Two dimensions (W x H x D) in mm

120x120x91, up to two drilled holes per side (M32 max.)

160x160x91, up to two drilled holes per side (M32 max.)

Glow-wire flammability index according to  
IEC/EN 60695-2-12

850 °C

Isolation voltage

1 000 V AC



Box are supplied with a  
DIN rail and without drilled  
holes as a standard.

Please contact us for your  
specific configurations.

## TYPE

Empty box 120x120x91\*

509ACP1

Empty box 160x160x91\*

509ACP2


\*hinges are not included, earthing bar on request.



## EXAMPLE CONFIGURATIONS



## DRAWINGS AND DIMENSIONS



	A	C	B	E1	E2
<b>120x120</b>	91	141	126	117	106
<b>160x160</b>	91	178	166	157	146

## JUNCTION BOX SB



IP66  
IP67



STAINLESS STEEL  
316L



IK10



-50 °C  
+95 °C


The SB is an IP66/IP67 junction box used for the most severe applications as in the food and beverage industry. All boxes sizes except the 150x150x100 version are equipped with:

- an internal mounting plate
- an earthing terminal
- a cable entry plate placed in the lower part of the box.

### OTHER FEATURES

Material	Stainless steel 316L - 1.5mm thickness
Fastenings	Stainless steel
Drilling (for cable glands)	Up to M80
Hinged lid with silicon sealing	

## REFERENCES AND DIMENSIONS



REFERENCE	DIMENSIONS [mm]				
	A	B	C	D	E
B016Y12064815*	150	150	100	180	-
B016Y12064816	200	200	160	230	160
B016Y12064817	280	280	160	310	240
B016Y12064818	350	350	160	380	310
B016Y12064819	380	380	200	410	340
B016Y12064820	500	500	200	530	460

\* Only fitted with a rail DIN.



# CUSTOMISED SOLUTIONS

BOXES, EXTENSIONS  
AND CABLE REEL

In direct connection with its production of industrial electrical socket-outlets, MARECHAL ELECTRIC has the internal skills to offer you complete customized solutions. From cable assemblies to power distribution boxes.

Contact us.



## EXAMPLE OF SOLUTIONS



Portable rubber box



Automatic cable reel



Equipped cable reel



Boxes of all sizes and materials, GRP, sheet metal or stainless steel.



Extension cable



Portable service box

# SOLUTIONS FOR TUNNELS

## BOXES AND CONNECTORS

### JUNCTION BOXES

MODEL	APPLICATION	CONDUCTOR SECTION
	EXPRESS® XL STANDARD LIGHTING	From 2.5 mm <sup>2</sup> to 35 mm <sup>2</sup>
	EXPRESS® STANDARD LIGHTING	From 2.5 mm <sup>2</sup> to 35 mm <sup>2</sup>
	B2 FIRE-RESISTANT EMERGENCY LIGHTING	From 1.5 mm <sup>2</sup> to 6 mm <sup>2</sup>
	EXPRESS® XL FIRE-RESISTANT EMERGENCY LIGHTING	From 4 mm <sup>2</sup> to 35 mm <sup>2</sup>
	EXPRESS® FIRE-RESISTANT EMERGENCY LIGHTING	From 4 mm <sup>2</sup> to 35 mm <sup>2</sup>
	EQINOX FIRE-RESISTANT EMERGENCY SIGNALLING, SIGNPOSTING	From 25 mm <sup>2</sup> to 120 mm <sup>2</sup>

### BOXES AND CONNECTORS

MODEL	APPLICATION
	FIRE DEPARTMENT BOX SAFETY REFUGE
	SAFETY BOXES SAFETY REFUGE
	DS F400 FANS AND SMOKE VENTILATORS



## SELECTION GUIDE

CABLE	STANDARDS	PAGE
Through boxes with or without cable termination Multi conductors ( $\varnothing$ 13 to 29 mm)	/	p. 214
Through boxes with or without cable termination Single or multi conductors ( $\varnothing$ 9 to 28 mm)	/	p. 216
Through boxes with cable termination Single or multi conductors ( $\varnothing$ 2.5 à 25 mm)	NF C 32-070 (DIN 4102-12 to come)	p. 218
Through boxes with or without cable termination Multi-conductors ( $\varnothing$ 13 to 29 mm)	NF C 32-070 DIN 4102-12/E30	p. 220
Through boxes with or without cable termination Single or multi conductors ( $\varnothing$ 9 to 28 mm)	NF C 32-070 EN 50362	p. 222
Through boxes with cable termination Single or multi conductors	NF C 32-070 DIN 4102-12/E60	p. 224
FUNCTION	STANDARDS	PAGE
Connection of electrical equipment for rescue teams inside tunnels.	/	p. 226
Communication between different rescue teams inside tunnels.	NF C 32-070	p. 228
Local isolation for fans and smoke ventilators (400 °C/2h)	IEC/EN 60947-3 EN 12101-3	p. 230

# SOLUTIONS FOR TUNNELS

MARECHAL ELECTRIC proposes a wide range of products dedicated to the electric connections for tunnels. Based on technology specially designed for such difficult environments and the quick disconnections of lights, MARECHAL ELECTRIC has already equipped more than 2 000 km of underground roads, railroads and inland waterways...

our objectives remain the same: to provide user safety, optimise maintenance and make the work of the emergency services easier.

## PRODUCTS SUITED FOR SPECIAL TUNNEL ENVIRONMENTS

Very often in a tunnel, there is dust, stone projections, smoke, gas, moisture, water streaming and, of course, pollution. Electric connections in tunnels are subjected to extremely corrosive conditions. Designed to withstand such conditions, MARECHAL® boxes equipped with connectors or decontactors provide safe solutions for tunnel maintenance.

## WATERTIGHTNESS

All boxes are watertight and withstand the use of high-pressure washing during tunnel maintenance.


## CORROSION AND IMPACT RESISTANCE HALOGEN AND SMOKE FREE

For optimum safety, the materials used for making Marechal® boxes and connectors are resistant to corrosion and impact (resistance IK09). In case of fire, these materials emit a limited amount of non dangerous smoke.

## QUALITY CONNECTION AND EASY DISCONNECTION: USE OF BUTT-CONTACTS

Easy disconnection = easy maintenance: thanks to the MARECHAL® silver-nickel butt-contact technology, the contacts never weld. Therefore, the connection quality remains absolutely stable, and the disconnection can be done any time, even after several years.

## TYPICAL WIRING DIAGRAM OF OUR JUNCTION BOXES.





## STANDARDS AND CERTIFICATIONS


The use of Marechal solutions for tunnels facilitates the compliance of your infrastructure to:

- European Directive 2004/54/EC relating to tunnels in the road networks across Europe in terms of safety measures,
- for the transposition of the European Directive,
- in France:
  - ▶ to the application of text in the Highway Code relating to the safety of people in tunnels, as well as to inter-ministerial circulars No 2006-20 and 2000-63 (Annexe 2) on safety in tunnels and road networks.


- ▶ the requirements of the CETU guide defining the behaviour of fire in road tunnels,
- ▶ according to the text relating to the Transport Code in terms of safety equipment.

MARECHAL® solutions for tunnels are compliant with the following fire resistance standards:


- EN 50362 (Europe) tested by the IMQ Italy laboratory,
- NF C 32-070 (France) tested by the laboratory C.S.T.B France,
- DIN 4102-12 (Germany) tested by the laboratory MPA Dresden GmbH,
- EN 12101-03 (Europe) tested by the laboratory EFECTIS France.



Oven temperature curve - Standardized time  
NF C 32-070 standard



Flame temperature curve - Time  
NF EN 50362 standard



Over temperature curve - Time  
DIN 4102 standard

## STANDARD LIGHTING

# BOX EXPRESS® XL



IP66



GRP



IK09

### OTHER FEATURES

Service terminals	2 to 5 insulation-piercing.
Service protection	By circuit breaker fitted to DIN rail.
Cables accepted	Armoured and unarmoured cables, stranded or flexible, from 2,5 mm <sup>2</sup> to 35 mm <sup>2</sup> , with an external diameter 13 to 29mm. Configuration with cable cut is also possible.
Earthing point	Inside and outside the enclosure.
Fire smoke class	M1F0
Self extinguishing material	UL94 V-0
Modularity box	• Secondary line wiring with MARECHAL® socket-outlet.
Options	• Accessories for fixing box to cable tray or ladder (option).
Other equipment	• “Power On” signal light (option).

## REFERENCES AND DIMENSIONS

### JUNCTION BOX WITH OR WITHOUT THE NEED TO CUT THE CABLE

Made from halogen-free glass fibre reinforced polyester compound, these boxes allow a service tap-off from the main through cable with or without the need to strip or cut the main cable. Gaskets allow the immediate positioning of cables with a maximum diameter of 29 mm whilst creating an IP66 seal. The box lid mounted on a stainless steel axis is fixed to the box by means of captive stainless steel screws.

#### BOX EXPRESS® XL

Type	H x W x D in mm	Distribution
91250	175 x 362 x 99	- Maximum 2 tap-offs using 2 sockets - Maximum 4 tap-offs using glands



# BOX EXPRESS®



## OTHER FEATURES

Service terminals	2 to 5 insulation-piercing.
Service protection	By circuit breaker fitted to DIN rail
Cables accepted	Armoured and unarmoured cables, stranded or flexible, from 2,5 mm <sup>2</sup> to 35 mm <sup>2</sup> , with an external diameter 9 to 28 mm. Configuration with cable cut is also possible.
Earthing point	Inside and outside the enclosure
Fire smoke class	M1F0
Self extinguishing material	UL94 V-0
Modularity box	• Secondary line wiring with MARECHAL® socket-outlet.
Options	• Accessories for fixing box to cable tray or ladder (option).
Other equipment	• “Power On” signal light (option). • Plate for external fixing. • Gasket for two cables*.

\*Contact us for more details.

## REFERENCES AND DIMENSIONS

### JUNCTION BOX WITH OR WITHOUT THE NEED TO CUT THE CABLE

Made from halogen free glass fibre reinforced polyester compound, these boxes allow a service tap-off from the main through cable with or without the need to strip or cut the main cable. "Snail" type gaskets allow the immediate positioning of cables with a maximum diameter of 28 mm whilst creating an IP66 seal. The box lid, fitted with a retaining cord, is fixed to the box by means of captive stainless steel screws.

#### BOX EXPRESS®


Type	H x W x D in mm	Distribution
91150	191 x 254 x 111	- Maximum 2 tap-offs using 2 sockets - Maximum 4 tap-offs using glands



## EMERGENCY LIGHTING

### BOX B2 FIRE-RESISTANT NFC 32-070 (DIN 4102-12 TO COME)

NEW



IP66  
IP67



2 x 1,5 mm<sup>2</sup>  
to 5 x 6 mm<sup>2</sup>



GRP



IK08



E90

#### OTHER FEATURES

Electrical continuity of the main power supply is guaranteed according to NFC 32-070 (DIN 4102-12 to come).

Service terminals

2 to 5 ceramic-isolated steel junction terminals mounted on a specific stainless steel rail fixed to the wall through a stainless steel base plate.

Cables accepted

Armoured and unarmoured cables, stranded or flexible, from 1.5 mm<sup>2</sup> to 6 mm<sup>2</sup>.

Earthing point

Inside and outside the enclosure.

Modularity box  
Options  
Other equipment

- Secondary line wiring with MARECHAL® socket-outlet\*.
- Accessories for fixing box to cable tray or ladder.

\*Contact us for more details.


# REFERENCES AND DIMENSIONS

## FIRE-RESISTANT JUNCTION BOX

Made from polyamide, these boxes ensure the junction between one or more main through fire-resistant cables. The interconnection of crossing cables is performed thanks to ceramic-isolated steel junction terminals mounted on a specific steel rail. The box lid, which can be mounted on hinges as an option, is fixed by means of captive stainless steel screws.

### BOX B2 FIRE-RESISTANT

Reference	W x H x D in mm	Distribution
91321	120 x 120 x 91	Maximum 4 tap-offs using glands
91361	160 x 160 x 91	Maximum 4 tap-offs using glands



	A	E1	B	C
<b>120x120</b>	94	171	201	138
<b>160x160</b>	94	215	245	178

## EMERGENCY LIGHTING

### BOX EXPRESS® XL FIRE-RESISTANT

NFC 32-070  
DIN 4102-12



IP66



GRP



IK09



NFC 32-070  
DIN 4102-12

#### OTHER FEATURES

Electrical continuity of the main line is guaranteed according to NFC 32-070/DIN 4102-12 - E30 classification.

Tapping terminals

Quantities : up to 5 stainless steel terminals

Technology: Insulation piercing terminal, fixed on a ceramic base (NFC 32-070/DIN 4102-12), or aerial (DIN 4102-12).

Fixing: Wall mounted stainless steel plate by means of the box's plate.

Tapping protection

By circuit breaker fitted to DIN rail

Cables accepted

Armoured and unarmoured cables, stranded or flexible, from 4 mm<sup>2</sup> to 35 mm<sup>2</sup>, with an external diameter 13 to 29 mm. Configuration with cable cut is also possible.

Earthing terminal

Inside and outside the enclosure

Fire smoke class

M1FO

Self extinguishing material

UL94 V-0

Modularity box

- Secondary line wiring with MARECHAL® socket-outlet.

Options

- Accessories for fixing box to cable tray or ladder (option).

Other equipment

- "Power On" signal light (option).

- Possibility to use non-perforating terminals.

# REFERENCES AND DIMENSIONS

## JUNCTION BOX WITH OR WITHOUT THE NEED TO CUT THE CABLE

Made from halogen-free glass fibre reinforced polyester compound, these boxes allow a service tap-off from the main through cable with or without the need to strip or cut the main cable. Gaskets allow the immediate positioning of fire resistant cables with a maximum diameter of 29 mm whilst creating an IP66 seal. The box lid mounted on a stainless steel axis is fixed to the box by means of captive stainless steel screws.

### BOX EXPRESS® XL FIRE-RESISTANT


### NF C 32-070

Type	Terminals	H x W x D in mm	Distribution
91251	Ceramic	175 x 362 x 99	- Maximum 2 tap-offs using 2 sockets - Maximum 4 tap-offs using glands

### BOX EXPRESS® XL FIRE-RESISTANT

### DIN 4102-12

Type	Terminals	W x H x D in mm	Distribution
91252	Ceramic	175 x 361 x 99	- Maximum 2 tap-offs using 2 sockets
91253	Loose		- Maximum 4 tap-offs using glands



## EMERGENCY LIGHTING

### BOX EXPRESS® FIRE-RESISTANT

NF C 32-070  
EN 50362  
DIN 4102



IP66



GRP



IK09



NF C 32-070  
EN 50362/E30 DIN 4102

#### OTHER FEATURES

Electrical continuity of the main power supply is guaranteed according to NF C 32-070/EN 50362 - 850°C/120min classification and DIN 4102 classification E30.

Service terminals

Quantités : Jusqu'à 5 bornes inox.

Technologie : Borne à perforation d'isolant, montée sur une embase céramique (NF C 32-070/EN 50362), ou volante (EN 50362).

Fixation : Platine inox, solidaire du mur par l'intermédiaire de la platine de fixation du coffret.

Service protection

By circuit breaker fitted to DIN rail

Cables accepted

Armoured and unarmoured cables, stranded or flexible, from 4 mm<sup>2</sup> to 35 mm<sup>2</sup> with an external diameter 9 to 28 mm.

Earthing point

Inside and outside the enclosure

Fire smoke class

M1F0

Self extinguishing material

UL94 V-0

Modularity box

- Secondary line wiring with MARECHAL® socket-outlet.

Options

- Accessories for fixing box to cable tray or ladder (option).

Other equipment

- "Power On" signal light (option).

- Possibility to use non-perforating terminals.

- Gasket for two cables\*.

\*Contact us for more details.

# REFERENCES AND DIMENSIONS

## FIRE-RESISTANT JUNCTION BOX

Made from halogen free glass fibre reinforced polyester compound or thermoplastic, these boxes allow a service tap-off from the main through cable without the need to strip or cut the main cable. "Snail" type gaskets allow the immediate positioning of fire resistant cables with a maximum diameter of 28 mm whilst creating an IP66 seal. The box lid, fitted with a retaining cord, is fixed to the box by means of captive stainless steel screws.

### BOX EXPRESS® FIRE-RESISTANT

### NF C 32-070

Type	Terminals	H x W x D in mm	Distribution
91151	Ceramic	191 x 254 x 111	- Maximum 2 tap-offs using 2 sockets - Maximum 4 tap-offs using glands

### BOX EXPRESS® FIRE-RESISTANT

### EN 50362

Type	Terminals	H x W x D in mm	Distribution
91154	Loose	191 x 254 x 111	- Maximum 2 tap-offs using 2 sockets - Maximum 4 tap-offs using glands



## EMERGENCY SIGNALLING, SIGNPOSTING

### BOX EQINOX FIRE-RESISTANT NF C 32-070 + DIN 4102-12/E60

NEW



IP66/67



AISI 316L  
STAINLESS STEEL



IK10



NF C 32-070  
DIN 4102-12/E60

#### OTHER FEATURES

Electrical continuity of the main power supply is guaranteed according to NF C 32-070 (91141 type) and DIN 4102-12 (91142 type)

Service terminals

2 to 7 insulation-piercing, stainless steel terminals, fitted into a ceramic base.

Service protection

By circuit breaker fitted to DIN rail

Cables accepted

Armoured and unarmoured cables, stranded or flexible, from 25 mm<sup>2</sup> to 120 mm<sup>2</sup>

Earthing point

Inside and outside the enclosure

Fire smoke class

M0

Modularity box

- Secondary line wiring with MARECHAL® socket-outlet.
- “Power On” signal light (option).

Options

Other equipment

# REFERENCES AND DIMENSIONS

## FIRE-RESISTANT JUNCTION BOX

Made from AISI 316L stainless steel, these boxes ensure the junction between one or more main through fire-resistant cables (in compliance with NF C 32-070 or DIN 4102 or E30/E60/E90 type) Cable glands are fire-resistant and the interconnection of crossing cables is performed thanks to stainless steel terminals mounted on ceramic plates. The box lid mounted on hinges is fixed by means of captive stainless steel screws.

### BOX EQINOX FIRE-RESISTANT

Type	Norm	W x H x D in mm	Distribution
91141	NF C 32-070	140x200x130 200x270x130	Cable glands or MARECHAL® socket-outlets.
91142	DIN 4102-12	270x350x130 350x350x160 350x500x160 500x500x160	Number of inputs/outputs depending on configuration.



## TUNNEL REFUGE POINT

### FIRE BOXES



IP65  
IP66/IP69



► ALUMINIUM  
► GRP



► IK09  
► IK09

#### OTHER FEATURES

Cables accepted

Armoured and unarmoured cables, stranded or flexible,  
from 2.5 mm<sup>2</sup> to 25 mm<sup>2</sup>

Service protection

30 mA differential breaker

Earthing point

Inside and outside the enclosure

# REFERENCES AND DIMENSIONS

## ALUMINIUM BOX

Especially developed in collaboration with emergency services who specialise in tunnel rescue, this box is installed in a refuge point. Made from aluminium, this box is composed of a back plate, an inclined cover with mounted socket-outlets and an inspection window.

Power supply of this box is performed using 5G16 cables (max. conductor section). The box lid is fixed by means of captive stainless steel screws.

### ALUMINIUM box

Type	H x W x D in mm	Distribution
91277	345 x 280 x 125	One or two MARECHAL® socket-outlet can be mounted on the inclined cover.



## THERMOPLASTIC BOX

Natural evolution of the aluminum version, this enclosure has equivalent functions and increased environmental resistance with its IP66/IP69 level (high cleaning pressure) and the increased resistance to corrosion to protect from road-salting. This box is composed of two parts fixed on hinges:

- a protection part, with a transparent window (locking key in option),
- an inclined cover with mounted socket-outlets.

Power supply of this box is performed using 5G25 cables (max. conductor section).

### THERMOPLASTIC BOX

Type	H x W x D in mm	Distribution
3134017CDxx	342 x 225 x 156	One or two MARECHAL® socket-outlet can be mounted on the inclined cover.



## TUNNEL REFUGE POINT

# EMERGENCY SERVICE BOXES

NEW



IP66



AISI 316L  
STAINLESS STEEL



IK10



NFC 32-070

### OTHER FEATURES

Electrical continuity of the main power supply is guaranteed according to NF C 32-070.

Service terminals

2 to 5 stainless steel terminals mounted on ceramic plates.

Cables accepted

Armoured and unarmoured cables, stranded or flexible, from 1.5 mm<sup>2</sup> to 6 mm<sup>2</sup>

Earthing point

Inside and outside the enclosure

Fire smoke class

M0

## REFERENCES AND DIMENSIONS

### FIRE-RESISTANT SELF-POWERED PHONE BOX

Made from AISI 316L stainless steel, these boxes ensure the junction between the main through fire-resistant cable (CR1-C1 type in compliance with NF C 32-070)

Cable glands are fire-resistant and the inter-connection of crossing cables is performed thanks to stainless steel terminals mounted on ceramic plates.

The box lid mounted on hinges is fixed by means of captive stainless steel screws.

### SLEEV-POWERED PHONE BOX

Type	H x W x D in mm	Distribution
91141	270 x 200 x 130	2 outputs with MARECHAL® metal PN socket-outlet.



# 125 A

690 V  
U MAX / U

DECONTACTOR™  
DS F400



400 °C/2H

FIRE-RATED FOR TUNNEL JET FANS



IP66  
IP67



10 - 35 mm<sup>2</sup> <sup>(1)</sup>  
10 - 50 mm<sup>2</sup> <sup>(2)</sup>



IK09



400 °C/2h



AC-22  
AC-23



60947-3  
12101-3



2 AUX.



-40 °C  
+60 °C

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).  
Earthing cable section 35 mm<sup>2</sup> max.



Other configurations  
on request

#### LOAD-BREAK CAPABILITY OF THE DECONTACTOR™

Load-break capability according to IEC/EN 60947-3/AC-22

125 A - 690 V

Load-break capability according to IEC/EN 60947-3/AC-23

125 A-400 V - 63 A 690 V

Power kW AC-22/AC-23

110 kW/55 kW

#### OTHER FEATURES

Electrical continuity of the main power supply is guaranteed according to EN 12101-3 - 400°C/120min classification.

Compliant with European Low Voltage Directive 2014/35/EU



SOCKET-OUTLET  
DS F400

INLET  
DS F400

380-440 V AC	3P+E	3964F13	3968F13
660-690 V AC	3P+E	3964F93	3968F93
Auxiliaries 5 A/500 V AC	+ 2 contacts	Ref. + 972	Ref. + 972*

\* Auxiliaries on connector side are shunted.

► Contact us for other configurations and references.

## DS F400 PLUGS AND SOCKET-OUTLETS FACILITATE THE COMPLIANCE OF:

- electrical machinery
  - to the "Machinery" European Directive on isolating device,
  - to the standard EN 60204-1 : Safety of machinery-electrical equipment of machines,
  - to the standard EN ISO 14118 : Safety of machinery - Prevention of unexpected start-up.
- smoke ventilators to the standard EN 12101-3 (fire resistance classification F400: 400°C/2h)

### DS F400 plugs and socket-outlets comply with:

- European Directives Low Voltage and RoHS (affixing of CE marking).
- REACH European Regulation,
- standard IEC/EN 60947-3 (dealing with the load breaking capacities of AC-22 and AC-23 utilization categories).

OPTION	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>	
	Réf + 843


WALL BOXES	 X°	Input	Reference
<b>METAL BOX WITHOUT CABLE GLAND (+ EARTHING WIRE + METAL SLEEVE) UP TO 50 mm<sup>2</sup> - Contact us for special cables</b>			
	30°	M25	574C3M25185
	30°	M32	574C3M32185
	30°	M40	574C3M40185
	30°	M50	574C3M50185
<b>METAL BOX WITH STRANDED CONDUCTOR WITH SECTION &gt;50 mm<sup>2</sup></b>			
	Contact us.		

HANDLES	Input	Reference
<b>METAL HANDLE WITHOUT CABLE GLAND (+ EARTHING WIRE) - Contact us for special cables</b>		
	M25	574P0M25185
	M32	574P0M32185
	M40	574P0M40185
	M50	574P0M50185
CABLE GLAND	Cable outer Ø	Input
	8 - 16 mm	M25
	16 - 24 mm	M32
	22 - 32 mm	M40
	34 - 44 mm	M50


## OUR CERTIFICATIONS

*Efectis*

### PLUG ON SOCKET OUTLET



### PLUG ON SOCKET MOUNTED ON WALL BOX



# CONNECTORS



## DECONTACTOR™ AND PLUGS

RANGE	CURRENT	U MAX AC	MAX NB OF CONTACTS	MAX NUMBER OF AUX./PIL.	DECONTACTOR™
PNCX	5 A	250 V	4+E	/	/
DXN1	20 A	550 V	4+E	/	Yes
DXN1 Z. 2-22	20 A	440 V	4+E	2 PIL.	/
DXA1	20 A	550 V	4+E	/	Yes
DX1	20 A	750 V	4+E	/	Yes
DX3	32 A	750 V	4+E	/	Yes
DXN3	32 A	750 V	4+E	2 AUX.	Yes
DXN3 Z. 2-22	40 A	690 V	4+E	2 AUX.	/
DXN6	63 A	750 V	4+E	2 AUX.	Yes
DXN6 Z. 2-22	63 A	1000 V	4+E	2 AUX.	/
DX6	63 A	750 V	4+E	/	Yes
DX9	125 A	750 V	4+E	/	Yes
DX2	200 A	750 V	4+E	/	Yes



## SINGLE POLE

SPeX	680 A	1 000 V	1	/	/
------	-------	---------	---	---	---



## MULTICONTACTS

PXN12C	10 A	220 V	11+E	/	/
DXN25C	10 A	440 V	24+E	/	/
DXN37C	10 A	230 V	36+E	/	/

DOWNLOAD ALL TECHNICAL DATA SHEETS FROM  
OUR WEBSITE **MARECHAL.COM**

## SELECTION GUIDE

MATERIAL	IP	IK	ATEX ZONES	PROTECTION MODE	PAGE
POLY	IP66/IP67/IP69	IK08	1, 2, 21, 22	e, tb	236
POLY	IP66/IP67	IK09	1, 2, 21, 22	db eb, tb	238
POLY	IP66/IP67	IK09	2, 22	ec, tc	240
METAL	IP66/IP67	IK10	1, 2, 21, 22	db eb, tb	244
METAL	IP65	IK10	1, 2, 21, 22	d e, tD	248
METAL	IP65	IK10	1, 2, 21, 22	d e, tD	250
POLY	IP66/IP67	IK09	1, 2, 21, 22	db eb, tb	252
POLY	IP66/IP67	IK09	2, 22	ec, tc	254
POLY	IP66/IP67	IK09	1, 2, 21, 22	db eb, tb	258
POLY	IP66/IP67	IK09	2, 22	ec, tc	260
METAL	IP65/IP66	IK10	1, 2, 21, 22	d e, tD	264
METAL	IP65/IP66	IK10	1, 2, 21, 22	d e, tD	266
METAL	IP65/IP66	IK10	1, 2, 21, 22	d e, tD	268
POLY	IP65/IP66	IK08	1, 2, 21, 22	e, tb	272
METAL	IP65/IP66	IK09	1, 2, 21, 22	e or i, tb	278
METAL	IP66/IP67	IK09	1, 2, 21, 22	e or i, tb	282
METAL	IP66/IP67	IK09	1, 2, 21, 22	e or i, tb	286

## MAIN FEATURES

5 A

### PNCX CONNECTOR

Ex II 2 G D Ex e IIC, Ex tb IIIC

IP66/IP67/IP69

GRP casing



#### PNCX CONNECTORS FACILITATE THE COMPLIANCE OF ELECTRICAL INSTALLATION TO:

- the national regulations relating to the improvement of safety and health of workers at work in France, Italy, Spain, Belgium,
- the installation standards: IEC/EN 60079-14, IEC/HD 60364 (international) and NF C 15-100 (France).

#### PNCX connectors comply with:

- ATEX European Directive (affixing "Ex" symbol and CE marking),
- RoHS Directive (affixing CE marking),
- REACH European Regulation,
- IEC/EN 61984, IEC/EN 60529, IEC/EN 62262, IEC/EN 60079-0, IEC/EN 60079-7 and IEC/EN 60079-31 international and European standards.

#### PNCX CERTIFICATION BODIES

PNCX are certified by LCIE (ATEX and IECEEx), NANIO (TR CU EAC) and EXPLOLABS (SANS) (French, Russian and South African notified bodies).

20 A ➔ 63 A

### DXN DECONTACTOR™

Ex II 2 G D Ex db eb IIC, Ex tb IIIC

IP66/

Breaking capacity

GRP casing



**Zone 2-22**  
version available

#### DECONTACTOR™ DXN FACILITATE THE COMPLIANCE OF:

- electrical machinery to the Machinery European Directive regarding isolation device and to EN 60204-1 standard: Safety of machinery - electrical equipment of machines,
- electrical installation to French decree of 30 aout 2010 and 22 septembre 2010 relating to health and safety at work when using electrical installations,
- electrical installation to national regulation relating to the improvement of the safety and health of workers at work in Italy, Spain, Belgium,
- electrical installation to the installation standards: IEC/EN 60079-14, IEC/HD 60364 (international), NF C 15-100 (France) and CSA Z462 (Canada).

#### DECONTACTOR™ DXN comply with:

- ATEX European Directive (affixing "Ex" symbol and CE marking),
- RoHS Directive (affixing CE marking),
- REACH European Regulation,
- IEC/EN 60079-0, IEC/EN 60079-1, IEC/EN 60079-7, IEC/EN 60079-31, IEC/EN 60309-1 and IEC/EN 60309-4 standards.
- Bureau Veritas Marine specifications.

#### DXN CERTIFICATION BODIES

Products are certified by LCIE (ATEX and IECEEx), NANIO (TR CU EAC), NCC (INMETRO), KGS (KCS), CLMEx (Japan), EXPLOLABS (SANS) and cCSAus (French, South Korean, Russian, Brazilian, English [for Japan] and American and Canadian\* notified bodies) and BUREAU VERTIAS MARINE.

(\* for North American market.





20A

## DXA1 DECONTACTOR™

Ex II 2 G D Ex db eb IIC, Ex tb IIIC  
IP66/IP67

Breaking capacity

Low temperature resistance -55 °C

Metal casing



30A ➞ 200A

## DX DECONTACTOR™

Ex II 2 G D Ex de IIC, tD A21, IP65

Breaking capacity

Metal casing

Padlocking when connected or disconnected



### DECONTACTOR™ DXA1 AND DX FACILITATE THE COMPLIANCE OF:

- electrical machinery to the Machinery European Directive regarding isolation device and to EN 60204-1 standard: Safety of machinery electrical equipment of machines,
- electrical installation to French decree of 30 aout 2010 and 22 septembre 2010 relating to health and safety at work when using electrical installations,
- electrical installation to national regulation relating to the improvement of the safety and health of workers at work in Italy, Spain, Belgium,
- electrical installation to the installation standards: IEC/EN 60079-14, IEC/HD 60364 (international), NF C 15-100 (France), CSA Z462 (Canada).

### DECONTACTOR™ DXA1 and DX comply with:

- ATEX European Directive (affixing "Ex" symbol and CE marking),
- RoHS Directive (affixing CE marking),
- REACH European Regulation,
- IEC/EN 60079-0, IEC/EN 60079-1, IEC/EN 60079-7, IEC/EN 60079-31, IEC/EN 60309-1, IEC/EN 60309-4 standards.

### DXA1 CERTIFICATION BODIES

Products are certified by LCIE (ATEX and IECEx), KGS (KCS), NANIO (TR CU EAC) and cCSAus (French, South Korean, Russian and American and Canadian\* notified bodies).

(\* ) for North American market.



### DX CERTIFICATION BODIES

Products are certified by LCIE (ATEC and IECEx), NANIO (TR CU EAC) and EXPLOLABS (SANS) (French, Russian, South African notified bodies).



# 5 A

250 V  
U MAX / U

## CONNECTOR PNCX



MARECHAL ELECTRIC FRANCE

Ex II 2 G D      Ex e IIC      T6 Gb  
Ex tb IIIC      T72 °C Db  
-20 °C ≤ Ta ≤ +70 °C  
IECEx LCIE 16.0001X/LCIE 16 ATEX 3001X



IP66  
IP67  
IP69



0,75 mm<sup>2</sup>  
2,5 mm<sup>2</sup>



GRP



IK08



-20 °C  
+70 °C



ATEX



1, 2,  
21, 22

### OTHER FEATURES

Impulse withstand voltage	5 kV
Contact resistance	< 2 mΩ
Casing/insulator	Glass reinforced thermoplastics UL94 V-0
Load cycles	> 2 000 cycles
Salt mist	50 000 hours

### STANDARDS

International and European  
IEC/EN standards

61984, 60529, 62262, 60079-0, 60079-7 and 60079-31

Protection mode

e, tb

# REFERENCES AND ACCESSORIES



Coupler socket and plug caps  
are fitted as standard.

**SOCKET-  
OUTLET** female  
(with lock nut)  
**PNCX**



**INLET**  
male (with lock nut)  
**PNCX**



250 V AC 4P+T

06E4007

06E8007

**CABLE  
OUTER Ø**

**COUPLER  
SOCKET**  
female  
**PNCX**



**PLUG**  
male  
**PNCX**



250 V AC 4P+T

10-14 mm


06E3007

06E1007

OPTIONS	Reference
<b>PROTECTIVE CAPS</b>	
	Socket-outlet cap Inlet cap 01EA125 01EA126
<b>ADAPTER PLATE FOR DXN1 ACCESSORIES (SEE PAGE 239)</b>	
	251A457-E

HANDLE	Input/Cable outer Ø	Reference
<b>WITH INLET WITHOUT CABLE GLAND</b>		
	M20	06E1007417
<b>WITH SOCKET-OUTLET WITHOUT CABLE GLAND</b>		
	M20	06E3007417
CABLE GLAND	Input/Cable outer Ø	Reference
	5 - 9 mm	9PEM20EX-RED

# DRAWINGS AND DIMENSIONS



A

185

B

45

C

45

# 20 A

550 V  
U MAX / 

## DECONTACTATOR™ DXN1



MARECHAL ELECTRIC FRANCE

 II 2 G D

Ex db eb IIC T\* Gb

Ex tb IIIC T\* Db

\* -40 °C ≤ Ta ≤ +60 °C      T5      T90 °C

-40 °C ≤ Ta ≤ +40 °C      T6      T70 °C

IECEx LCI 09.0005X/LCIE 99 ATEX 6027 X



IP66  
IP67



1-4 mm<sup>2</sup> <sup>(1)</sup>  
1,5-6 mm<sup>2</sup> <sup>(2)</sup>



GRP



IK09



-40 °C  
+60 °C



AC-22  
AC-23



ATEX



1, 2,  
21, 22

(1) Flexible wiring [min.-max].  
(2) Stranded wiring [min.-max].

### TEMPERATURE RATING

Gas temperature classes

T6 for an ambient T° between -40 °C and +60 °C

T5 for an ambient T° between -40 °C and +60 °C

Dust surface temperature classes

Surface T° ≤ 70 °C for an ambient T° between -40 °C and +40 °C

Surface T° ≤ 90 °C for an ambient T° between -40 °C and +60 °C

  
Other configurations  
on request

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-1, 60079-7, 60079-31, 60309-1, 60309-4, 60947-3

Protection mode

db eb, tb

### SOCKET-OUTLET

female  
**DXN1**



**INLET\*** male  
**DXN1**



  
Each socket outlet  
or inlet must be  
associated with a box,  
a sleeve or a handle.

20-24 V AC	2P	251408A	251808A
220-250 V AC	1P+N+E	2514015	2518015
380-440 V AC	3P+E	2514013	2518013
380-440 V AC	3P+N+E	2514017	2518017
480-500 V AC	3P+E	2514093	2518093
480-500 V AC	3P+N+E	2514097	2518097

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

\* inlet cap included.

OPTIONS	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	399A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	251A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	611A346
<b>SELF CLOSING/SELF RETURNING LID</b>	
	Socket-outlet ref.+R
<b>COMPATIBILITY WITH DSN SOCKET-OUTLET (INDUSTRIAL RANGE)</b>	
	Contact us.
<b>SELF-EJECTION</b>	
	See page 192

WALL BOX	Incline angle	Input/ Cable outer Ø	Reference
<b>WALL BOX POLY WITH EX POLY CABLE GLAND</b>			
	30°	5-10 mm	251AB5316P
	30°	10-14 mm	251AB53
	30°	12-18 mm	251AB5325P
<b>WALL BOX POLY WITHOUT CABLE GLAND</b>			
	30°	M20	251AB53417
	30°	M25	251AB53418
<b>WALL BOX POLY WITH EX POLY CABLE GLAND</b>			
	70°	10-14 mm	251AB8820P
	70°	12-18 mm	251AB8825P
	70°	16-25 mm	251AB8832P
<b>WALL BOX POLY WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>			
	70°	8-10 mm	251AB8820M
	70°	12-14 mm	251AB8825M
	70°	18-24 mm	251AB8832M
<b>WALL BOX POLY WITH TERMINAL BLOCKS (IECEx LCIE 16.0042X/LCIE 16 ATEX 3054X)</b>			
	70°	10-14 mm	251A08820P <sup>[1]</sup>
	70°	12-18 mm	251A08825P <sup>[1]</sup>

1. Delivered with two predrilled entries fitted with 1 cable gland and 1 stopping plugs, 8+2 terminals up to 4 mm<sup>2</sup> with 2.5 mm<sup>2</sup> wires. Wiring : 1-4 mm<sup>2</sup>. For other configurations, contact us.

HANDLES	Cable outer Ø	Reference
<b>POLY HANDLE WITH GLAND EX POLY</b>		
	10-14 mm	251A753
	12-18 mm	251A25325P
	16-25 mm	251A25332P
<b>POLY HANDLE WITH EX POLY GLAND FOR SELF-EJECTION OPTION</b>		
	10-14 mm	251A463
	12-18 mm	251A44325P
<b>STRAIGHT POLY HANDLE WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>		
	8-10 mm	251A25320M
	12-14 mm	251A25325M
	18-24 mm	251A25332M

SLEEVE	Incline angle	Reference
<b>INCLINED POLY SLEEVE</b>		
	30°	251A057
	70°	251A757

# 20 A

440 V  
U MAX / I

## ZONE 2-22 PLUGS & SOCKETS DXN1



MARECHAL ELECTRIC FRANCE

II 3 G D

Ex ec IIC T\* Gc

Ex tc IIIC T\* Dc

\* -40 °C ≤ Ta ≤ +60 °C      T5      T95 °C  
-40 °C ≤ Ta ≤ +40 °C      T6      T75 °C

TF: MAR X 23.0002



IP66  
IP67



1-2,5 mm<sup>2</sup> <sup>(1)</sup>  
1,5-4 mm<sup>2</sup> <sup>(2)</sup>



GRP



IK09



-40 °C  
+60 °C



ATEX



2, 22



2 PIL. <sup>(3)</sup>

(1) Flexible wiring [min.-max].  
(2) Stranded wiring [min.-max].  
(3) Câblage souple 0,8 mm<sup>2</sup>.



Other configurations  
on request

### TEMPERATURE RATING

Gas temperature classes

T6 for an ambient T° between -40 °C and +60 °C

T5 for an ambient T° between -40 °C and +60 °C

Dust surface temperature classes

Surface T° ≤ 75 °C for an ambient T° between -40 °C and +40 °C

Surface T° ≤ 95 °C for an ambient T° between -40 °C and +60 °C

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-7, 60079-31

Protection mode

ec, tc

### SOCKET-OUTLET

female  
DXN1



INLET\* male  
DXN1



20-24 V AC

2P

251408AMZ2

251808AMZ2

220-250 V AC

1P+N+E

2514015MZ2

2518015MZ2

380-440 V AC

3P+E

2514013MZ2

2518013MZ2

380-440 V AC

3P+N+E

2514017MZ2

2518017MZ2

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

\* inlet cap included.


OPTIONS	Reference
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	399A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	251A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	611A346
<b>SELF CLOSING/SELF RETURNING LID</b>	
	Socket-outlet ref.+R
<b>COMPATIBILITY WITH DSN SOCKET-OUTLET (INDUSTRIAL RANGE)</b>	
	Contact us.

WALL BOX	Incline angle	Input/ Cable outer Ø	Reference
<b>WALL BOX POLY WITH EX POLY CABLE GLAND</b>			
	30°	5-10 mm	251AB5316P
	30°	10-14 mm	251AB53
	30°	12-18 mm	251AB5325P
<b>WALL BOX POLY WITHOUT CABLE GLAND</b>			
	30°	M20	251AB53417
	30°	M25	251AB53418
<b>WALL BOX POLY WITH EX POLY CABLE GLAND</b>			
	70°	10-14 mm	251AB8820P
	70°	12-18 mm	251AB8825P
	70°	16-25 mm	251AB8832P
<b>WALL BOX POLY WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>			
	70°	8-10 mm	251AB8820M
	70°	12-14 mm	251AB8825M
	70°	18-24 mm	251AB8832M
<b>WALL BOX POLY WITH TERMINAL BLOCKS (TF: MAR X 14.0001)</b>			
	70°	10-14 mm	Contact us
	70°	12-18 mm	Contact us


HANDLES	Cable outer Ø	Reference
<b>POLY HANDLE WITH GLAND EX POLY</b>		
	10-14 mm	251A753
	12-18 mm	251A25325P
	16-25 mm	251A25332P
<b>STRAIGHT POLY HANDLE WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>		
	8-10 mm	251A25320M
	12-14 mm	251A25325M
	18-24 mm	251A25332M

SLEEVE	Incline angle	Reference
<b>INCLINED POLY SLEEVE</b>		
	30°	251A057
	70°	251A757


# DRAWINGS AND DIMENSIONS

**PLUG ON SOCKET-OUTLET**


A	B	C	E
165	134	58	42

**COUPLER**

A	B	C
266	89	58


**PLUG ON 30° WALL MOUNTED SOCKET OUTLET**

A	B	C	D	E1	E2
209	180	68	90	36/56	79

**PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET**


A	B	C	D	E1	E2
208	264	138	126	117	105.5

PLUG ON 30° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
203	175	77	108	64	96

PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E
139	264	126	126	95



# 20 A

550 V  
U MAX / U<sub>MAX</sub>

## DECONTACTOR™ DXA1



MARECHAL ELECTRIC FRANCE

Ex II 2 G D

Ex db eb IIC T\* Gb  
Ex tb IIIC T\* Db

-55 °C ≤ Ta ≤ +40 °C      T6      T68 °C

-55 °C ≤ Ta ≤ +60 °C      T5      T88 °C

LCIE 15 ATEX 3033X/IECEx LCIE 15.0030X



IP66  
IP67



1-4 mm<sup>2</sup> <sup>(1)</sup>  
1,5-6 mm<sup>2</sup> <sup>(2)</sup>



METAL



IK10



-55 °C  
+60 °C



AC-22  
AC-23



ATEX



1, 2,  
21, 22



EMC

(1) Flexible wiring [min.-max.]  
(2) Stranded wiring [min.-max.]

### TEMPERATURE RATING

Gas temperature classes

T6 for an ambient T° between -55 °C and +40 °C

T5 for an ambient T° between -55 °C and +60 °C

Dust surface temperature classes

Surface T° ≤ 68 °C for an ambient T° between -55 °C and +40 °C

Surface T° ≤ 88 °C for an ambient T° between -55 °C and +60 °C

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-1, 60079-7, 60079-31, 60309-1, 60309-4, 60947-3

Protection mode

db eb, tb

<b>SOCKET-OUTLET</b> female <b>DXA1</b>		<b>PLUG male</b> <b>DXA1</b>
220-250 V AC	1P+N+E	2914015
380-440 V AC	3P+E	2914013
380-440 V AC	3P+N+E	2914017
		2918015
		2918013
		2918017

<b>WALL MOUNTING</b> socket female <b>DXA1</b>		<b>PLUG male</b> <b>DXA1</b>
220-250 V AC	1P+N+E M20 8-13 mm	2914015 + 291A053
220-250 V AC	1P+N+E M25 9-16 mm	2914015 + 291A05325M
220-250 V AC	1P+N+E M32 12-21 mm	2914015 + 291A653
380-440 V AC	3P+E M20 8-13 mm	2914013 + 291A053
380-440 V AC	3P+E M25 9-16 mm	2914013 + 291A05325M
380-440 V AC	3P+E M32 12-21 mm	2914013 + 291A653
380-440 V AC	3P+N+E M20 8-13 mm	2914017 + 291A053
380-440 V AC	3P+N+E M25 9-16 mm	2914017 + 291A05325M
380-440 V AC	3P+N+E M32 12-21 mm	2914017 + 291A653
		2918015 + 291A963
		2918015 + 291A95325M
		2918015 + 291A95332M
		2918013 + 291A963
		2918013 + 291A95325M
		2918013 + 291A95332M
		2918017 + 291A963
		2918017 + 291A95325M
		2918017 + 291A95332M

<b>INCLINED SOCKET</b> female <b>DXA1</b>		<b>INCLINED APPLIANCE</b> inlet male <b>DXA1</b>
220-250 V AC	1P+N+E	2914015 + 291A027
380-440 V AC	3P+E	2914013 + 291A027
380-440 V AC	3P+N+E	2914017 + 291A027
		2918015 + 291A027
		2918013 + 291A027
		2918017 + 291A027

<b>COUPLER SOCKET</b> female <b>DXA1</b>		<b>WALL MOUNTING</b> appliance inlet male <b>DXA1</b>
220-250 V AC	1P+N+E M20 8-13 mm	2914015 + 291A963
220-250 V AC	1P+N+E M25 9-16 mm	2914015 + 291A95325M
220-250 V AC	1P+N+E M32 12-21 mm	2914015 + 291A95332M
380-440 V AC	3P+E M20 8-13 mm	2914013 + 291A963
380-440 V AC	3P+E M25 9-16 mm	2914013 + 291A95325M
380-440 V AC	3P+E M32 12-21 mm	2914013 + 291A95332M
380-440 V AC	3P+N+E M20 8-13 mm	2914017 + 291A963
380-440 V AC	3P+N+E M25 9-16 mm	2914017 + 291A95325M
380-440 V AC	3P+N+E M32 12-21 mm	2914017 + 291A95332M
		2918015 + 291A053
		2918013 + 291A053
		2918017 + 291A053
		2918017 + 291A05325M
		2918017 + 291A05332M
		2918013 + 291A653
		2918013 + 291A653
		2918017 + 291A053
		2918017 + 291A05325M
		2918017 + 291A653

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

<b>OPTIONS</b>	<b>Reference</b>
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCKS NOT SUPPLIED)</b>	
	Ref. + 843
<b>INLET CAP IP66/IP67</b>	
	291A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	291A346

For other Ex cable glands, contact us.



#### ELECTROMAGNETIC COMPATIBILITY (EMC)


NEW




Please order an Ex EMC cable gland  
to be found on page 318.

# DRAWINGS AND DIMENSIONS


PLUG




MOBILE SOCKET

A  
170B  
79C  
70A  
185B  
103C  
78

SOCKET MOUNTED ON 30° WALL BOX M20 - M25






SOCKET MOUNTED ON 30° WALL BOX M32







A	B	C	D	E1	E2
178	156	84	95	70	76

A	B	C	D	E1	E2

**SOCKET ON 30° INCLINED SLEEVE****PLUG ON 30° INCLINED SLEEVE**

A	B	C	D	E1	E2
120	140	77	108	63	95

A	B	C	D	E1	E2
98	117	77	108	63	95

**PLUG ON 30° WALL BOX M20 - M25**


A	B	C	D	E1	E2
157	133	84	95	70	76

A	B	C	E1	E2
159	119	110	70	94

# 20 A

750 V  
U MAX / U

## DECONTACTATOR™ DX1



### MARECHAL ELECTRIC FRANCE

Ex II 2 G D      Ex de IIC      tD A21  
-25 °C ≤ Ta ≤ +60 °C      T5      T84 °C  
-25 °C ≤ Ta ≤ +50 °C      T6      T74 °C  
IECEx LCI 09.0014/LCIE 05 ATEX 6127



IP65

2.5-10 mm<sup>2</sup> <sup>(1)</sup>

METAL



IK10

-25 °C  
+60 °C

ATEX

1, 2,  
21, 22

EMC

(1) Flexible and stranded wiring (min.-max.).



Other configurations  
on request

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-1, 60079-7, 60079-31, 60309-1, 60309-4,

Protection mode

de, tD

Locking position  
connected or  
disconnected by  
lockable shaft.



Each socket outlet  
or inlet must be  
associated with a box,  
a sleeve or a handle.

SOCKET-OUTLET  
female  
DX1



INCLINED  
APPLIANCE  
inlet  
DX1



PLUG  
male  
DX1



220-250 V AC	1P+N+E	2624015	2626015	8-13 mm	2621015
380-440 V AC	3P+E	2624013	2626013	8-13 mm	2621013
380-440 V AC	3P+N+E	2624017	2626017	8-13 mm	2621017

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

## REFERENCES ACCESSORIES

WALL BOX	Cable gland entry	Cable outer Ø	Reference
<b>WALL BOX METAL 90° EX METAL CABLE GLAND INCLUDED*</b>			
	M20	8-13 mm	262AB53
	M25	9-16 mm	262AB5325M
	M32	12-21 mm	262AB5332M

\* Optional versions for earth continuity are available, please contact us


HANDLES	Cable gland entry	Cable outer Ø	Reference
<b>STRAIGHT HANDLE METAL BOX EX METAL CABLE GLAND INCLUDED*</b>			
	M20	8-13 mm	262A963
	M25	9-16 mm	262A95325M
	M32	12-21 mm	262A9532M

OPTIONS	Reference
<b>INLET CAP IP66/IP67</b>	
	262A926


<b>ELECTROMAGNETIC COMPATIBILITY (EMC)</b>		<b>NEW</b>
Please order a metal accessory herewith, together with a Ex EMC cable gland to be found on page 318.		

## DRAWINGS AND DIMENSIONS

PLUG ON WALL MOUNTED SOCKET



COUPLER




A1	A2	B	C	E1	E2	E3
115	145	341	129	90	118	168

A	B	C
116	154	352

# 32 A

750 V  
U MAX / U

## DECONTACTATOR™ DX3



MARECHAL ELECTRIC FRANCE

II 2 G D Ex de IIC tD A21  
-25 °C ≤ Ta ≤ +60 °C T5 T84 °C  
-25 °C ≤ Ta ≤ +50 °C T6 T74 °C  
IECEx LCI 09.0014/LCIE 05 ATEX 6127



IP65



2,5-10 mm<sup>2</sup> <sup>(1)</sup>



METAL



IK10



-25 °C  
+60 °C



ATEX



1, 2,  
21, 22



EMC

<sup>(1)</sup> Flexible and stranded wiring (min.-max.).



Other configurations  
on request

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-1, 60079-7, 60079-31, 60309-1, 60309-4,

Protection mode

de, tD

Locking position  
connected or  
disconnected by  
lockable shaft.



Each socket outlet  
or inlet must be  
associated with a box,  
a sleeve or a handle.



**SOCKET-OUTLET**  
female  
**DX3**



**INCLINED  
APPLIANCE**  
inlet  
**DX3**



**PLUG**  
male  
**DX3**



220-250 V AC	1P+N+E	2634015	2636015	9-16 mm	2631015
380-440 V AC	3P+E	2634013	2636013	9-16 mm	2631013
380-440 V AC	3P+N+E	2634017	2636017	9-16 mm	2631017

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

## REFERENCES ACCESSORIES

WALL BOX	Cable gland entry	Cable outer Ø	Reference
<b>WALL BOX METAL 90° EX METAL CABLE GLAND INCLUDED*</b>			
	M20	8-13 mm	263AB5320M
	M25	9-16 mm	263AB53
	M32	12-21 mm	263AB5332M

\* Optional versions for earth continuity are available, please contact us


HANDLES	Cable gland entry	Cable outer Ø	Reference
<b>STRAIGHT HANDLE METAL BOX EX METAL CABLE GLAND INCLUDED*</b>			
	M20	8-13 mm	263A95320M
	M25	9-16 mm	263A963
	M32	12-21 mm	263A95332M

OPTIONS	Reference
<b>INLET CAP IP66/IP67</b>	
	263A926


ELECTROMAGNETIC COMPATIBILITY (EMC)	NEW
 Please order a metal accessory herewith, together with a Ex EMC cable gland to be found on page 318.	

## DRAWINGS AND DIMENSIONS

PLUG ON WALL MOUNTED SOCKET OUTLET



COUPLER



A1	A2	B	C	E1	E2	E3
115	145	341	129	90	118	168

A	B	C
116	154	352

# 32 A

750 V  
U MAX / I

## DECONTACTATOR™ DXN3



MARECHAL ELECTRIC FRANCE

II 2 G D

Ex db eb IIC T\* Gb

Ex tb IIIC T\* Db

\* -40 °C ≤ Ta ≤ +60 °C      T5      T77 °C

-40 °C ≤ Ta ≤ +40 °C      T6      T57 °C

IECEx LCI 09.0006X/LCIE 05 ATEX 6149X



IP66  
IP67



2,5-10 mm<sup>2</sup><sup>(1)</sup>  
2,5-16 mm<sup>2</sup><sup>(2)</sup>



GRP



IK09



-40 °C  
+60 °C



AC-22



ATEX



1, 2,  
21, 22

[1] Flexible wiring (min.-max.).  
[2] Stranded wiring (min.-max.).

### TEMPERATURE RATING

Gas temperature classes

T6 for an ambient T° between -40 °C and +60 °C

T5 for an ambient T° between -40 °C and +60 °C

Dust surface temperature classes

Surface T° ≤ 57 °C for an ambient T° between -40 °C and +40 °C

Surface T° ≤ 77 °C for an ambient T° between -40 °C and +60 °C



Other configurations  
on request

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-1, 60079-7, 60079-31, 60309-1, 60309-4, 60947-3

Protection mode

db eb, tb

**SOCKET-OUTLET**  
female  
**DXN3**



**INLET** male  
**DXN3**



20-24 V AC	2P	253408A	253808A
220-250 V AC	1P+N+E	2534015	2538015
380-440 V AC	3P+E	2534013	2538013
380-440 V AC	3P+N+E	2534017	2538017
480-500 V AC	3P+E	2534093	2538093
480-500 V AC	3P+N+E	2534097	2538097
550 V AC - Auxiliaries 5 A	+ 2 contacts	Ref. + 972	Ref. + 972

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

OPTIONS	Reference	WALL BOX	Incline angle	Input/ Cable outer Ø	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)</b>					
	Socket-outlet ref. +843		30°	10-14 mm	253AB53
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>					
	613A541		30°	12-18 mm	253AB5325P
<b>LARGER RELEASE BUTTON</b>					
	Ref. socket +453		30°	M20	253AB53417
<b>INLET CAP IP66/IP67</b>					
	253A426		30°	M25	253AB53418
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>					
	613A346		70°	10-14 mm	253AB8820P
<b>SELF CLOSING/SELF RETURNING LID</b>					
	Socket-outlet ref.+R		70°	12-18 mm	253AB8825P
<b>COMPATIBILITY WITH DSN SOCKET-OUTLET (INDUSTRIAL RANGE)</b>					
	Contact us.	120 X 120 mm	70°	16-25 mm	253AB8832P
<b>SELF-EJECTION</b>					
	See page 192		70°	8-10 mm	253AB8820M
				12-14 mm	253AB8825M
		120 X 120 mm	70°	18-24 mm	253AB8832M
<b>WALL BOX POLY WITH TERMINAL BLOCKS (IECEx LCIE 16.0042X/LCIE 16 ATEX 3054X)</b>					
			70°	10-14 mm	253A08820P <sup>[1]</sup>
		120 X 120 mm	70°	12-18 mm	253A08825P <sup>[1]</sup>
<b>IN THIS CONFIGURATION</b> $U_{MAX} = 630 V$					


1. Delivered with two predrilled entries fitted with 1 cable gland and 1 stopping plug, 8+2 terminals up to 10 mm<sup>2</sup> with 6 mm<sup>2</sup> wires. Wiring : 2.5-10 mm<sup>2</sup>. For other configurations, contact us.

HANDLE	Cable outer Ø	Reference	SLEEVE	Incline angle	Reference
<b>POLY HANDLE WITH GLAND EX POLY</b>					
	10-14 mm	253A753		30°	253A027
	12-18 mm	253A783			
	16-25 mm	253A25332P		70°	253A757
	22-32 mm	253A25340P			
<b>POLY HANDLE WITH EX POLY GLAND FOR SELF-EJECTION OPTION</b>					
	10-14 mm	253A463			
	12-18 mm	253A44325P			
	16-25 mm	253A44332P			
<b>STRAIGHT POLY HANDLE WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>					
	8-10 mm	253A25320M			
	12-14 mm	253A25325M			
	18-24 mm	253A25332M			

# 40 A

690 V  
U MAX / 

## ZONE 2-22 PLUGS & SOCKETS DXN3



MARECHAL ELECTRIC FRANCE  
 Ex II 3 G D      Ex ec IIC      T\* Gc  
 Ex tc IIIC      T\* Dc  
 \* -40 °C ≤ Ta ≤ +60 °C      T4      T115 °C  
 -40 °C ≤ Ta ≤ +40 °C      T5      T95 °C  
 TF: MAR X 23.0001



IP66  
IP67



2,5-6 mm<sup>2</sup><sup>(1)</sup>  
2,5-10 mm<sup>2</sup><sup>(2)</sup>



GRP



IK09



-40 °C  
+60 °C



ATEX



2, 22

[1] Flexible wiring (min.-max.).  
 [2] Stranded wiring (min.-max.).

### TEMPERATURE RATING

Gas temperature classes      T5 for an ambient T° between -40 °C and +40 °C

T4 for an ambient T° between -40 °C and +60 °C

Dust surface temperature classes

Surface T° ≤ 95 °C for an ambient T° between -40 °C and +40 °C

Surface T° ≤ 115 °C for an ambient T° between -40 °C and +60 °C



Other configurations  
on request

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-7, 60079-31

Protection mode

ec, tc

**SOCKET-OUTLET**  
female  
**DXN3**



**INLET** male  
**DXN3**



20-24 V AC	2P	253408AMZ2	253808AMZ2
220-250 V AC	1P+N+E	2534015MZ2	2538015MZ2
380-440 V AC	3P+E	2534013MZ2	2538013MZ2
380-440 V AC	3P+N+E	2534017MZ2	2538017MZ2
480-500 V AC	3P+E	2534193MZ2	2538193MZ2
480-500 V AC	3P+N+E	2534197MZ2	2538197MZ2
400 V AC - Auxiliaries 30 A	+ 2 contacts	Ref. + 972MZ2	Ref. + 972MZ2


► Other currents, voltages, frequencies and contact configurations are available (see page 14).

OPTIONS	Reference	WALL BOX	Incline angle	Input/ Cable outer Ø	Reference
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>					
	613A541		30°	10-14 mm	253AB53
<b>LARGER RELEASE BUTTON</b>					
	Ref. socket +453		30°	12-18 mm	253AB5325P
<b>INLET CAP IP66/IP67</b>					
	253A426		30°	M20	253AB53417
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>					
	613A346		70°	10-14 mm	253AB8820P
<b>SELF CLOSING/SELF RETURNING LID</b>					
	Socket-outlet ref.+R		70°	12-18 mm	253AB8825P
<b>COMPATIBILITY WITH DSN SOCKET-OUTLET (INDUSTRIAL RANGE)</b>					
	Contact us.	120 X 120 mm	70°	16-25 mm	253AB8832P
<b>WALL BOX POLY WITH EX POLY CABLE GLAND</b>					
			70°	8-10 mm	253AB8820M
			70°	12-14 mm	253AB8825M
		120 X 120 mm	70°	18-24 mm	253AB8832M
<b>WALL BOX POLY WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>					
			70°	10-14 mm	253AB8820M
			70°	12-18 mm	253AB8825M
<b>WALL BOX POLY WITH TERMINAL BLOCKS (TF: MAR X 14.0001)</b>					
			70°	10-14 mm	Contact us
		120 X 120 mm	70°	12-18 mm	Contact us

HANDLE	Cable outer Ø	Reference	SLEEVE	Incline angle	Reference
<b>POLY HANDLE WITH GLAND EX POLY</b>					
	10-14 mm	253A753		30°	253A027
	12-18 mm	253A783			
	16-25 mm	253A25332P			
	22-32 mm	253A25340P			
<b>STRAIGHT POLY HANDLE WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>					
	8-10 mm	253A25320M		70°	253A757
	12-14 mm	253A25325M			
	18-24 mm	253A25332M			


## DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
190	171	77	48

COUPLER




A	B	C
304	71	118

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
226	191	84	84	71	71

A	B	C	D	E1	E2
208	264	138	126	117	105.5

**PLUG ON 30° INCLINED SOCKET-OUTLET**



**PLUG ON 70° INCLINED SOCKET-OUTLET**



A	B	C	D	E1	E2
201	204	77	108	64	96

A	B	C	D	E
148	275	126	126	95



# 63 A

750 V  
U MAX / 

## DECONTACTATOR™ DXN6



MARECHAL ELECTRIC FRANCE

 II 2 G D

Ex db eb IIC T\* Gb

Ex tb IIIC T\* Db

\* -40 °C ≤ Ta ≤ +60 °C T4 T107 °C

-40 °C ≤ Ta ≤ +40 °C T5 T87 °C

IECEx LCI 09.0007X/LCIE 05 ATEX 6150X



IP66  
IP67



6-16 mm<sup>2</sup> <sup>(1)</sup>  
6-25 mm<sup>2</sup> <sup>(2)</sup>



GRP



IK09



-40 °C  
+60 °C



AC-22



ATEX



1, 2,  
21, 22

(1) Flexible wiring [min.-max].  
(2) Stranded wiring [min.-max].

### TEMPERATURE RATING

Gas temperature classes

T5 for an ambient T° between -40 °C and +60 °C

T4 for an ambient T° between -40 °C and +60 °C

Dust surface temperature classes

Surface T° ≤ 87 °C for an ambient T° between -40 °C and +40 °C

Surface T° ≤ 107 °C for an ambient T° between -40 °C and +60 °C



Other configurations  
on request

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-1, 60079-7, 60079-31, 60309-1, 60309-4, 60947-3

Protection mode

db eb, tb

**SOCKET-OUTLET**  
female  
**DXN6**



**INLET** male  
**DXN6**



20-24 V AC	2P	256408A	256808A
220-250 V AC	1P+N+E	2564015	2568015
380-440 V AC	3P+E	2564013	2568013
380-440 V AC	3P+N+E	2564017	2568017
480-500 V AC	3P+E	2564093	2568093
480-500 V AC	3P+N+E	2564097	2568097
550 V AC - Auxiliaries 5 A	+ 2 contacts	Ref. + 972	Ref. + 972

► Other currents, voltages, frequencies and contact configurations are available (see page 14).




Each socket outlet  
or inlet must be  
associated with a box,  
a sleeve or a handle.

OPTIONS	Reference
<b>LOCKING PIN FOR 2 PADLOCKS Ø 4 TO 8 mm (PADLOCK NOT SUPPLIED)</b>	
	Socket-outlet ref. +843
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	613A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	256A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
	616A346
<b>SELF CLOSING/SELF RETURNING LID</b>	
	Socket-outlet ref.+R
<b>COMPATIBILITY WITH DSN SOCKET-OUTLET (INDUSTRIAL RANGE)</b>	
	Contact us.
<b>SELF-EJECTION</b>	
	See page 192

WALL BOX	Incline angle	Input/ Cable outer Ø	Reference
<b>WALL BOX POLY WITH EX POLY CABLE GLAND</b>			
	30°	12-18 mm	256AB53
<b>WALL BOX POLY WITHOUT CABLE GLAND</b>			
	30°	M25	256AB53418
<b>WALL BOX POLY WITH EX POLY CABLE GLAND</b>			
	70°	10-14 mm	256AB8820P
	70°	12-18 mm	256AB8825P
	70°	16-25 mm	256AB8832P
	70°	22-32 mm	256AB8840P
<b>WALL BOX POLY WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>			
	70°	8-10 mm	256AB8820M
	70°	12-14 mm	256AB8825M
	70°	18-24 mm	256AB8832M
<b>WALL BOX POLY WITH TERMINAL BLOCKS (IECEx LCIE 16.0042X/LCIE 16 ATEX 3054X)</b>			
	70°	10-14 mm	256A08820P <sup>[1]</sup>
	70°	12-18 mm	256A08825P <sup>[1]</sup>
	70°	16-25 mm	256A08832P <sup>[1]</sup>
	70°	22-32 mm	256A08840P <sup>[1]</sup>
<b>IN THIS CONFIGURATION</b>			
$U_{MAX} = 630 V$ $-40^{\circ}C \leq T_a \leq +55^{\circ}C$ T4 T105° C $-40^{\circ}C \leq T_a \leq +50^{\circ}C$ T5 T95° C			

1. Delivered with two predrilled entries fitted with 1 cable gland and 1 stopping plug, 8+2 terminals up to 16 mm<sup>2</sup> with 16 mm<sup>2</sup> wires. Wiring : 6-16 mm<sup>2</sup>. For other configurations, contact us.

HANDLE	Cable outer Ø	Reference
<b>POLY HANDLE WITH GLAND EX POLY</b>		
	10-14 mm	256A25320P
	12-18 mm	256A753
	16-25 mm	256A25332P
	22-32 mm	256A25340P
<b>POLY HANDLE WITH EX POLY GLAND FOR SELF-EJECTION OPTION</b>		
	12-18 mm	256A463
	16-25 mm	256A44332P
	22-32 mm	256A44340P
<b>STRAIGHT POLY HANDLE WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>		
	8-10 mm	256A25320M
	12-14 mm	256A25325M
	18-24 mm	256A25332M

SLEEVE	Incline angle	Reference
<b>INCLINED POLY SLEEVE</b>		
	30°	256A027
	70°	256A757

# 63 A

1000 V  
U MAX / I

## ZONE 2-22 PLUGS & SOCKETS DXN6



MARECHAL ELECTRIC FRANCE  
 Ex II 3 G D      Ex ec IIC      T\* Gc  
 Ex tc IIIC      T\* Dc  
 \* -40 °C ≤ Ta ≤ +60 °C      T4      T105 °C  
 -40 °C ≤ Ta ≤ +40 °C      T5      T85 °C  
 TF: MAR X 23.0003



IP66  
IP67



6-16 mm<sup>2</sup> <sup>(1)</sup>  
10-25 mm<sup>2</sup> <sup>(2)</sup>



GRP



IK09



-40 °C  
+60 °C



ATEX



2, 22

(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

### TEMPERATURE RATING

Gas temperature classes

T5 for an ambient T° between -40 °C and +40 °C

T4 for an ambient T° between -40 °C and +60 °C

Dust surface temperature classes

Surface T° ≤ 85 °C for an ambient T° between -40 °C and +40 °C

Surface T° ≤ 105 °C for an ambient T° between -40 °C and +60 °C



Other configurations  
on request

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-7, 60079-31

Protection mode

ec, tc

**SOCKET-OUTLET**  
female  
**DXN6**



**INLET** male  
**DXN6**



20-24 V AC	2P	256408AMZ2	256808AMZ2
220-250 V AC	1P+N+E	2564015MZ2	2568015MZ2
380-440 V AC	3P+E	2564013MZ2	2568013MZ2
380-440 V AC	3P+N+E	2564017MZ2	2568017MZ2
480-500 V AC	3P+E	2564193MZ2	2568193MZ2
480-500 V AC	3P+N+E	2564197MZ2	2568197MZ2
400 V AC - Auxiliaries 16 A	+ 2 contacts	Ref. + 972MZ2	Ref. + 972MZ2

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

OPTIONS	Reference
<b>SAFETY HASP FOR UP TO 6 PADLOCKS</b>	
	613A541
<b>LARGER RELEASE BUTTON</b>	
	Ref. socket +453
<b>INLET CAP IP66/IP67</b>	
	256A426
<b>IN-LINE CONNECTIONS (A PAIR OF FINGER DRAW PLATES TO AID CLOSING)</b>	
 	616A346
<b>SELF CLOSING/SELF RETURNING LID</b>	
	Socket-outlet ref.+R
<b>COMPATIBILITY WITH DSN SOCKET-OUTLET (INDUSTRIAL RANGE)</b>	
	Contact us.


WALL BOX	Incline angle	Input/ Cable outer Ø	Reference
<b>WALL BOX POLY WITH EX POLY CABLE GLAND</b>			
	30°	12-18 mm	256AB53
<b>WALL BOX POLY WITHOUT CABLE GLAND</b>			
	30°	M25	256AB53418
<b>WALL BOX POLY WITH EX POLY CABLE GLAND</b>			
	70°	10-14 mm	256AB8820P
	70°	12-18 mm	256AB8825P
 160 X 160 mm	70°	16-25 mm	256AB8832P
 160 X 160 mm	70°	22-32 mm	256AB8840P
<b>WALL BOX POLY WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>			
	70°	8-10 mm	256AB8820M
	70°	12-14 mm	256AB8825M
 160 X 160 mm	70°	18-24 mm	256AB8832M
<b>WALL BOX POLY WITH TERMINAL BLOCKS (TF: MAR X 23.0003)</b>			
	70°	10-14 mm	Contact us
	70°	12-18 mm	Contact us
 160 X 160 mm	70°	16-25 mm	Contact us
 160 X 160 mm	70°	22-32 mm	Contact us

HANDLE	Cable outer Ø	Reference
<b>POLY HANDLE WITH GLAND EX POLY</b>		
	10-14 mm	256A25320P
	12-18 mm	256A753
	16-25 mm	256A25332P
	22-32 mm	256A25340P
<b>STRAIGHT POLY HANDLE WITH METAL CABLE GLAND WITH EARTH CONTINUITY</b>		
	8-10 mm	256A25320M
	12-14 mm	256A25325M
	18-24 mm	256A25332M

SLEEVE	Incline angle	Reference
<b>INCLINED POLY SLEEVE</b>		
	30°	256A027
	70°	256A757


# DRAWINGS AND DIMENSIONS

PLUG ON SOCKET-OUTLET




A	B	C	E
218	195	84	55

COUPLER




A	B	C
350	84	122

PLUG ON 30° WALL MOUNTED SOCKET OUTLET




A	B	C	D	E1	E2
265	225	89	100	77	89

PLUG ON 70° WALL-MOUNTED SOCKET-OUTLET




A	B	C	D	E1	E2
244	341	175	166	157	145.5

PLUG ON 30° INCLINED SOCKET-OUTLET



PLUG ON 70° INCLINED SOCKET-OUTLET



A	B	C	D	E1	E2
239	219	77	108	64	96

A	B	C	D	E
175	341	166	166	135



# 63 A

750 V  
U MAX

## DECONTACTATOR™ DX6



MARECHAL ELECTRIC FRANCE

II 2 G D Ex de IIC tD A21  
-40 °C ≤ Ta ≤ +60 °C T5 T90 °C  
-40 °C ≤ Ta ≤ +50 °C T6 T80 °C  
IECEx LCI 09.0015/LCIE 04 ATEX 6038



IP65  
IP66



16-35 mm<sup>2</sup> <sup>(1)</sup>  
16-50 mm<sup>2</sup> <sup>(2)</sup>



METAL



IK10



-40 °C  
+60 °C



ATEX



1, 2,  
21, 22



EMC

<sup>(1)</sup> Flexible wiring (min.-max.).  
<sup>(2)</sup> Stranded wiring (min.-max.).

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-1, 60079-7, 60079-31, 60309-1, 60309-4,

de, tD

Protection mode

60079-0, 60079-1, 60079-7, 60079-31, 60309-1, 60309-4,



Other configurations  
on request

Locking position  
connected or  
disconnected by  
lockable shaft.



Each socket outlet  
or inlet must be  
associated with a box,  
a sleeve or a handle.



**SOCKET-OUTLET**  
female  
**DX6**



**INCLINED APPLIANCE**  
inlet  
**DX6**



**PLUG**  
male  
**DX6**



220-250 V AC	1P+N+E	2664015	2666015	12-21 mm	2661015
380-440 V AC	3P+E	2664013	2666013	12-21 mm	2661013
380-440 V AC	3P+N+E	2664017	2666017	12-21 mm	2661017

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

## REFERENCES ACCESSORIES

WALL BOX	Cable gland entry	Cable outer Ø	Reference
<b>WALL BOX METAL 90° EX METAL CABLE GLAND INCLUDED*</b>			
	M25	9-16 mm	266AB5325M
	M32	12-21 mm	266AB53
	M40	16-27 mm	266AB5340M

\* Optional versions for earth continuity are available, please contact us


HANDLES	Cable gland entry	Cable outer Ø	Reference
<b>STRAIGHT HANDLE METAL BOX EX METAL CABLE GLAND INCLUDED*</b>			
	M25	9-16 mm	266A95325M
	M32	12-21 mm	266A963
	M40	16-27 mm	266A95340M

OPTIONS	Reference
<b>INLET CAP IP66/IP67</b>	
	266A926

**ELECTROMAGNETIC COMPATIBILITY (EMC)**   
 Please order a metal accessory herewith,  
together with a Ex EMC cable gland  
to be found on page 318.


## DRAWINGS AND DIMENSIONS

PLUG ON WALL MOUNTED SOCKET OUTLET



A	B	C	E1	E2	E3
221	511	173	130	173	195

COUPLER




A	B	C
582	212	160

# 125 A

750 V  
U MAX / I

## DECONTACTATOR™ DX9



MARECHAL ELECTRIC FRANCE

II 2 G D Ex de IIC tD A21  
-40 °C ≤ Ta ≤ +60 °C T5 T90 °C  
-40 °C ≤ Ta ≤ +50 °C T6 T80 °C  
IECEx LCI 09.0015/LCIE 04 ATEX 6038



IP65  
IP66



35-50 mm<sup>2</sup> <sup>(1)</sup>  
50-70 mm<sup>2</sup> <sup>(2)</sup>



METAL



IK10



-40 °C  
+60 °C



ATEX



1, 2,  
21, 22



EMC



(1) Flexible wiring (min.-max.).  
(2) Stranded wiring (min.-max.).

Other configurations  
on request

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-1, 60079-7, 60079-31, 60309-1, 60309-4,

Protection mode

de, tD

Locking position  
connected or  
disconnected by  
lockable shaft.

**SOCKET-OUTLET**  
female  
**DX9**



**INCLINED APPLIANCE**  
inlet  
**DX9**



**PLUG**  
male  
**DX9**



380-440 V AC	3P+E	2694013	2696013	16-27 mm	2691013
				23-35 mm	269101350M
				36-48 mm	269101363M
380-440 V AC	3P+N+E	2694017	2696017	16-27 mm	2691017
				23-35 mm	269101750M
				36-48 mm	269101763M

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

## REFERENCES ACCESSORIES

WALL BOX	Cable gland entry	Cable outer Ø	Reference
<b>WALL BOX METAL 90° EX METAL CABLE GLAND INCLUDED*</b>			
	M32	12-21 mm	269AB5332M
	M40	16-27 mm	269AB53
	M50	23-35 mm	269AB5350M
	M63	36-48 mm	269AB5363M

\* Optional versions for earth continuity are available, please contact us


HANDLES	Cable gland entry	Cable outer Ø	Reference
<b>STRAIGHT HANDLE METAL BOX EX METAL CABLE GLAND INCLUDED*</b>			
	M32	12-21 mm	269A95332M
	M40	16-27 mm	269A963
	M50	23-35 mm	269A95350M
	M63	36-48 mm	269A95363M

OPTIONS	Reference
INLET CAP IP66/IP67	269A926

ELECTROMAGNETIC COMPATIBILITY (EMC)	NEW
Please order a metal accessory herewith, together with a Ex EMC cable gland to be found on page 318.	


## DRAWINGS AND DIMENSIONS

PLUG ON WALL MOUNTED SOCKET OUTLET



A	B	C	E1	E2	E3
221	511	173	130	173	195

COUPLER



A	B	C
582	212	160

# 200 A

750 V  
U MAX / U

## DECONTACTATOR™ DX2



MARECHAL ELECTRIC FRANCE

II 2 G D Ex de IIC tD A21  
-40 °C ≤ Ta ≤ +60 °C T3 T91 °C  
IECEx LCI 09.0015/LCIE 04 ATEX 6038



IP65  
IP66



50 mm<sup>2</sup> <sup>(1)</sup>  
70 mm<sup>2</sup> <sup>(2)</sup>



METAL



IK10



-40 °C  
+60 °C



ATEX



1, 2,  
21, 22



EMC



[1] Flexible wiring.  
[2] Stranded wiring.

Other configurations  
on request

Locking position  
connected or  
disconnected by  
lockable shaft.

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-1, 60079-7, 60079-31, 60309-1, 60309-4,

Protection mode

de, tD



Each socket outlet  
or inlet must be  
associated with a box,  
a sleeve or a handle.

SOCKET-OUTLET  
female  
**DX2 (200 A)**



INCLINED  
APPLIANCE  
inlet  
**DX2 (200 A)**



PLUG  
male  
**DX2 (200 A)**



380-440 V AC	3P+E	2674013	2676013	36-48 mm	2671013
380-440 V AC	3P+N+E	2674017	2676017	36-48 mm	2671017

► Other currents, voltages, frequencies and contact configurations are available (see page 14).

## REFERENCES ACCESSORIES

WALL BOX	Cable gland entry	Cable outer Ø	Reference
<b>WALL BOX METAL 90° EX METAL CABLE GLAND INCLUDED*</b>			
	M63	36-48 mm	267AB53

\* Optional versions for earth continuity are available, please contact us


HANDLES	Cable gland entry	Cable outer Ø	Reference
<b>STRAIGHT HANDLE METAL BOX EX METAL CABLE GLAND INCLUDED*</b>			
	M63	36-48 mm	267A963

OPTIONS	Reference
<b>INLET CAP IP66/IP67</b>	
	267A926

ELECTROMAGNETIC COMPATIBILITY (EMC)	NEW
 Please order a metal accessory herewith, together with a Ex EMC cable gland to be found on page 318.	


## DRAWINGS AND DIMENSIONS

PLUG ON WALL MOUNTED SOCKET OUTLET



A	B	C	E1	E2	E3
221	511	173	130	173	195

COUPLER



A	B	C
582	212	160

**680 A**

# SPeX SINGLE POLE CONNECTOR



## SPeX SINGLE POLE CONNECTORS COMPLY WITH:

- ATEX European Directive (affixing "Ex" symbol and CE marking),
- RoHS Directive (affixing CE marking),
- REACH European Regulation,
- IEC/EN 60079-0, IEC/EN 60079-7 and IEC/EN 60079-31 international and European standards,
- BUREAU VERITAS Marine specifications.

## SPeX CERTIFICATION BODIES

SPeX are certified by LCIE (ATEX and IECEEx), NANIO (TR CU EAC) and cCSAus (french, russian and americano-canadian\* notified bodies).

\* for North American market.



## THE HIGHEST POSSIBLE SAFETY

- IP2X socket-outlet when cap removed,
- Automatic IP65/IP66 when plug is connected.

## AN EASY-TO-USE CONNECTOR

- Straight insertion of the plug into the socket-outlet,
- Different mechanical keying for L1, L2, L3, N and E, positive and negative (DC)
- Visual identification by standard colours.

## SPeX ATEX CLASSIFICATION ACCORDING TO CABLE CROSS-SECTION AND AMBIENT TEMPERATURE

	-20 °C ≤ Ta ≤ +40 °C G D T5/T56 °C	-20 °C ≤ Ta ≤ +40 °C G D T6/T56 °C	-20 °C ≤ Ta ≤ +60 °C G D T5/T76 °C
70 mm <sup>2</sup>	290 A	235 A	235 A
95 mm <sup>2</sup>	415 A	335 A	335 A
120 mm <sup>2</sup>	456 A	376 A	376 A
150 mm <sup>2</sup>	493 A	415 A	415 A
185 mm <sup>2</sup>	530 A	450 A	450 A
240 mm <sup>2</sup>	570 A	497 A	497 A
300 mm <sup>2</sup>	620 A	540 A	540 A
400 mm <sup>2</sup>	680 A	600 A	600 A

## PERFORMANCES

With 240 mm<sup>2</sup> wiring, the SPeX accepts a permanent current up to 570 A/1000 V AC with T5 EX classification at 40 °C ambient temperature.


 II 2 G D Ex e IIC, Ex tb IIIC

IP65/IP66


Temperature rating -20°C to +60°C

Electromechanical interlocking system

Mechanic and visual keying




**INTERLOCKING ELECTRICAL WIRING DIAGRAM:  
INCREASED POWER WITH PARALLEL CONNECTION.**



Pilot wiring is mandatory to break and mate on load

**ENERGY DISTRIBUTION SYSTEM WITH SEPARATE  
CONNECTION OF CONTACTS**

The pilot contact breaks the circuit in conformity with ATEX Directive (increased safety "e"). External control contactor not supplied by MARECHAL.



# 680 A

1 000 V  
U MAX / I

## SINGLE POLE POWER CONNECTOR SPeX



MARECHAL ELECTRIC FRANCE

Ex e IIC Gb  
Ex tb IIIC Db  
IECEx LCI 12.0005X  
LCIE 07 ATEX 6073 X



IP65  
IP66



SEE  
TABLE



GRP



IK08



-20 °C  
+60 °C



ATEX



1, 2,  
21, 22



**LEVER MECHANISM**  
**TO BE ORDERED SEPARATELY**  
Compatible with socket  
or inlet since 2018  
Lever mechanism :  
454A876  
Draw base : 454A396



### OTHER FEATURES

Rated current	According to temperature class and section of cable
Number of operations	2000
Pre-wired pilot circuit	6 A/250 V
Short-circuit current Icc	20 kA during 250 ms

### STANDARDS

International and European IEC/EN standards	60079-0, 60079-7 et 60079-31
Protection mode	e, tb



**SOCKET-OUTLET** female  
**SPeX WITHOUT LUG**



**INLET** male  
**SPeX WITHOUT LUG**

Type	Europe*	Reference	Reference 16-25 mm	Reference 22-32 mm	Reference 28-38 mm	Reference 40-48 mm
L1	Brown	4647001	464100132P	464100140P	464100150P	464100163P
L2	Black	4647002	464100232P	464100240P	464100250P	464100263P
L3	Grey	4647003	464100332P	464100340P	464100350P	464100363P
Neutral	Blue	464700N	464100N32P	464100N40P	464100N50P	464100N63P
Earth	Green	464700T	464100T32P	464100T40P	464100T50P	464100T63P
Positive	Red	464700P	464100P32P	464100P40P	464100P50P	464100P63P
Negative	Black	464700M	464100M32P	464100M40P	464100M50P	464100M63P

\* The indicated references are valid for Europe and Japan.

For mobile socket-outlets or wall-mounted inlet references, contact us.



COLOR coding			SOCKET-OUTLET female SPeX WITHOUT LUG		INLET male SPeX WITHOUT LUG		
Type	Australia and New Zealand	Reference	Reference 16-25 mm	Reference 22-32 mm	Reference 28-38 mm	Reference 40-48 mm	
L1	Red	4347001	434100132P	434100140P	434100150P	434100163P	
L2	White	4347002	434100232P	434100240P	434100250P	434100263P	
L3	Blue	4347003	434100332P	434100340P	434100350P	434100363P	
Neutral	Black	434700N	434100N32P	434100N40P	434100N50P	434100N63P	
Earth	Green	434700T	434100T32P	434100T40P	434100T50P	434100T63P	
Positive	Red	434700P	434100P32P	434100P40P	434100P50P	434100P63P	
Negative	Black	434700M	434100M32P	434100M40P	434100M50P	434100M63P	

For the UK, South Africa and India, replace the first two digits by 44.

Type	USA	Reference	Reference 16-25 mm	Reference 22-32 mm	Reference 28-38 mm	Reference 40-48 mm
L1	Black	4247001*	424100132P	424100140P	424100150P	424100163P
L2	Red	4247002*	424100232P	424100240P	424100250P	424100263P
L3	Blue	4247003*	424100332P	424100340P	424100350P	424100363P
Neutral	White	424700N*	424100N32P	424100N40P	424100N50P	424100N63P
Earth	Green	424700T*	424100T32P	424100T40P	424100T50P	424100T63P
Positive	Red	424700P*	424100P32P	424100P40P	424100P50P	424100P63P
Negative	Black	424700M*	424100M32P	424100M40P	424100M50P	424100M63P

\* cCSAus certified products.

For mobile socket-outlets or wall-mounted inlet references, contact us.

## COPPER LUGS

**Lug choice depends on the cable:** the cross-section of the flexible cable mentioned in the table below is for information only. Please check dimensions as these may vary according to cable types and manufacturers.





Wiring (mm <sup>2</sup> )	Strait with hole	Straight threaded M12	Internal diameter (mm)	External diameter (mm)*
Flexible	Stranded	Reference	Reference	
50	70	454A50C	454A50D	11
70	95	454A70C	454A70D	13.1
95	120	454A95C	454A95D	14.5
120	150	454A12C	454A12D	16.2
150	185	454A15C	454A15D	18
185	240	454A18C	454A18D	20.6
240	300	454A24C	454A24D	23.1
300	400	454A30C	454A30D	26.1
400	500	454A40C	454A40D	29.2
500	630	454A500C	454A500D	33.2
630	/	/	454A63D	37.6
				52

For male contact, wiring with crimping lugs, according to NF C20-130 standard (for VDE 0220 standard, please contact us). Crimping: Double hexagonal crimping is recommended.

\*Choose the crimping tool according to the external diameter of your lug.

# DRAWINGS AND DIMENSIONS

PLUG ON 30° ANGLED SOCKET OUTLET



	A	B	C	D	E1	E2
SP M50	254	306	105	128	89	112



## MAIN FEATURES



**12 CONTACTS**

**10 A**

**PXN12C**



**25 CONTACTS**

**10 A**

**DXN25C**



**37 CONTACTS**

**10 A**

**DXN37C**



◀◀ Ex II 2 G D Ex e IIC Gb, Ex tb IIIC Db ▶▶

◀◀ II 2 G D Ex ia ou ib IIC Gb ▶▶

◀◀ padlocking when connected or disconnected ▶▶

◀◀ Corrosion protected metal casing ▶▶

### MULTICONTACTS **PXN12C, DXN25C AND DXN37C** CONNECTORS COMPLY WITH:

- ATEX European Directive (affixing "Ex" symbol and CE marking),
- RoHS Directive (affixing CE marking),
- REACH European Regulation,
- IEC/EN 60079-0, IEC/EN 60079-7 and IEC/EN 60079-31 standards.

### **PXN12C, DXN25C AND DXN37C** CERTIFICATION BODIES

Products are certified by LCIE (ATEX and IECEx), NANIO (TR CU EAC), EXPLOLABS (SANS) and KGS (KCS\*) (French, Russian, South African and South Korean notified bodies).

\*DXN37C excluded



**12 ➞ 37 CONTACTS**



## SIMPLE ASSEMBLY AND DISASSEMBLY

### FAST WIRING

- Cable conductors: 1 mm<sup>2</sup> to 2,5 mm<sup>2</sup>.
- Before wiring, add a heat-shrink sleeve or insulating sleeve on each conductor..
- After wiring, cover the visible portion of the contact with the sleeve.
- Crimp the contact with a KNIPEX crimping tool P/N° 61CA500 or a GREENLEE crimping tool P/N° 45505.
- Use the 4 mm<sup>2</sup> footprint whatever the conductor cross-section.
- Perform a double crimping in compliance with CEI 60352-2 standard.
- Conductors can equally be soldered.

### ASSEMBLY

To insert contacts when they have been wired is simple.  
Push wired contact into rear of insulator until it stops to complete the installation.



### DISASSEMBLY

To remove, use the tool provided.  
Push tool from front onto contact until tool stops.  
Contact is then released at rear of insulator.



# 12 CONTACTS

10 A

220 V  
U MAX /

## CONNECTORS MULTICONTACTS PXN12C

MARECHAL ELECTRIC FRANCE

Ex II 2 G D Ex e IIC T5 Gb

EX TB IIIC T69°C DB

-40 °C ≤ Ta ≤ +55 °C

IECEx LCIE 14.0041X / LCIE 07 ATEX 6070X

MARECHAL ELECTRIC FRANCE

Ex II 2 G D Ex ia ou ib IIC T6 Gb

EX TB IIIC T69°C DB

-40 °C ≤ Ta ≤ +55 °C

IECEx LCIE 14.0041X / LCIE 07 ATEX 6070X



IP65  
IP66



1-2,5 mm<sup>2</sup>



METAL



IK09



-40 °C  
+55 °C



ATEX



1, 2,  
21, 22



### OTHER FEATURES

Rated current (with wiring according to standard)

4-20 mA/10A

Terminals wiring

crimping

Flexible wiring (min.-max.).

1-2,5 mm<sup>2</sup>

### STANDARDS

International and European IEC/EN standards

60079-0, 60079-7 et 60079-31

Protection mode

e, tb

ia or ib, tb (consult us)

# REFERENCES AND OPTIONS

**WALL MOUNTING**  
socket female  
**PXN12c**



**PLUG male**  
**PXN12c**



Input	Cable outer Ø	Reference	Input	Cable outer Ø	Reference
M25	9-16 mm	06A000125M	M25	9-16 mm	06A100125M
M32	12-21 mm	06A0001	M32	12-21 mm	06A1001



Connection or  
disconnection screw  
locking imprint  
BTR 2.5.

**INCLINED SOCKET  
FEMALE**  
**PXN12c**



**INCLINED  
APPLIANCE inlet male**  
**PXN12c**



Reference
06A7001

Reference
06A9001

Each product is supplied with 1 bag of 13 contacts depending on the maximum configuration. This allows you to set up the product to suit your needs.

**COUPLER  
SOCKET** female  
**PXN12c**



**INCLINED  
APPLIANCE inlet**  
**PXN12c**



Input	Cable outer Ø	Reference	Input	Cable outer Ø	Reference
M25	9-16 mm	06A300125M	M25	9-16 mm	06A600125M
M32	12-21 mm	06A3001	M32	12-21 mm	06A6001

## INFOS +


Leaving 2 contacts unused can give 9 different keying positions (on socket outlet side or mobile plug side) using the two specific stopping plugs supplied.

OPTIONS	Reference
<b>BAG OF 13 FEMALES CONTACTS</b>	
	01AA213
<b>BAG OF 13 MALES CONTACTS</b>	
	01AA113
<b>REMOVAL KEY</b>	
	61CA593

OPTIONS	Reference
<b>CRIMPING TOOL</b>	
	61CA500
<b>HELVIA SLEEVE EXPANSION TOOL</b>	
	61CA400
<b>BAG OF 13 HEAT SHRINK INSULATION SLEEVES</b>	
	61CA083
<b>INLET CAP</b>	
	01NA426


# DRAWINGS AND DIMENSIONS

**PLUG ON 45° WALL MOUNTED SOCKET OUTLET**




A	B	C	D	E1	E2
213	193	110	114	94	70

**PLUG ON 45° INCLINED SOCKET OUTLET**



A	B	C	D	E1	E2
153	189	77	107	63	95

**COUPLER**

A	B	C
246	136	58



# 25 CONTACTS

10 A

440 V  
U MAX

## CONNECTORS MULTICONTACTS DXN25C

MARECHAL ELECTRIC FRANCE

Ex II 2 G D Ex e IIC T\* Gb

EX TB IIIC T\*\* DB

-40 °C ≤ Ta ≤ +40 °C : T6 T51°C

-40 °C ≤ Ta ≤ +60 °C : T5 T71°C

IECEx LCIE 14.0040X / LCIE 09 ATEX 3050X

MARECHAL ELECTRIC FRANCE

Ex II 2 G D Ex ia ou ib IIC T6 Gb

EX TB IIIC T\*\* DB

-40 °C ≤ Ta ≤ +40 °C : T51°C

-40 °C ≤ Ta ≤ +60 °C : T71°C

IECEx LCIE 14.0040X / LCIE 09 ATEX 3050X



IP66  
IP67



1-2,5 mm<sup>2</sup>



METAL



IK09



-40°C  
+60°C



ATEX



1, 2,  
21, 22



### OTHER FEATURES

Rated current (with wiring according to standard)

4-20 mA/10A

Terminals wiring

Crimping

Flexible wiring (min.-max.).

1-2,5 mm<sup>2</sup>

### STANDARDS

International and European IEC/EN standards

60079-0, 60079-7 et 60079-31

Protection mode

e, tb

ia or ib, tb (consult us)

# REFERENCES AND OPTIONS

**WALL MOUNTING**  
 socket female  
**DXN25c**

**PLUG male**  
**DXN25c**


Input	Cable outer Ø	Reference
M32	12-21 mm	36D000232M
M40	16-27 mm	36D0002

Input	Cable outer Ø	Reference
M32	12-21 mm	36D100232M
M40	16-27 mm	36D1002



Locking position connected or disconnected by lockable shaft.

**INCLINED SOCKET FEMALE**  
**DXN25c**

**INCLINED APPLIANCE inlet male**  
**DXN25c**

**COUPLER SOCKET**  
 female  
**DXN25c**

**INCLINED APPLIANCE inlet**  
**DXN25c**


Input	Cable outer Ø	Reference
M32	12-21 mm	36D300232M
M40	16-27 mm	36D3002

Input	Cable outer Ø	Reference
M32	12-21 mm	36D600232M
M40	16-27 mm	36D6002

Other accessories on request.

Each product is supplied with 2 bags of 13 contacts depending on the maximum configuration. This allows you to set up the product to suit your needs. Delivered with padlocking shaft.

**INFOS +**


Leaving 2 contacts unused can give 9 different keying positions (on socket outlet side or mobile plug side) using the two specific stopping plugs supplied.

OPTIONS	Reference
<b>BAG OF 13 FEMALES CONTACTS</b>	
	01AA213
<b>BAG OF 13 MALES CONTACTS</b>	
	61CA113
<b>REMOVAL KEY</b>	
	61CA593

OPTIONS	Reference
<b>CRIMPING TOOL</b>	
	61CA500
<b>HELVIA SLEEVE EXPANSION TOOL</b>	
	61CA400
<b>BAG OF 13 HEAT SHRINK INSULATION SLEEVES</b>	
	61CA083
<b>INLET CAP IP66/IP67</b>	
	313A426


# DRAWINGS AND DIMENSIONS

**PLUG ON 30° WALL MOUNTED SOCKET OUTLET**




A	B	C	D	E1	E2
299	200	110	114	94	70

**PLUG ON 30° INCLINED SOCKET-OUTLET**



A	B	C	D	E1	E2
239	197	77	107	63	95

**COUPLER**

A	B	C
346	108	80



# 37 CONTACTS

10 A

230 V  
U MAX

## CONNECTORS MULTICONTACTS DXN37C

MARECHAL ELECTRIC FRANCE

Ex II 2 G D Ex e IIC T\* Gb

EX TB IIIC T\*\* DB

-40 °C ≤ Ta ≤ +40 °C : T6 T56°C

-40 °C ≤ Ta ≤ +55 °C : T5 T76°C

IECEx LCIE 14.0038X / LCIE 07 ATEX 6071X

MARECHAL ELECTRIC FRANCE

Ex II 2 G D Ex ia ou ib IIC T6 Gb

EX TB IIIC T\*\* DB

-40 °C ≤ Ta ≤ +40 °C : T56°C

-40 °C ≤ Ta ≤ +55 °C : T76°C

IECEx LCIE 14.0038X / LCIE 07 ATEX 6071X



IP66  
IP67



1-2,5 mm<sup>2</sup>



METAL



IK09



-40°C  
+55°C



ATEX



1, 2,  
21, 22



### OTHER FEATURES

Rated current (with wiring according to standard)

4-20 mA/10A

Terminals wiring :

crimping

Flexible wiring (min.-max.).

1-2,5 mm<sup>2</sup>

### STANDARDS

International and European  
IEC/EN standards

60079-0, 60079-7 et 60079-31

Protection mode

e, tb

ia or ib, tb (consult us)

# REFERENCES AND OPTIONS

**WALL MOUNTING**  
socket female  
**DXN37C**



**PLUG male**  
**DXN37C**



Input	Cable outer Ø	Reference	Input	Cable outer Ø	Reference
M32	12-21 mm	36C000332M	M32	12-21 mm	36C100332M
M40	16-27 mm	36C0003	M40	16-27 mm	36C1003



Locking position  
connected or  
disconnected by  
lockable shaft.

**INCLINED SOCKET  
FEMALE**  
**DXN37C**



**INCLINED  
APPLIANCE inlet male**  
**DXN37C**



**COUPLER SOCKET**  
female  
**DXN37C**



**INCLINED  
APPLIANCE inlet**  
**DXN37C**



Input	Cable outer Ø	Reference	Input	Cable outer Ø	Reference
M32	12-21 mm	36C300332M	M32	12-21 mm	36C600332M
M40	16-27 mm	36C3003	M40	16-27 mm	36C6003

Other accessories  
on request.

Each product is  
supplied with 3 bags of  
13 contacts depending  
on the maximum  
configuration.  
This allows you to set  
up the product to suit  
your needs.  
Delivered with  
padlocking shaft.

## INFOS +

Leaving 2 contacts unused can give 9 different keying positions (on socket outlet side or mobile plug side) using the two specific stopping plugs supplied.

### OPTIONS

#### Reference

##### BAG OF 13 FEMALES CONTACTS



01AA213

##### BAG OF 13 MALES CONTACTS



61CA113

##### REMOVAL KEY



61CA593

### OPTIONS

#### Reference

##### CRIMPING TOOL



61CA500

##### HELVIA SLEEVE EXPANSION TOOL



61CA400

##### BAG OF 13 HEAT SHRINK INSULATION SLEEVES

61CA083


##### INLET CAP IP66/IP67



313A426


# DRAWINGS AND DIMENSIONS

**PLUG ON 30° WALL MOUNTED SOCKET OUTLET**




A	B	C	D	E1	E2
299	200	110	114	94	70

**PLUG ON 30° INCLINED SOCKET-OUTLET**



A	B	C	D	E1	E2
239	197	77	107	63	95

**COUPLER**

A	B	C
346	108	80



# BOXES



## EMPTY ENCLOSURES

### **B2X/CDX** INCREASED SAFETY ENCLOSURES



## DISTRIBUTION AND JUNCTION

### **B2X** SOCKET OR JUNCTION BOXES



### **MXBJ** JUNCTION BOXES



### **MXBS** SOCKET-OUTLET COMBINATION BOXES



292

P. 294

P. 298

P. 300

- Ex II 2 G D Ex eb IIC, Ex tb IIIC Db
- GRP casing
- 120x120 mm or 160x160 mm or 342x225x156 mm
- On hinges

- Ex II 2 G D Ex e IIC, Ex tb IIIC
- Intrinsic safety capability
- GRP casing
- For Ex socket and/or EX terminals
- 120x120 mm ou 160x160 mm
- On hinges

- Ex II 2 G D Ex eb IIC, Ex tb IIIC
- Intrinsic safety capability
- GRP casing, aluminium, stainless steel AISI 316L
- Custom configuration

- Ex II 2 G D Ex eb IIC, Ex tb IIIC
- Intrinsic safety capability
- Assembly of multi-contact connectors and socket-outlets on the same enclosure
- GRP casing, aluminium, stainless steel AISI 316L
- Custom configuration

## **CONTROL AND SIGNALLING**

### **CONTROL STATIONS**



Increased safety



Flameproof

P. 302

-  II 2 G D Ex eb IIC, Ex tb IIIC
- or  II 2 G D Ex db IIC, Ex tb IIIC
- Intrinsic safety option
- A wide range of boxes equipped with certified accessories (push buttons, light indicators etc...)
- GRP casing, aluminium, stainless steel AISI 316L
- Custom configuration

## **ENCLOSURES**

### **FLAMEPROOF GAS GROUP IIB + H<sub>2</sub> OU IIC**



IIB + H<sub>2</sub>




IIC

P. 304

-  II 2 G D Ex db IIB ou IIB+H<sub>2</sub> ou IIC
- or  II 2 G D Ex d IIC, Ex tb IIIC
- A wide range of metal boxes (cast aluminium or stainless steel) equipped with certified accessories (push buttons, rotating buttons, light indicators, potentiometers...)
- Custom configuration

# INCREASED SAFETY ENCLOSURES B2X/CDX



IP66  
IP67



GRP



IK09



B2X  
-50 °C  
+85 °C



CDX  
-25 °C  
+90 °C



ATEX



1, 2,  
21, 22

## OTHER FEATURES

CDX modularity

Flat or angled covers

## STANDARDS

International and European IEC/EN standards

62262, 60079-0, 60079-7 and 60079-31

## MARKING AND CERTIFICATION


ATEX markings

Ex II 2 G Ex eb IIC Gb  
Ex II 2 D Ex tb IIIC Db


Certificates

IECEx and ATEX component certificates pending

# DRAWINGS AND DIMENSIONS



	A	B	C	E1	E2
<b>120x120</b>	91	141	126	117	106
<b>160x160</b>	91	178	166	157	146



	A	B	C	D	E1	E2	E3
<b>CDX</b>	156	305	225	342	185	320	120

# SOCKET OR JUNCTION BOXES B2X



IP66  
IP67



0,22 –  
35 mm<sup>2</sup>



GRP



IK09



-50 °C  
+60 °C



ATEX



1, 2,  
21, 22



Existing terminal  
configurations for 25 A,  
32 A, 45 A and 63 A.

## OTHER FEATURES

Dimensions	120x120x90 and 160x160x90
Fitting	Certified Ex e terminals
Cable entries	M12 to M40
Flexible and stranded wiring (min.-max.)	0,22 – 35 mm <sup>2</sup>

## STANDARDS

International and European IEC/EN standards	62262, 60079-0, 60079-7, 60079-11 et 60079-31
---	---

## ASSOCIATED MARECHAL® PRODUCTS

DECONTACTOR™	DXA1, DXN1, DXN3 and DXN6
Connectors	PNCX
Multicontact connectors	PXN12C

## MARKING AND CERTIFICATION

ATEX markings	or Ex ia ou ib IIC T2Gb or Ex ia ou ib IIC T2Gb 
Certificates	[2] depending on configurations and ambient T° T6/T5/T4 for the gas. Certificates IECEx N° IECEx LCIE 16.0042X ATEX N° LCIE 16 ATEX 3054X

## CONFIGURATIONS

- For standard configurations of socket boxes with terminals, see the DXN1, DXN3 and DXN6 pages.
- For special configurations, contact us.



### ACCESSORIES ON REQUEST

- Earth stud
- Earth bar
- Junction bar
- Draining and breathing device
- Earth continuity plate
- Metal cable gland with or without earth continuity

# CONFIGURATION TYPES

## POLYAMIDE CABLE GLAND



Junction box in GRP, with polyamide cable glands, blanking-plug, terminals as described.

SIZE	CONFIG.	CABLE GLAND	STOPPING PLUG (as free part)	TERMINAL	MAX CURRENT <sup>(1)</sup>	ARTICLE NUMBER
120x120x90 mm		2 x M20 (10-14 mm)	/	5 x 4 mm <sup>2</sup> + 2 E	25 A	24A1C0000J169
		3 x M20 (10-14 mm)	1 x M20	5 x 4 mm <sup>2</sup> + 2 E	25 A	24A1C0000J170
		4 x M20 (10-14 mm)	2 x M20	7 x 4 mm <sup>2</sup> + 2 E	25 A	24A1C0000J171
		2 x M25 (12-18 mm)	/	5 x 6 mm <sup>2</sup> + 2 E	32 A	24A1D0000J172
		3 x M25 (12-18 mm)	1 x M25	5 x 6 mm <sup>2</sup> + 2 E	32 A	24A1D0000J173
		4 x M25 (12-18 mm)	2 x M25	7 x 6 mm <sup>2</sup> + 2 E	32 A	24A1D0000J174
160x160x90 mm		2 x M32 (16-25 mm)	/	5 x 10 mm <sup>2</sup> + 2 E	45 A	24C1E0000J175
		3 x M32 (16-25 mm)	1 x M32	5 x 10 mm <sup>2</sup> + 2 E	45 A	24C1E0000J176
		4 x M32 (16-25 mm)	2 x M32	7 x 10 mm <sup>2</sup> + 2 E	45 A	24C1E0000J177
		2 x M40 (22-32 mm)	/	5 x 16 mm <sup>2</sup> + 2 E	63 A	24C1F0000J178
		3 x M40 (22-32 mm)	1 x M40	5 x 16 mm <sup>2</sup> + 2 E	63 A	24C1F0000J179
		4 x M40 (22-32 mm)	2 x M40	7 x 16 mm <sup>2</sup> + 2 E	63 A	24C1F0000J180
		6 x M20 (10-14 mm)	3 x M20	12 x 4 mm <sup>2</sup> + 4 E	25 A	24C1C0000J195
		8 x M20 (10-14 mm)	4 x M20	14 x 4 mm <sup>2</sup> + 4 E	25 A	24C1C0000J196
		6 x M25 (12-18 mm)	3 x M25	12 x 6 mm <sup>2</sup> + 4 E	32 A	24C1D0000J197
		8 x M25 (12-18 mm)	4 x M25	12 x 6 mm <sup>2</sup> + 4 E	32 A	24C1D0000J198
		6 x M32 (16-25 mm)	3 x M32	10 x 10 mm <sup>2</sup> + 3 E	45 A	24C1E0000J199
		8 x M32 (16-25 mm)	4 x M32	10 x 10 mm <sup>2</sup> + 3 E	45 A	24C1E0000J200

[1] Maximum current, at +60°C, for the maximum cable cross-section per terminal of the configuration concerned.  
Details and drawings available on request.



According to configurations and the temperature class requested, the maximum current can be modified.  
Contact us for other configurations and boxes.

# CONFIGURATION TYPES

## POLYAMIDE CABLE GLAND



Junction box in GRP, with cable glands, blanking-plug, terminals as described.

SIZE	CONFIG.	CABLE GLAND	STOPPING PLUG (as free part)	TERMINAL	MAX CURRENT <sup>(1)</sup>	ARTICLE NUMBER
120x120x90 mm		2 x M20 (6-12/8-17 mm)	/	5 x 4 mm <sup>2</sup> + 2 E	25 A	24A1C0000J201
		3 x M20 (6-12/8-17 mm)	1 x M20	5 X 4 mm <sup>2</sup> + 2 E	25 A	24A1C0000J202
		4 x M20 (6-12/8-17 mm)	2 x M20	7 X 4 mm <sup>2</sup> + 2 E	25 A	24A1C0000J203
		2 x M25 (6-17/14-23 mm)	/	5 X 6 mm <sup>2</sup> + 2 E	32 A	24A1D0000J204
		3 x M25 (6-17/14-23 mm)	1 x M25	5 X 6 mm <sup>2</sup> + 2 E	32 A	24A1D0000J205
		4 x M25 (6-17/14-23 mm)	2 x M25	7 X 6 mm <sup>2</sup> + 2 E	32 A	24A1D0000J206
160x160x90 mm		2 x M32 (14-23/20-29 mm)	/	5 X 10 mm <sup>2</sup> + 2 E	45 A	24C1E0000J207
		3 x M32 (14-23/20-29 mm)	1 x M32	5 X 10 mm <sup>2</sup> + 2 E	45 A	24C1E0000J208
		4 x M32 (14-23/20-29 mm)	2 x M32	7 X 10 mm <sup>2</sup> + 2 E	45 A	24C1E0000J209
		2 x M40 (23-36/29-42 mm)	/	5 X 16 mm <sup>2</sup> + 2 E	63 A	24C1F0000J210
		3 x M40 (23-36/29-42 mm)	1 x M40	5 X 16 mm <sup>2</sup> + 2 E	63 A	24C1F0000J211
		4 x M40 (23-36/29-42 mm)	2 x M40	7 X 16 mm <sup>2</sup> + 2 E	63 A	24C1F0000J212
		6 x M20 (6-12/8-17 mm)	3 x M20	12 X 4 mm <sup>2</sup> + 4 E	25 A	24C1C0000J213
		8 x M20 (6-12/8-17 mm)	4 x M20	14 X 4 mm <sup>2</sup> + 4 E	25 A	24C1C0000J214
		6 x M25 (6-17/14-23 mm)	3 x M25	12 X 6 mm <sup>2</sup> + 4 E	32 A	24C1D0000J215
		8 x M25 (6-17/14-23 mm)	4 x M25	12 X 6 mm <sup>2</sup> + 4 E	32 A	24C1D0000J216
		6 x M32 (14-23/20-29 mm)	3 x M32	10 X 10 mm <sup>2</sup> + 3 E	45 A	24C1E0000J217
		8 x M32 (14-23/20-29 mm)	4 x M32	10 X 10 mm <sup>2</sup> + 3 E	45 A	24C1E0000J218

(1) Maximum current, at +60°C, for the maximum cable cross-section per terminal of the configuration concerned.  
Details and drawings available on request.



According to configurations and the temperature class requested, the maximum current can be modified.  
Contact us for other configurations and boxes.

# JUNCTION BOXES

## MXBJ



IP66

0,2 -  
300 mm<sup>2</sup>GRP  
METAL

IK09

-25 °C<sup>(1)</sup>  
+60 °C

ATEX

1, 2,  
21, 22

### OTHER FEATURES

Material

GRP casing, aluminium, stainless steel AISI 316L.

Cable entries

M12 to M80.

Flexible and stranded wiring (min.-max.)

0,2 - 300 mm<sup>2</sup>

Existing terminal  
configurations up to 400 A.

### STANDARDS

International and European IEC/EN standards

62262, 60079-0, 60079-7, 60079-11 et 60079-31.

### MARKING AND CERTIFICATION

ATEX markings

 Ex II 2 G Ex eb IIC T<sup>[2]</sup> Gb increased safety Ex II 2 G Ex ia IIC T<sup>[2]</sup> Gb or Ex II 2 G Ex ib IIC T<sup>[2]</sup> Gb intrinsic safety Ex II 2 G Ex eb ib or ia IIC T<sup>[2]</sup> Gb increased safety and intrinsic safety Ex II 2 D Ex tb IIIC T<sup>[2]</sup> Db in dust.<sup>[2]</sup> Depending on ambient temperature and terminals used.

Certificates

Certificates IECEx N° IECEEx LCI 11.0026X  
et ATEX N° LCIE 11 ATEX 3028X.

**i****ACCESSORIES ON REQUEST**

- Earth stud
- Earth bar
- Shield bar
- Junction bar
- Hinges
- Mounting
- Purge or breather
- Earthing plate
- Metal gland with or without earth ring

# SOCKET-OUTLET COMBINATION BOXES MXBS



IP66

0,22 -  
400 mm<sup>2</sup>GRP  
METAL

IK09

-25 °C<sup>(1)</sup>  
+60 °C

ATEX

1, 2,  
21, 22

Existing terminal config-  
urations up to 680 A.

## OTHER FEATURES

Material

Casing in GRP, aluminium alloy or stainless steel.  
Screws in stainless steel.

Junction

Terminal blocks. Feed through and loop-in loop-out connection.

Cable entries

M12 to M80 depending on the size of the box/Polyamide cable gland for  
unarmoured cable.

Flexible and stranded wiring

Nickel plated brass cable gland for unarmoured cable and armoured cable  
(with plate or washer bonding inside the box).

(min.-max.)

## STANDARDS

International and European IEC/EN standards

62262, 60079-0, 60079-7, 60079-11 et 60079-31.

## MARKING AND CERTIFICATION

ATEX markings

Ex II 2 G Ex eb IIC T<sup>[2]</sup> Gb increased safety Ex II 2 G Ex ia IIC T<sup>[2]</sup> Gb  
Ex II 2 G Ex ib IIC T<sup>[2]</sup> Gb intrinsic safety  
Ex II 2 G Ex eb ia or eb ib IIC T<sup>[2]</sup> Gb  
increased safety and intrinsic safety  
Ex II 2 D Ex tb IIIC T<sup>[2]</sup> Db in dust.

<sup>[2]</sup> Depending on ambient temperature and connectivity used..

Certificates

Certificates IECEEx N° IECEEx LCI 11.0042X  
ATEX n° LCIE 11 ATEX 3047X.

**ASSOCIATED MARECHAL® PRODUCTS**

DECONTACTOR™

DXA1, DXN1, DXN3 and DXN6

Connectors

PNCX and SPeX

Multicontact connectors

PXN12C, DXN25C and DXN37C

**ACCESSORIES ON REQUEST**


- Inclined sleeve
- Earth stud
- Earth bar
- Hinges
- Mounting brackets
- Purge or breather
- Earthing plate
- Metal gland with or without earth ring



# CONTROL STATIONS AND BOXES



INCREASED SAFETY AND  
FLAMEPROOF



Ex db, Ex eb, Ex db eb, Ex db eb ia/ib mb




A wide range of control stations in GRP, aluminium (copper-free) or stainless steel designed for more flexibility, less weight and adapted to customer specifications. To be assembled with Ex db eb switches in EF version or PL switches for CP version.



## INCREASED SAFETY


## FLAMPROOF

### EFXE..



- AISI-316L stainless steel.
- Acid treatment.
- Hidden hinges.
- Customised dimensions up to 910x1140x500 mm.
- From -50 °C to +60 °C.
- Designed to meet the requirements for use ON and OFF-SHORE, in petrochemical and marine applications.

### CP../EFDCN..




- Copper-free aluminum.
- From -50 °C to +60 °C (ATEX),  
From -60 °C to +60 °C (IECEx).

### EFXE..




- Copper-free aluminum.
- From -50 °C to +60 °C.
- A wide range of dimensions.

### CP../EFSRC..



- Copper-free aluminum.
- Selector switches can be customised on request.
- From -50 °C to +60 °C (ATEX),  
From -60 °C to +60 °C (IECEx).

### EFE..



- GRP material.
- Designed to meet the requirements for use ON and OFF-SHORE, in petrochemical and marine applications.
- From -50 °C to +60 °C
- A wide range of dimensions.

### EPKZM



- Copper-free aluminum.
- used to house motor protector circuit breakers up to 63 A.
- From -30 °C to +55 °C.
- ATEX certification only.




# BOXES AND ENCLOSURES

GAS GROUP  
IIB + H<sub>2</sub> AND IIC

Ex db IIB, IIB+H<sub>2</sub> et IIC



- High resistance to corrosion
- High mechanical resistance
- Highest standards of safety
- An ideal solution for extreme environmental conditions



## GAS GROUP IIB + H2



### EJB..

II 2G Ex db IIB Gb or Ex db IIB+H<sub>2</sub> Gb  
II 2D Ex tb IIC Db IP65 or 66




- Copper-free aluminum.
- Adapted for indoor and outdoor applications.
- AISI316 stainless steel screws.
- From -60°C to +60°C
- IP65, IP66.



### EJB..

II 2G Ex db IIB Gb or Ex db IIB+H<sub>2</sub> Gb  
II 2D Ex tb IIC Db IP65 or 66



- AISI 316L stainless steel or galvanised steel.
- Adapted for indoor and outdoor applications.
- AISI 316L stainless steel screws and accessories.
- From -60°C to +60°C
- IP65, IP66.
- Customised dimensions.

## GAS GROUP IIC



### GUB..

II 2G Ex d IIC Gb  
II 2D Ex tb IIC Db IP66



- Copper-free aluminum.
- Adapted for indoor and outdoor applications.
- From -50 °C to +55 °C (ATEX), from -60 °C to +60 °C (IECEx).
- AISI 316L version: customised dimensions on request.



### GUB/EMH..

II 2G Ex d IIC Gb  
II 2D Ex tb IIC Db IP66



- Copper-free aluminum.
- Adapted for indoor and outdoor applications.
- From -50 °C to +55 °C (ATEX), from -60 °C to +60 °C (IECEx).
- Window diameter from 155 to 230 mm..
- AISI 316L version: customised dimensions on request.



### GUB../QL

II 2G Ex d IIC Gb  
II 2D Ex tb IIC Db IP66



- Copper-free aluminum.
- Adapted for indoor and outdoor applications.
- Can be fitted with push buttons, rotary selectors.
- From -50 °C to +55 °C (ATEX), from -60 °C to +60 °C (IECEx).
- AISI 316L version: customised dimensions on request.



### CPS../EMH

II 2G Ex db IIC Gb  
II 2D Ex tb IIC Db IP66



- Copper-free aluminum.
- Adapted for indoor and outdoor applications.
- From -50 °C to +60 °C (ATEX), from -60 °C to +60 °C (IECEx).

# LIGHTING



## LINEAR LED LIGHTING

**EVF-P..**

**LED/FLUORESCENT**

II 2G Ex mb db eb IIC T4 Gb  
(normal & emergency)  
II 2D Ex tb IIIC T130°C Db



**Luminosity:** up to 13 000 lm  
**Luminous efficiency:** 172 lm/W  
**LED colour:** 4.400 K  

- Ambient temp. range: -20°C/+55°C (emergency: -20°C/+40°C).
- Transparent PC UV protected casing with copper-free aluminum flanges.



## FLOODLIGHT AND WELLGLASS LED/HALOGEN/H.I.D.

**FL..**

**LED**

II 2 G Ex db IIB+H<sub>2</sub> T6/T5/T4 Gb  
II 2 D Ex tb IIIC T85°C/T100°C/T135°C Db IP66



**Luminosity:** up to 12.000lm  
**Luminous efficiency:** 125 lm/W  
**LED colour:** 5.000 K

- Ambient temp. range: -50°C/+55°C.
- Copper-free aluminium body.
- Stainless steel mounting brackets.
- Available with battery pack for 180 min.

**EVF-L..**

**LED/FLUORESCENT**

II 2G Ex mb db eb IIC T4 Gb  
(normal & emergency)  
II 2D Ex tb IIIC T130°C Db



**Luminosity:** up to 13 000 lm  
**Luminous efficiency:** 170 lm/W  
**LED colour:** 4.400 K  

- Ambient temp. range: -20°C/+60°C.
- Transparent PC UV protected casing with GRP flanges.



**FL..**

**H.I.D.**

II 2 G Ex db eb IIB+H<sub>2</sub> T4/T3/T2 Gb  
II 2 D Ex tb IIIC T135°C to T235°C Db IP66



**Power:** up to 400 W

- Ambient temp. range: -50°C/+55°C;
- Copper-free aluminium or AISI316L stainless steel body;
- AISI304 stainless steel mounting brackets.
- Suitable for H.I.D. lamp (metal halide or high pressure sodium).

**G2X**

**LED/FLUORESCENT**

II 3 G Ex nA IIC T6 Gc;  
II 3 D Ex tc IIIC T85°C Dc IP66.



**Luminosity:** up to 5 200 lm  
**Luminous efficiency:** 118 lm/W  

- T°C amb. : -20°C/+40°C.
- GRP body.
- Available also for safe areas.



**EVDE-PR 3**

**LED/SPOTLIGHT**

II 2 G Ex db IIC T5/T4/T3 Gb;  
II 2 D Ex tb IIIC T100°C/T135°C/T200°C Db IP66.



**Luminosity :** up to 22 000 lm  
**Luminous efficiency:** up to 135 lm/W  
**LED colour:** 4000 K  

- T°C Amb.: -60°C/+60°C.
- LED floodlight.
- Copper-free aluminum body.

## SELECTION GUIDE

### VISUAL SIGNAL

**FL1** / LED

II 2G Ex db eb mb IIC T4 Gb  
II 2D Ex mb tb IIIC T90°C Db IP66.



Luminosity: up to 32.000 lm

Luminous efficiency: 125 lm/W

- Ambient temp. range: -30°C/+60°C
- Copper-free aluminium body
- Modular solution: up to 4 units

**TL2** / LED

II 2 D Ex tb IIIA T80°C Db;  
II 3 G Ex ec IIC T3 Gc;  
II 3 D Ex tc IIIB T80°C Dc.



Luminosity: up to 50.220 lm

Luminous efficiency: 164 lm/W

- Ambient temp. range: -40°C/+55°C
- Thermal protection against overtemperature
- Overvoltage protection system

**EVDE-5**

**LED MIOL - MEDIUM INTENSITY OBSTRUCTION LIGHT**



II 2 G Ex db IIC T5/T4/T3 Gb

II 2 D Ex tb IIIC T100°C/T135°C/T200°C Db IP66.



Luminosity:

Type A: up to 20.000 cd white flashing (day) + 2.000 cd white flashing (night)

Type B: up to 2.000 cd red flashing (night)

Type AB: up to 20.000 cd white flashing (day) + 2.000 cd red flashing (night)

Type AC: up to 20.000 cd white flashing (day) + 2.000 cd steady red (night)

- Designed for structures > 45 m

- Compliant with ICAO Annex 14

- Available in single or twin version

**EV../XN-MXN**

**LED/XENOFASLIGHT**



II 2 G Ex db IIC T5/T4 Gb;

II 2 G Ex db eb IIC T5/T4 Gb;

II 2 D Ex tb IIIC T100°C/T135°C Db IP66.



Luminosity: up to 8.500 cd

- Ambient temp. range: -60°C/+60°C;

- Copper-free aluminium body.

- Provided with Fresnel lens.

- Available in different luminous intensities: 2J, 6J, 15J.

- Provided with red lamp.

**EVCC-PR**

**LED/TRAFFIC LIGHT**



II 2 G Ex db IIC T3 Gb

II 2 D Ex tb IIIC T200°C Db IP66.

Luminosity: up to 1.500 cd

- Ambient temp. range: -20°C/60°C

- Copper-free aluminium body.

- Provided with red and green lamps.



## ACCESSORIES AND SPARE PARTS





## SOMMAIRE

MECHANICAL LOCKING .....	P. 310
ELECTRO-MECHANICAL LOCKING SYSTEM .....	P. 312
CABLE AMPLIFIER LUGS .....	P. 312
STOP-LATCH.....	P. 313
TYPOLOGY OF LIDS .....	P. 314
DRAW MECHANISM.....	P. 315
ELECTROMAGNETIC COMPATIBILITY (EMC) .....	P. 316
MAIN OPTION COMBINATION SUFFIXES .....	P. 317
CABLE GLANDS.....	P. 318
REVERSED INTERIOR AND CONTACTS .....	P. 320
PHASE-SEQUENCE INDICATOR .....	P. 320
VISUAL STATUS INDICATORS .....	P. 321
INDUSTRIAL/DOMESTIC ADAPTER .....	P. 321
PILOTS AND AUXILIARIES.....	P. 322
SPARE PARTS .....	P. 324



# MECHANICAL LOCKING

## IMMEDIATE VISIBILITY AND SAFETY FOR END-USERS : PADLOCKING

The use of MARECHAL® products can be part of your lockout tagout procedures. Padlocking, when used on your machines or electric motors, ensures protection of your staff with safe local breaking, without any need for an accredited electrical engineer

MARECHAL ELECTRIC offers you simple and fast padlocking for many of its socket-outlets for use in industrial environments or hazardous areas. Padlocking can be done with the socket-outlet either connected or disconnected. It prevents the user from powering some equipment or from inadvertent use during maintenance work.

### DECONTACTOR™



#### Plug alone

A padlock or lockout hasp can be fitted on the inlet body. Add suffix 843 to the inlet part number.



**Mating, unmating or closing of the lid is made impossible in order to guarantee the safety of the users.**

#### Socket-outlet alone with its lid shut or the full set connected

A padlock or lockout hasp can be fitted on the inlet body. Add suffix 843 to the socket-outlet part number.



### Suffix to be added to the socket-outlet or plug/inlet part number (P/N°) depending on the locking option:

OPTIONS	DSN SERIES	DS/DSP/DSF SERIES	DXN SERIES	PN SERIES	CS1000 SP
Locking shaft for up to 2 padlocks Ø 4 to 8 mm max.	Socket-outlet P/N° + 843	Socket-outlet P/N° + 843	Socket-outlet P/N° + 843	NA	NA
Locking shaft for up to 3 padlocks Ø 8 mm max.	NA	NA	NA	NA	NA
Padlocking latch (no shaft) one padlock Ø 4 mm max.	NA	NA	NA	Socket-outlet P/N° + 843	NA
Allen-screw locking latch*	NA	DS2 Socket-outlet P/N° + 22 (6 mm hexagonal key)	NA	Socket-outlet P/N° + 22 (2.5 mm hexagonal key)	NA
Locking plug/inlet (padlocking hole)	<<< Inlet P/N° + 843 >>>			NA	NA
Safety lock (up to 6 padlocks)	613A541	613A541 (poly shaft) 399A541 (metal shaft)	613A541	NA	NA
Padlocking ring	NA	NA	NA	NA	453A843 454A844

\* no possibility to use a padlock.

### Some of our ranges are equipped with a mechanical locking device as standard.

With a BTR screw:  
**PXN12C/DS4**



With lockable shaft:  
**DX/DXN25C and DXN37C**



Standard padlocking in the OFF position  
(Ø 4 to 8 mm).

### SEPARABLE SWITCH-DISCONNECTOR EVO





## SECURE YOUR ELECTRICAL WORKS WHILE YOUR DEVICES ARE OFF LOAD

With a  
**DECONTACTOR™**

OR

With an **EVO** separable  
switch-disconnector

Separating: local  
current interruption  
and on load break  
► Visible break



Separating: local  
current interruption  
and on load break  
► Visible break  
► Fully visible  
break



Padlocking: on the device itself

Identifying



NO RISK  
OF ERRORS



Safety for end users and  
machines

FAST AND EASY  
ASSEMBLY



Time  
saving

ONGOING AND  
WORK IN PROGRESS



Cost reduction

THE INSTALLATION IS SAFE

ALSO VALID FOR Ex VERSIONS.

The use of MARECHAL® DECONTACTOR™ and EVO products may be part of the lock out tag out procedures for safe working.



## ELECTRO-MECHANICAL LOCKING SYSTEM

**NEW**

Voltage presence LED light indicator

Rotary on/off button

Captive and discrete locking pin diam. 8mm included.



### PLUG ENGAGED SYSTEM FOR THE DS2 AND DS4 :

The latch of the socket is equipped with a plug presence detection system.

- When linked to an upstream control device the external power supply is only turned on once the plug is fully engaged
- The rotary button activates the locking system
- In the ON position the socket release latch is disabled and the plug cannot be removed
- In the case of LED or switch failure, connection of the plug is prevented for safety reasons

**Locking system is integrated in the module.**

- The system lock works either for the lid only or with the plug connected.
- When the system is locked, operation of the release latch is disabled:
  - the rotary on/off is also disabled
  - the release latch is disabled preventing the socket lid to be opened or the plug to be removed.
- When ordering this option, the product IP level will no more be guaranteed.

## CABLE LUG AMPLIFIERS



CONDUCTOR SECTION	DSN1	DS1 DSN3	DS2	DS2 350	DS4	DXN6	DX6	DX9	DX2
FLEXIBLE STRANDED									
4 mm <sup>2</sup>	6 mm <sup>2</sup>	611A277-06	-	-					
6 mm <sup>2</sup>	10 mm <sup>2</sup>	611A277-10	-	-					
<b>FLEXIBLE</b>	<b>16 mm<sup>2</sup></b>	<b>611A277-16</b>	<b>613A277-16</b>	-					
25 mm <sup>2</sup>	35 mm <sup>2</sup>	-	-	-	-	256A277-35	-	-	-
50 mm <sup>2</sup>	70 mm <sup>2</sup>	-	-	-	-	-	266A277-50	-	-
70 mm <sup>2</sup>	95 mm <sup>2</sup>	-	-	-	269A277-70	-	-	269A277-70	269A277-70
95 mm <sup>2</sup>	120 mm <sup>2</sup>	-	-	-	269A277-120	-	-	269A277-120	269A277-120
120 mm <sup>2</sup>	150 mm <sup>2</sup>	-	-	392A277150					
150 mm <sup>2</sup>	185 mm <sup>2</sup>	-	-	392A277185					
185 mm <sup>2</sup>	240 mm <sup>2</sup>	-	-	-	394A277-240				

Cable sections are given for information.

A full check must be undertaken due to the variation of diameter depending on manufacturers.



## STOP-LATCH

This option is ideal for quick disconnection of machinery and equipment by operators wearing gloves.

The latch is fitted with a red label with warning "stop" for ease of identification.



**The use of this latch is not recommended in case of in-line coupler extension cables.**

**Suffix to be added to the socket-outlet part number (P/N°):**

OPTION	DSN SERIES	DS SERIES*
Stop-latch	<<< Socket-outlet P/N° + 453 >>>	

\* The stop-latch is standard for the metal DS9, DS2 and DS4.



**The stop latch is not an emergency-stop button**





## TYPOLOGY OF LIDS

### LID OPENING

Different lid opening configurations are available depending on our ranges. See ranges pages for more details.



DS6 meal example



DSN6 GRP example

### AUTOMATIC SELF-RETURNING LID AND LID-SPRUNG-CLOSED

A normally closed lid configuration is available for applications where it is desirable to protect the front face of the socket outlet – the shutter – from ingress of dust and debris or potential damage. This option provides a lid that automatically returns to an almost closed position after withdrawal of the plug. The user must then always manually close the lid in order to achieve the complete seal (IP-rating), except for the DS1- and DS3- poly, which are available with an automatic sprung loaded lid, which completely closes.



DS1/DS3 example



PN example



This option is recommended for self-ejecting applications.

### Suffix to be added to the socket-outlet part number (P/N°):

OPTION	DSN SERIES	DS SERIES <sup>(1)</sup>	PN SERIES <sup>(2)</sup>	DXN SERIES
Socket-outlet with self-returning lid closed			<< Socket-outlet P/N° + R >>	

(1) For DS1- and DS3-, this is an automatic sprung-closed lid.

(2) The IP55 PN series version is available with a standard automatic sprung-closed lid [no need to add R] : replace N of the P/N° of the socket-outlet by a S.

### MOUNTING : LOAD BREAK RELEASE BUTTON SHOULD BE IN UPPER POSITION





# DRAW MECHANISM

## FINGER DRAW PLATES

Easy-mating accessories.

Part numbers (P/N°) for these products:

OPTION	DSN1	DSN3/DS1	DSN6/DS3	DS6	SP/SPeX
Plates	611A346	613A346	616A346	316A346	
Lever mechanism					454A876
Draw base					454A396

Finger draw-plates are available in pairs with 2 seals and longer fixing screws than standard.



Lever mechanism



Some of our products are supplied with a draw mechanism as standard.

Easy-mating mechanism is included both on socket-outlet and connector side for the below products:

**DS9 - 150A**



**DS2 - 250A**



**DS4 - 400A**





# ELECTROMAGNETIC COMPATIBILITY (EMC)

## PERFORMANCES IN ELECTROMAGNETIC ENVIRONMENTS

MARECHAL ELECTRIC has developed a simple and reliable solution with outstanding performances in electromagnetic environments. This solution is available for MARECHAL® industrial or hazardous area device ranges, for high currents up to 1 250 A or for signal and control up to 37 contacts. This solution is particularly adapted to electromagnetic environments involving variable frequency drives for electric motors.

Variable frequency drives include power electronic switches (diodes, thyristors, insulated gate bipolar transistors...) which enable to control the motor power supply frequency, thus its speed.

The switching of these switches generate harmful electromagnetic pollution consisting of:

- current and voltage harmonics, and
- high frequency (HF) disturbances, generally ranging from 2 to 16 kHz.

This pollution can lead to downtimes caused by overloads, or inadvertent tripping of protection devices.

To reduce such disturbances, MARECHAL ELECTRIC solution consists of using metal housing devices and to associate them with metal accessories (handle, sleeve, wall box, spacer) with an adapted shielding continuity cable gland (see page 318).


The performances of this solution were measured by the Laboratoire National d'Essais (LNE - France) based on the requirements of standard ISO 11452-4.

The resulting values according to the considered frequencies are as follows:

- 0 Hz to 20 kHz (range of disturbances generated by variable speed drives): negligible input signal power losses,
- 20 kHz to 500 MHz: input signal power losses between -2 dB and -33 dB.

The solution developed by MARECHAL ELECTRIC does not negatively impact upon the declared levels of sealing, mechanical or corrosion resistance.

## SHIELDING CONTINUITY EFFICIENCY OF MARECHAL® CONNECTED DEVICES



Available ranges:

DS6 - DS9 - DS2 - DS4 - DSP400 - DSP1250 - DN9C - PN - PN7C -  
DN20C - PN12C - DS7C3 - DS7C6 - DXA1 - DX range -  
PXN12C - DXN25C - DXN37C



# OPTIONS SUFFIXES

## MAIN OPTION COMBINATION SUFFIXES

Suffix to be added to the 7 digits of standard product references.

### SOCKET-OUTLET SUFFIX

Locking	OPTION CHOICE					APPLICABLE RANGE							
	180° Opening lid	Self returning lid	2 aux.	Self ejection*	Ejection latch*	PN	DSN1 DSN3 DSN6	DS1 DS3	DS6 POLY	DS6 METAL	DS9 POLY	DS9 METAL	DS2
•						843	843	843	843	843	843	843	843
	•					10							
		•				R	R	R	R	R	R	R	R
			•				972	972	972	972	262	262	972
•						841							
•		•				858	858	858	858	858	858	858	858
•		•	•				977	977	977	977	662	662	977
•			•				372	372	372	372	213	213	372
•		•				514							
	•	•				18							
		•	•				960	960	960	960	267	267	960
		•	•	•			853	853	853	853		**	
		•	•	•	•		973	973	973	973		**	
		•		•			352	352	352	352		**	**
		•		•	•		354	354	354	354			

### PLUG SUFFIX

Locking	OPTION CHOICE		APPLICABLE RANGE								
	2 aux.	Self ejection*	PN	DSN1	DSN3 DSN6	DS1 DS3	DS6 POLY	DS6 METAL	DS9 POLY	DS9 METAL	DS2
•				843	843	843	843	843	843	843	843
	•				972	972	972	972	262	262	972
		•								**	**
•	•					372	372	372	213	213	372
	•	•								**	**

\* See chapter related to mechanical self-ejection in page 192 for more details.

\*\* Contact us.



# CABLE GLANDS



## Gray/black polyamide cable glands with flat gaskets (without locknut)

Cable entry (E)	Cable outer Ø	Thread length (H)	Reference		Additional accessory
			Gray	Black	
M16	2,5-8 mm	8 mm	9PEM16POLY+J	/	Plastic locknut
M16	4-8 mm	10 mm	/	9PEM16POLY-N	9ECM16POLY
M20	5-12 mm	10 mm	9PEM20POLY+J	9PEM20POLY-N	9ECM20POLY
M25	9-18 mm	10 mm	9PEM25POLY+J	9PEM25POLY-N	9ECM25POLY
M32	14-25 mm	15 mm	9PEM32POLY+J	9PEM32POLY-N	9ECM32POLY
M40	18-32 mm	16 mm	9PEM40POLY+J	9PEM40POLY-N	9ECM40POLY
M50	24-38 mm*	16 mm	9PEM50POLY+J	9PEM50POLY-N	9ECM50POLY
M63	35-48 mm	12 mm	9PEM63POLY+J	9PEM63POLY-N	9ECM63POLY


\* 17-38 mm the black cable glands.

## Metal (nickel plated brass) cable glands with O-rings (without locknut)

Cable entry (E)	Cable outer Ø	Thread length (H)	Reference	Additional accessory
M16	5-9 mm	5 mm	9PEM16METAL+J	Metal locknut
M20	7-13 mm	6 mm	9PEM20METAL+J	9ECM16MET
M25	8-16 mm	7 mm	9PEM25METAL+J	9ECM20MET
M32	15-24 mm	8,5 mm	9PEM32METAL+J	9ECM25MET
M40	22-32 mm	9 mm	9PEM40METAL+J	9ECM32MET
M50	34-44 mm	9 mm	9PEM50METAL+J	9ECM40MET
M63	35-48 mm	10 mm	9PEM63METAL+J	9ECM50MET
				9ECM63MET

## EMC metal cable glands with O-rings (without locknut)

Cable entry (E)	Cable outer Ø	Thread length (H)	Reference	Additional accessory
M16	5-9 mm	12 mm	9PEM16EMC	Metal locknut
M20	7-12 mm	12 mm	9PEM20EMC	9ECM16MET
M25	9-16 mm	12 mm	9PEM25EMC	9ECM20MET
M32	11-21 mm	15 mm	9PEM32EMC	9ECM25MET
M40	19-28 mm	15 mm	9PEM40EMC	9ECM32MET
M50	27-35 mm	15 mm	9PEM50EMC	9ECM40MET
M63	34-45 mm	15 mm	9PEM63EMC	9ECM50MET
				9ECM63MET



### ATEX polyamide cable glands with O-rings (without locknut)

Cable entry (E)	Cable outer Ø	Thread length (H)	Reference	Additional accessory
M16	5-10 mm	15 mm	9PEM16EX	Metal locknut
M20	10-14 mm	15 mm	9PEM20EX	9ECM16MET
M25	12-18 mm	15 mm	9PEM25EX	9ECM20MET
M32	16-25 mm	15 mm	9PEM32EX	9ECM25MET
M40	22-32 mm	16 mm	9PEM40EX	9ECM32MET
M50	28-38 mm	16 mm	9PEM50EX	9ECM40MET
M63	40-48 mm	16 mm	9PEM63EX	9ECM50MET
				9ECM63MET

### ATEX/ATEX-EMC metal cable glands with O-rings (without locknut)

Cable entry (E)	Cable outer Ø	Thread length (H)	Reference		Additional accessory
			ATEX	ATEX-EMC	
M16	5-9 mm	5 mm	9PEM16EXMET+J	9PEM16EMCEX	Metal locknut
M20	8-13 mm	6 mm	9PEM20EXMET+J	9PEM20EMCEX	9ECM16MET
M25	9-16 mm	7 mm	9PEM25EXMET+J	9PEM25EMCEX	9ECM20MET
M32	12-21 mm	8 mm	9PEM32EXMET+J	9PEM32EMCEX	9ECM25MET
M40	16-27 mm	8 mm	9PEM40EXMET+J	9PEM40EMCEX	9ECM32MET
M50	23-35 mm	9 mm	9PEM50EXMET+J	9PEM50EMCEX	9ECM40MET
M63	36-48 mm	10 mm	9PEM63EXMET+J	9PEM63EMCEX	9ECM50MET
					9ECM63MET

### ATEX metal cable glands (with grounding) + O-rings\* (without earth tag, without locknut)

Cable entry (E)	Cable outer Ø	Thread length (H)	Reference	Metal locknut	With earth tag + metal locknut
M16	6-8 mm	13 mm	9PEM16CMM1EX	9ECM16MET	9BRIDEM16EXEC
M20	8-10 mm	13 mm	9PEM20CMM1EX	9ECM20MET	9BRIDEM20EXEC
M20	10-12 mm	13 mm	9PEM20CMM1EX1	9ECM20MET	9BRIDEM20EXEC
M25	12-14 mm	14 mm	9PEM25CMM1EX	9ECM25MET	9BRIDEM25EXEC
M32	15-18 mm	14,5 mm	9PEM32CMM1EX1	9ECM32MET	9BRIDEM32EXEC
M32	18-24 mm	14,5 mm	9PEM32CMM1EX	9ECM32MET	9BRIDEM32EXEC
M40	18-24 mm	14,5 mm	9PEM40CMM1EX	9ECM40MET	9BRIDEM40EXEC

\*Contact us for cable glands for cable entries higher than M40.



## REVERSED INTERIORS

In the PN series, the interior mouldings and contacts can be swapped:

- The plug interior moulding and contacts can be assembled in a socket-outlet casing.
- The socket-outlet moulding and contacts can be assembled in plug casing.

**Suffix to be added to socket-outlet & inlet part number (P/N°):**

OPTION	PN SERIES
Reversed interior mouldings and contacts	Socket-outlet & inlet P/N° + 001

As the plug top housing becomes the live power side it is supplied with a protective cap as standard (01NA426).



Some of the products of our multicontacts range exist with reversed interior and contacts, please contact us.

## PHASE-SEQUENCE INDICATOR

The phase-sequence indicator is an accessory that provides a simple way to test if the phase sequence is correct, and the rotation direction of AC motors, from 250 to 690 V AC.

The accessory comprises either a plug fitted with a handle with LEDs which is to be mated with the socket-outlet which phase sequence is to be tested or, a plug connected with a cable to a phase sequence indicator.



Please contact us for part numbers



## VISUAL STATUS-INDICATORS

Our devices can be fitted with LEDs indicating the presence of voltage.

The LEDs are fitted on handles as follows:

- Voltage 24 V AC Ø 8 mm yellow LED
- Voltage 240 V AC Ø 8 mm red LED
- Voltage 400 V AC Ø 8 mm red LED

**Suffix to be added to handles part numbers (P/N°):**

HANDLES*	DSN1 - DSN3 - DSN6 - DS1 - DS3 - DS6 - PN
For 24 V	Standard P/N° + LY
For 240 V	Standard P/N° + LR
For 400 V	Standard P/N° + LR4

\* IP level is not guaranteed.



## INDUSTRIAL/ DOMESTIC ADAPTER

In order to allow the connection of an appliance fitted with a domestic plug to an industrial type socket-outlet, MARECHAL ELECTRIC has developed an adapter which features a MARECHAL® single phase industrial plug top at one end and a 10/16 A - 230 V domestic socket at the other end. The adapter includes a 6 x 32 mm 10/16 A fuse-link.



**Part numbers (P/N°) for these products:**

TYPE		DSN1	DSN3	DS1	PN
France	Poly	6118015D11	6138015D11	3118015D11	01N8015D11
	Metal	-	-	-	09N8015D11
United Kingdom	Poly	6118015D40	6138015D40	3118015D40	01N8015D40
	Metal	-	-	-	09N8015D40
Germany	Poly	6118015D30	6138015D30	3118015D30	01N8015D30
	Metal	-	-	-	09N8015D30
Italy	Poly	6118015D06	6138015D06	3118015D06	01N8015D06
	Metal	-	-	-	09N8015D06

Adaptation device without domestic socket is also available. Contact us for the references.




# PILOTS & AUXILIARIES

## PILOTS

A pilot circuit allows the safe remote control of a contactor by signalling confirmation that the plug is correctly inserted into the socket-outlet. The circuit must be designed so that the contactor coil cannot be energised (closing the contactor) until all downstream connections between socket-outlets (connector) and plug (appliance inlet) are correctly made - ie closed.

The contactor controls the power supply of the socket-outlet by:

- a micro switch inside the socket outlet or inlet only, which is mechanically activated when the plug is connected,
- a contact or pair of normally open contacts on the male and female sides which close last and open first used as part of the external control circuit.



Some of our products feature pilot contacts as standard.

SP series



PF series  
Up to 6 auxiliaries (and 2 pilot contacts)




DS4 series





## AUXILIARY CONTACTS

Auxiliary contacts on the male and female sides are separate from the main power contacts. These contacts can be used for signal and control requirements.




For suffix references to add auxiliary contacts to the socket outlet and inlet part numbers please refer to the option suffixes section.

## SEQUENCING BETWEEN AUXILIARY CONTACTS AND POWER CONTACTS

To ensure optimum performance, DECONTACTOR™ contacts are sequenced in the following order on insertion of the plug:

### In order:

- ① the earth contact closes first,
- ② then the neutral contact,
- ③ then the phase contacts,
- ④ and last the auxiliary contacts which can be used as pilot contacts.



This design ensures no arcing at connection and disconnection.

# SPARE PARTS



## PLUG

	PN POLY	PN METAL
① Plug interior	01NA010	09NA110
② Locking ring	611A583	09NA583
③ Plug contact (P or N)	01NA011	01NA011
④ Color-coded voltage gasket	611AV26	611AV26
	611AB26	611AB26
	611AR26	611AR26
	611AN26	611AN26
⑤ Plug casing	01NA501	09NA501



## SOCKET

	PN POLY	PN METAL
① Socket Interior 3P+E	01NA020C3	09NA220C3
① Socket Interior 1P+N+E	01NA020C5	09NA220C5
① Socket Interior 3P+N+E	01NA020C7	09NA220C7
② Locking ring	611A583	09NA583
③ Socket contact	01NA021	01NA021
④ Color-coded voltage gasket	611AV26	611AV26
	611AB26	611AB26
	611AR26	611AR26
	611AN26	611AN26
⑤ Socket Lid Gasket	01NA524*	09NA524*
⑥ Casing gasket	01NA074	01NA074

\*Add suffix cover option (opening 180 °, self-returning, etc.).



### REMEMBER TO ORDER THE SPECIAL REMOVAL KEY

Yellow disassembly key for poly casing  
31-A500-1



CONTACT US FOR SPARE PARTS.



PLUG	DSN1	DSN3	DSN6
① Plug interior	611A010	311A010	313A010
② Locking ring	611A583	311A583	616A583
③ Plug contact	611A011	311A011	616A011
④ Color-coded voltage gasket	611AB26 611AR26 611AV26 611AN26	613AB26 613AR26 613AV26 613AN26	313AB26 313AR26 313AV26 313AN26
⑤ Plug casing	611A501	613A501	616A501



SOCKET	DSN1	DSN3	DSN6
① Socket Interior	611A020	311A020	313A020
② Locking ring	611A583	311A583	616A583
③ Socket contact	611A021	311A021	616A021
④ Color-coded voltage gasket	611AB26 611AR26 611AV26 611AN26	613AB26 613AR26 613AV26 613AN26	313AB26 313AR26 313AV26 313AN26
⑤ Socket Casing	611A524*	613A524*	616A524*
⑥ Casing gasket	611A074	613A074	616A074

\*Add suffix cover option (opening 180 °, self-returning, etc.).



#### REMEMBER TO ORDER THE SPECIAL

#### REMOVAL KEY

Yellow disassembly key for poly casing

31-A500-1



CONTACT US FOR SPARE PARTS.

# SPARE PARTS



②

①

③

①

④

⑤

<b>PLUG</b>	<b>DS1</b>	<b>DS3</b>	<b>DS6</b>	<b>DS9</b>	<b>DS2</b>	<b>DS4</b>
① Plug interior	311A010	313A010	316A010	619A010	-	-
① Plug interior metal + E	-	-	396A110	699A110	392A110	394A110
② Locking ring	311A583	616A583	316A583	319A583	-	-
② Locking ring metal	-	-	396A583	399A583	392A583	394A583
③ Plug contact (P or N)	311A011	616A011	316A011	619A011	392A011	394A011
④ Color-coded voltage gasket	311AB26 311AR26 311AV26 311AN26	313AB26 313AR26 313AV26 313AN26	316AB26 316AR26 - 316AN26	319AB26 319AR26 - 319AN26	392AB26 392AR26 - 392AN26	- - - -
⑤ Plug casing poly	311A501	313A501	316A501	619A501	-	-
⑤ Plug casing metal	-	-	396A501	399A501	392A501	394A501



REMEMBER TO ORDER THE SPECIAL  
REMOVAL KEY

Yellow disassembly key for poly casing  
31-A500-1





<b>SOCKET</b>	<b>DS1</b>	<b>DS3</b>	<b>DS6</b>	<b>DS9</b>	<b>DS2</b>	<b>DS4</b>
① Socket Interior poly	311A020	313A020	316A020	619A020	-	-
① Socket Interior metal +E			396A220	699A220	392A220	394A220
② Locking ring	311A583	616A583	316A583	319A583	-	-
② Locking ring metal	-	-	396A583	399A583	392A583	394A583
③ Socket contact (P or N)	311A021	616A021	316A021	619A021	392A021	394A021
④ Color-coded voltage gasket	311AB26	313AB26	316AB26	319AB26	392AB26	-
	311AR26	313AR26	316AR26	319AR26	392AR26	-
	311AV26	313AV26	-	-	-	-
	311AN26	313AN26	316AN26	319AN26	392AN26	-
⑤ GRP socket casing	311A524*	313A524*	316A524*	619A524*	-	-
⑤ Metal socket casing	-	-	396A524*	399A524*	392A524*	394A524*
⑥ Lid gasket	311A563 (lid)	313A563 (lid)	396A074 (casing)	399A074 (metal) 619A074 (poly) (casing)	392A074 (casing)	392A074 (casing)

\*Add suffix cover option (opening 180 °, self-returning, etc.).

**CONTACT US FOR SPARE PARTS.**

# SPARE PARTS



1


5

6

7

**PLUG****PFQ**

① Plug interior (with auxiliary contacts)	473A310
② Phase contact	474A011
③ Neutral contact	474A011L
④ Earth contact	474A019
⑤ Internal gasket	473A074
⑥ Plug casing (with internal and external gaskets)	473A014
⑦ External gasket	474A026



1

2

3

4

8


9

**SOCKET****PFQ**

① Cap (with gasket)	474A925
② Cap gasket	474A563
③ Socket interior (with auxiliaries)	473A320
④ Insulator block for Auxs and Pilots (includes contacts)	473A229
⑤ Phase contact	474A021
⑥ Neutral contact	474A021L
⑦ Earth contact	474A029
⑧ Socket casing (with gasket and cap)	473A024
⑨ External gasket	474A026

**PLUG**

	PFC
① Plug interior (with auxiliary contacts)	496A310
② Phase contact	496A011
③ Neutral contact	496A011N
④ Earth contact	496A019
⑤ Internal gasket	494A074
⑥ Plug casing (with internal and external gaskets)	494A014
⑦ External gasket	494A026

**SOCKET**

	PFC
① Socket cap (with gasket)	496A925
② Cap gasket	494A074
③ Socket interior (with auxiliary contacts)	496A320
④ Insulator block for Auxs and Pilots (includes contacts)	494A229
⑤ Phase contact	496A021
⑥ Neutral contact	496A021N
⑦ Earth contact	496A029
⑧ Socket casing (with gasket and cap)	494A024
⑨ External gasket	494A026



# NOTES



# NOTES



# NOTES



# NOTES



# NOTES



# NOTES



# NOTES



# NOTES

## WEBSITE

- Configure your product specification with our online configurator: [marechal.com/configurator](http://marechal.com/configurator)
- Retrieve your business contacts.
- Download our documentation related to your field of activity.
- Download our product data sheets.
- Follow current events and news.

### NON CONTRACTUAL DOCUMENT AND PICTURES

All the indications appearing in this catalogue are indicative and could not constitute a commitment on our part.

We reserve the right to alter specifications of our products without any prior notice in our efforts to continuously improve our products features.

Please note: The most up to date versions of our products can be found on our website [marechal.com](http://marechal.com).


FIND ALL INFORMATION  
ON OUR WEBSITE:  
[marechal.com](http://marechal.com)





## THE FIRST SEPARABLE SWITCH- DISCONNECTOR

- Complies with the low voltage directive
- Up to 40 A and 18,5 kW
  - Up to 6 poles + earth
- IP66/IP67/IP69 automatic waterproofing in ON and OFF positions



[marechal.com](http://marechal.com)

 **MARECHAL**  
ELECTRIC  
BEYOND CONNECTIONS



THORNE &  
**DERRICK**  
INTERNATIONAL

Thorne & Derrick  
+44 (0) 191 410 4292  
[www.powerandcables.com](http://www.powerandcables.com)

## WORLD PRESENCE

